



NOTES

GENERAL

1.

All dimensions are in metres unless noted otherwise

2.

DO NOT SCALE THIS DRAWING - If in doubt ask

3.

All dimensions & levels to be checked by the Contractor prior to commencement of work, any discrepancy shall be reported immediately to the Engineer.

4.

Underground services are present in the area. Contractor is to confirm the precise line and depth of any services prior to the commencement of any excavation works.

5.

All work shall be carried out in accordance with Local Authority, Statutory Authority, Health & Safety requirements and regulations.

6.

The drawings shall be read in accordance with all other contract documents relevant at that time of issue and during the period of the contract.

7.

The Contractor must ensure the overall stability of the works is adequate at all stages of the construction.

8.

All chamber covers, valve boxes etc., situated within the works to be raised/lowered to match proposed levels where necessary.

9.

All setting out shall be agreed on site with the overseeing organisation.

10.

All works are to be in accordance with the North Yorkshire Council design guide for Highways & Transport and the Specification for Highway Works.

Vehicle Profile

Phoenix 2-25W (with Volvo FM12 chassis)
Overall Length 11.125m
Overall Width 2.550m
Overall Body Height 3.250m
Min Body Ground Clearance 0.410m
Track Width 2.500m
Lock to lock time 4.00s
Kerb to Kerb Turning Radius 9.250m

PO	Primary - Initial Issue	RD
REV	DESCRIPTION	DATE BY
 Project: Blackmoorfoot Road, Huddersfield		
Client: Vistry Yorkshire		
Drawing: Section 278 Works Swept path analysis		
Drawn By: RID	Date: 30/07/2024	
Checked: GDM	Scale: 1:250	A1
Drawing No: AMA/22224/D/101 - 2.2	Rev: P0	