

Do not scale from this drawing. Northlight Architectural Consultants Ltd must be notified immediately should any discrepancies be found. The contractor must check all dimensions on site before construction or manufacture of materials. This drawing or any portion of it may not be reproduced without the consent of Northlight Architectural Consultants Ltd.

NOTE: DRAWING PRODUCED FROM THIRD PARTY INFORMATION. DO NOT SCALE FROM THIS DOCUMENT. ALL DIMENSIONS TO BE CHECK ON SITE.



2 SITE LOCATION PLAN  
SCALE 1:1250

GENERAL KEY

- Existing ground level to be maintained
- Proposed new ground/ floor level

LANDSCAPING KEY

- Proposed bitumen macadam (permeable)
- Existing hardstanding access road widened to match
- Proposed slab paving patios
- Proposed turfed/ soft landscaped areas
- Root protection areas in accordance with Arboriculturalist's specification

ENCLOSURES/ FEATURES KEY

- 1.8m overall high timber hit and miss fence and trellis with 1.8m wide lockable timber gate
- Proposed natural stone walling
- Proposed electric vehicle charging point

DRAINAGE KEY

- Proposed below ground foul drainage pipework
- Proposed below ground surface water drainage pipework

Revisions

**NORTHLIGHT**  
ARCHITECTURAL CONSULTANTS

The Media Centre  
7 Northumberland Street  
Huddersfield  
HD1 1RL  
1: 07815 290496  
e: chris@northlight@gmail.com

Client  
**Longwood**

Project  
**Land at Occupation Lane  
off Birky Road, Birky  
Huddersfield, HD2 2ES**

Drawing No:  
**Site Plan as Proposed**

PLANNING APPLICATION

Scale: @ A0	Drawn by:
1:200	CG
Date:	App'd:
July '24	-
Drawing No:	Rev:
24.002/(AL)01	-

GENERAL SPECIFICATION FOR INITIAL ESTABLISHMENT AND MAINTENANCE OF PLANTED AREAS.

**Preparation:**  
Prior to planting, shrub beds shall be forked, dug, hoed and stone picked to create a smooth, even surface free from weeds, stones greater than 50mm in any dimension or other deleterious material. Any perennial weed shall be removed including the roots. If necessary an approved herbicide shall be applied to manufacturer's instructions.

**1st Season Maintenance:**  
Following planting all areas of new shrub planting shall be mulched with coarse grade bark to a minimum settled depth of 75mm during moist ground conditions. Shrub beds shall be kept clear of all weeds by either mechanical or chemical control during the first growing season after planting. Edges of shrub beds that abut grassed areas shall be kept tidy by regular edging at the time of grass cutting.

**Long term Maintenance**  
Bark mulch shall be topped up as necessary at the start of each growing season to maintain a minimum settled depth of 75mm. Such mulching shall only be done once the beds are weed-free. Weeding shall be carried out as necessary during the growing season to keep beds in a tidy condition. Edges of shrub beds shall be kept clipped as above. Pruning of shrubs shall be carried out as appropriate to maintain shape, flower and vigour.

**Turfing**  
Soil to be prepared with all stones removed. Surface to be lightly scarified and graded to slope evenly where gradients necessary. Supply, lay and bed imported turf to be sourced from an Approved landscape turf supplier (Turf should be in accordance with the specifications given in BS 3969, and laid in accordance with BS 4428:1989, Section 6).

**EXISTING BORDERS AND NEW PLANTING**  
**Existing Borders:**  
To provide maturity to the garden where possible existing mature shrubs will be retained and any areas requiring infill will be supplemented with the addition of Pachysandra, Hebe, Vinca, Euonymus, Genista etc.

**New Planting:**  
New planting to include a mix of native species: - Malus x domestica (Apple) Prunus avium (Wild Cherry) Pyrus communis (Pear) Corylus avellana (Hazel) Crataegus monogyna (Hawthorn) Ilex aquilinum (Holly) Prunus spinosa (Blackthorn) Sorbus aucuparia (Rowan/Mountain Ash).  
To soften the base of the new house at the edge of the drive and pathway use Buxus microphylla 'Faulkner' (Small-Leaved Boxwood), Calluna vulgaris 'Spring Torch' (Heather), Cornus sanguinea 'Anny's Winter Orange' (Bloodwing Dogwood), Carex pseudocyperus (Sedge Hop), Dryopteris affinis (Golden Male Fern) etc.  
To be planted in spring following completion of development and to be maintained thereafter.

HEDGES AND THEIR PROTECTION DURING THE CONSTRUCTION PHASE

**Hedging:**  
In the interests of providing effective screening and to attract wildlife new boundary hedges of beech, hawthorn, holly, privet and hazel will be provided.

**Construction Phase Protection**  
During the construction phase the existing hedges and existing trees are to be protected by means of barriers that offer full protection to the trees and hedges and their root systems (contractors responsibility)



1 SITE PLAN AS PROPOSED  
SCALE 1:200