



DB32 FIRE APPLIANCE	
OVERALL LENGTH	8.680m
OVERALL WIDTH	2.180m
OVERALL BODY HEIGHT	3.452m
MIN BODY GROUND CLEARANCE	0.337m
MAX TRACK WIDTH	2.121m
LOCK TO LOCK TIME	6.00s
KERB TO KERB TURNING RADIUS	7.910m

REV.	AMENDMENTS	DATE
-	-	-



VIASOLUTIONS

THE OLD COACH HOUSE
1 CAMPBELL STREET
PUDSEY
LS28 6DP
tel: 0113 3453957
email: highwaymen@viasolutions.co.uk

PROPOSED DEVELOPMENT

POPELEY FARM, MUFFIT LANE,
GOMERSAL

FIRE TENDER SWEEP PATH ANALYSIS

NOTES

1.  BIN STORE TO BE PROVIDED BEHIND PUBLIC HIGHWAY LIMITS (WALL TO BE SET BACK IF REQUIRED) – MAXIMUM OF 8m FROM ROAD EDGE.
2. ACCESS TO BE WIDENED TO A MINIMUM WIDTH OF 3.7m IN ACCORDANCE WITH "THE BUILDING REGULATIONS (2010) APPROVED DOCUMENT B: FIRE SAFETY" TO ALLOW SUITABLE ACCESS FOR FIRE TENDER
3. ORDNANCE SURVEY (C) CROWN COPYRIGHT 2023. ALL RIGHTS RESERVED. LICENCE NUMBER 1000224323

SCALE: 1:1000 @A3

DATE: NOVEMBER 2024

DRAWING NO: 2301703

STATUS: - REVISION: -