

## Spatial Requirements

The following Table sets out the spatial requirements of a dry grain storage barn for the holding:

Dry Crop Store Requirments			
Tonage	Crop	Space	Notes
800	wheat	1016	1.27m <sup>3</sup> = 1tonne
150	Barley	210	1.4 m <sup>3</sup> = 1tonne
175	Oats	297.5	1.7 m <sup>3</sup> = 1tonne
120	Oil Rape Seed	204	1.7m <sup>3</sup> = 1 tonne
		<b>1727.5</b>	<b>m<sup>3</sup></b>
		<b>431.875</b>	<b>m<sup>2</sup></b>
Stored to 4m to allow air flow			
Misc			
Space between Grain Piles & Acces/ Manouvering e		<b>20</b>	<b>m<sup>2</sup></b>
<b>Total Minimum Suggested Size</b>		<b>451.875</b>	<b>m<sup>2</sup></b>