



Sanitary / Soil and Vent Pipes:

110mm diameter PVC-u soil and vent pipes to Bs 5572

Waste connections to discharge into soil vent pipe minimum 200mm below any W.C. connection.

All waste fittings to have 75mm deep seal traps and separate connections to SVP's and to be installed in accordance with BS 5572.

All traps are to be fitted directly adjacent the sanitary item and is to be removable for access.

Waste pipes to be proprietary PVC-u with diameters as listed below.

Wash-Hand Basins to be 32mm diameter for runs not exceeding 1700mm and 40mm diameter for runs up to a maximum of 3000mm in length.

Include rodding eyes at change of direction as appropriate

Rev	Amendment	Drawn	Date	Checked

Project Name
Hall Bower Athletic Club
 533 Hall Bower
 Huddersfield
 HD4 6RR

Drawing Title
Proposed Alterations

Scale	1:50	Drawn By	
Drawing Size	A3	Checked By	
Date	Oct 2024	Approved By	

Drawing Number	HBC-002	Rev	
----------------	---------	-----	--