



**NOTES**

1. This drawing is to be read in conjunction with all relevant architect's and engineer's drawings.
2. It is assumed that all works will be carried out by a competent contractor working, where appropriate, to an approved method

**KEY**

- Existing Kerbing to be removed and disposed of off site
- Existing stone wall to be dismantled and disposed of off site
- BS Existing bus stop to be relocated
- Extent of road markings to be removed w/ Hydroblasting  
Existing road studs to be removed and carriageway reinstated

Primary - Initial Issue	10/02/23	AJA
REV	DESCRIPTION	DATE BY
Project: FENAY BRIDGE		
Client: NEWETT HOMES		
Drawing: S278 WORKS SITE CLEARANCE		
Drawn By: AJA	Date: MAY 2023	
Checked: GS	Scale: 1:200	A1
Drawing No: AMA/21312/D/200		Rev: -