

**ARBORICULTURAL IMPACT ASSESSMENT  
to BS 5837:2012  
at  
Land adjacent to Forge Lane  
Dewsbury  
West Yorkshire  
WF12 9EX**

**Client:**  
Hebble Homes Ltd

**Client Address:**  
Ewood  
Langbar Road  
Ilkley  
LS29 0AR

**JCA Ref:**  
22374b/LW

## Contents

<b>1. Introduction</b>	<b>3</b>
1.1 Purpose of the Report	3
1.2 Terms of Reference	3
1.3 Scope of the Report	3
1.4 Survey Details	3
<b>2. Tree Descriptions and Recommendations</b>	<b>4</b>
<b>3. Arboricultural Implications Assessment (AIA)</b>	<b>5</b>
3.1 Proposed Development	5
3.2 Tree Removals for Development	5
3.3 Pruning for Development	5
3.4 Temporary Protection Measures	5
3.5 Implications for Retained Trees	6
3.6 Remedial Measures	7
<b>4. Summary</b>	<b>8</b>
<b>Appendix 1: Tree Descriptions and Recommendations</b>	<b>10</b>
<b>Appendix 2: Explanation of Tree Descriptions</b>	<b>11</b>
<b>Appendix 3: General Guidelines</b>	<b>13</b>
<b>Appendix 4: Author Qualifications</b>	<b>14</b>
<b>Appendix 5: Tree Constraints Plan</b>	<b>15</b>
<b>Appendix 6: Arboricultural Implications Plan</b>	<b>16</b>

## 1. Introduction

### 1.1 Purpose of the Report

- 1.1.1 This Arboricultural Impact Assessment has been prepared for the proposed development of **Land adjacent to Forge Lane, WF12 9EX**.
- 1.1.2 The purpose of this report is to assess the impact of the proposed development on the existing tree stock and outline mitigation actions, where appropriate, to minimise any potential damage to retained trees.

### 1.2 Terms of Reference

- 1.2.1 JCA Limited has been instructed by **Hebble Homes Ltd** to prepare an Arboricultural Impact Assessment, based on our Arboricultural Report dated 8<sup>th</sup> November 2024 (JCA Ref: **22374a/LW**). The arboricultural survey and report conform to the most recent specifications outlined in BS 5837: 2012 Trees in relation to design, demolition and construction - Recommendations.
- 1.2.2 We have been supplied with Drawing No. **2776 Forge Lane main v2025**, which details the proposed development. The tree data has been overlaid onto the proposed designs to create the Arboricultural Implications Plan, which can be found at **Appendix 6**. This provides the basis for which this Arboricultural Impact Assessment has been prepared.

### 1.3 Scope of the Report

- 1.3.1 This report is compiled in accordance with *BS 5837:2012 'Trees in relation to design, demolition and construction – Recommendations'* and is based on an objective assessment of the existing vegetation.
- 1.3.2 The specific design of the proposed development has been considered within the Arboricultural Implication Assessment in **Section 3** and is detailed on the Arboricultural Implications Plan at **Appendix 6**.

### 1.4 Survey Details

- 1.4.1 The original tree survey took place during November 2024 and was conducted by **Luke Wickham FdSc (Arboriculture and Urban Forestry)**, LANTRA Accredited PTI, MArborA.

## **2. Tree Descriptions and Recommendations**

- 2.1 The tree information recorded during the original survey is detailed in the tables at **Appendix 1**. A full explanation of the tables can be found at **Appendix 2**. Please refer also to the Tree Constraints Plan at **Appendix 5** for tree locations.

### 3. Arboricultural Implications Assessment (AIA)

#### 3.1 Proposed Development

- 3.1.1 The proposed development will consist of the construction of 2 industrial units, car-parking, access roads and associated hard standings.
- 3.1.2 Any tree works required to accommodate the proposals are detailed in the 'Development Impacts' column of the table at **Appendix 1**. Please note that any required Arboricultural works recommended during the initial survey are also listed in this table.

#### 3.2 Tree Removals for Development

- 3.2.1 There is little room for development within this site without the removal of some trees. However the trees requiring removal are of lower quality (retention category 'C') and can be removed without significantly affecting the visual amenity of the surrounding area.
- 3.2.2 **3** groups of trees (**G8, G9** and **G10**), and parts of **5** groups of trees (**G3, G4, G5, G6** and **G7**) require removal to accommodate the proposals.
- 3.2.3 Whilst the development will require the removal of some trees within the site, it should be noted that a planting scheme is included within the proposals. This will act to mitigate tree losses, improve the visual benefits of the site and the surrounding area, and will improve the localised tree stock.

#### 3.3 Pruning for Development

- 3.3.1 No pruning works are required to accommodate the proposed layout.

#### 3.4 Temporary Protection Measures

##### 3.4.3 The Protective Barrier

- 3.4.3.1 In order to ensure the effective protection of retained trees during development, a protective barrier will be installed, in accordance with BS5837: 2012 and may comprise of protective fencing and/or ground protection. The fencing should ideally be positioned to protect the entire **Root Protection Area (RPA)** of the retained trees, in order to create a **Construction Exclusion Zone (CEZ)**.
- 3.4.3.2 Routes for pedestrian and site traffic will be located outside, and diverted away from, the RPAs of the retained trees wherever possible. Where this is not practicable, temporary protective surfaces (ground protection) must be laid over the exposed RPAs which will distribute the weight of site vehicles, machinery or pedestrians whilst allowing moisture to reach the tree rooting area beneath. Such surfaces should be constructed in accordance with BS5837: 2012.

## **3.5 Implications for Retained Trees**

### **3.5.1 Demolition**

3.5.1.1 In this case, no significant demolition activities are required adjacent to retained trees and as such, no mitigation measures are considered necessary.

### **3.5.2 Access/Construction of Hard Surfacing**

3.5.2.1 The proposed development entails the construction of hard surfacing within the retained RPAs of **G7**. This takes the form of a footpath. In order to prevent foreseeable damage to tree roots, a 'no-dig' method of construction will be utilised.

3.5.2.2 The chosen system must be fit for purpose and of suitable construction to dissipate compaction damage to tree roots, allow gaseous diffusion to/from the soil and the percolation of water to the soil surface. This may require the use of specialist materials and sensitive edging systems to prevent damage to tree roots. It is recommended that this surfacing be constructed as a final phase of construction, in order to afford the maximum protection throughout development.

3.5.2.3 Design principles must be confirmed by an appropriately qualified engineer and should be included in an Arboricultural Method Statement.

### **3.5.3 Building Construction / Foundation Design**

3.5.3.1 The footprints of the proposed structures do not incur the RPA of retained trees. As such no specialist construction or foundation methods are considered necessary for the sole purpose of preventing damage to trees.

3.5.3.2 Despite this, specialist foundation designs may still be required for other reasons, and advice should always be sought from a suitably qualified structural expert. The water demand of trees can be an important consideration when determining the appropriate foundation design. Because of this, water demands for the trees identified on this site are included at **Appendix 1**, in accordance with **NHBC Standards**, for use by the appointed structural expert.

### **3.5.4 Utilities**

3.5.4.1 Details on service routes have not been provided to JCA at this time. Where utilities need to be brought onto the site, these should be routed away from the RPAs of retained trees. Where this is not possible, methodologies on the installation of underground services without damage to tree roots should be considered.

3.5.4.2 All service providers should be consulted prior to commencement of works with the aim of minimising the number of service runs on the site. Any foreseeable incursions to RPAs should be communicated to the appointed arboricultural consultant and the LPA at the earliest possible time to prevent breach of planning conditions and damage to retained trees.

### 3.5.5 **Site Compound**

3.5.5.1 The site compound, which typically includes the site office, mess facilities, toilets, storage of materials and parking, must be located away from all of the trees and outside their RPAs. Care should also be taken to prevent soil contamination from chemical spillages, including petrol, diesel and oils.

### 3.5.6 **Landscaping**

3.5.6.1 Proposed fence lines may be constructed within the RPA of a tree if necessary, providing that appropriate considerations are taken with regards to the well-being of the effected tree. As such, no continual trenching is to be undertaken within the RPA (e.g. for small walls onto which panel fencing is installed). Excavations must be kept to a minimum and therefore only fence designs requiring intermittent posts will be acceptable within the RPA. Fences should also be kept as far away from the main stems of the trees as is reasonably possible.

## **3.6 Remedial Measures**

3.6.1 In order to protect the retained trees during the construction phase, protective fencing needs to be installed. Protective fencing specifications and on site positioning, along with details of any necessary specialist construction methods can be provided in an Arboricultural Method Statement (AMS).

3.6.2 Part of the proposed development will encroach into the RPAs of retained trees, resulting in possible root loss. It would therefore be prudent to apply appropriate mycorrhizae fungi to the soils around these trees after the construction phase is complete. Certain mycorrhiza fungi form a symbiotic relationship with tree roots. A tree root associated with such mycorrhiza will take up nutrients more effectively and this will therefore help the tree to produce new roots more effectively, so benefitting their recovery.

3.6.3 The site offers scope for landscaping and tree planting. All areas identified for the new planting should also be protected by fencing during the construction phase to prevent the compaction of the soil.

## 4. Summary

- 4.1 Some tree works were recommended during the original survey, irrespective of the development proposals. This is to manage potential risks or for general maintenance purposes. These are detailed in **non-italics** in the tables at **Appendix 1**.
- 4.2 It is proposed to construct 2 industrial units, car-parking, access roads and associated hard standings.
- 4.3 The arboricultural implications of the development have been considered and are discussed in **Section 3**.
- 4.4 Some trees require removal or pruning works in order to facilitate the proposed development. Tree works required to accommodate the proposals are detailed in **italics** in the tables at **Appendix 1**. Those trees requiring removal are shown in red on the Arboricultural Implications Plan at **Appendix 6**, where the proposals can also be viewed.
- 4.5 All development work carried out in close proximity to trees should be done so in a manner sympathetic to their needs. Otherwise the condition of the trees may deteriorate in the months and years following the development, leading to a loss of amenity and potentially hazardous trees.
- 4.6 The protection of retained trees can be achieved by the creation of a Construction Exclusion Zone based on the Root Protection Area of a tree. The Root Protection Area of each tree or group is marked on the Tree Constraints Plan at **Appendix 5**.
- 4.7 The proposed development should be accompanied by an Arboricultural Method Statement (AMS) detailing the specific protection measures necessary for each tree. This should specify the required fencing standard and positions (the creation of the Construction Exclusion Zone), acceptable construction techniques and necessary tree works.
- 4.8 The data gained during the original survey provides an indication of the health of the trees. However, it does not enable a comprehensive assessment of their condition over time. Trees are living organisms which are affected by many factors including weather conditions, diseases/disorders, light levels and human activities. Due to this, the report is only valid for a period of 1 year from the date of issuing. Should an update or revision of this report be required outside of this time period, JCA may require a further site visit to ensure that the condition of the trees has not significantly changed. It is advised that the trees are inspected regularly, in the interests of risk management.

# Appendices

Tree Ref.	Age Common Name Botanical Name	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread			Observations	Recommendations Priority	Development Impacts	Physiological Condition	Structural Condition	Amenity Value	NHBC Water Demand	Life Expectancy (yrs)	Retention Category
					N	W	E									
T 1	Mature Crack Willow <i>Salix fragilis</i>	18	0+	50, 55, 55, 60, 70 #	7	5	7	Limited inspection due to access and surrounding vegetation, surveyed from road side. Multi-stemmed from ground level, multiple limb failures and deadwood throughout.	No action required at present.  n/a	No action required.	FAIR	POOR	LOW	HIGH	20+	1 C 2
T 2	Mature Ash <i>Fraxinus excelsior</i>	22	2 #	75 #	8	7	7	Limited inspection due to access and surrounding vegetation, surveyed from road side. Early signs of Ash Dieback ( <i>Hymenoscyphus fraxineus</i> ).	Monitor annually due to proximity to Forge Lane  Moderate	No action required.	FAIR	GOOD	MOD	MOD	10+	1 C 2
G 3	Young to Early-mature Mixed species <i>Details in Observations</i>	to 20	0+	from 75 to 600 #	See plan			Group of self-seeded pioneer species bordering Forge Lane. Species include Silver Birch and Willow with the occasional Rowan and Oak. Sporadic bird boxes noted on trees.	No action required at present  n/a	Partial removal as displayed at <b>Appendix 6</b> , to accommodate the proposed scheme.	GOOD	GOOD	MOD	LOW to HIGH	40+	1 C 2
G 4	Young to Early-mature Mixed species <i>Details in Observations</i>	to 20	0+	from 75 to 400 #	See plan			Situated adjacent to the canal, a group of self-seeded pioneer species consisting of Silver Birch and Willow with the occasional Rowan and Oak.	No action required at present  n/a	Partial removal as displayed at <b>Appendix 6</b> , to accommodate the proposed scheme.	GOOD	GOOD	MOD	LOW to HIGH	40+	1 C 2
G 5	Young to Early-mature Mixed species <i>Details in Observations</i>	to 16	0+	from 75 to 300 #	See plan			Limited inspection due to access and dense undergrowth. Group of pioneer species including Birch, Willow and Rowan, with infrequent Dog Rose and Oak.	No action required at present  n/a	Partial removal as displayed at <b>Appendix 6</b> , to accommodate the proposed scheme.	GOOD	GOOD	MOD	LOW to HIGH	40+	1 C 2
G 6	Young to Early-mature Mixed species <i>Details in Observations</i>	To 18	0+	from 75 to 400 #	See plan			Limited inspection due to access. Predominantly Silver Birch with the occasional Oak, Holly and Willow. Occasional wind-blown Willow.	No action required at present  n/a	Partial removal as displayed at <b>Appendix 6</b> , to accommodate the proposed scheme.	GOOD	GOOD	MOD	LOW to HIGH	40+	1 C 2
G 7	Young to Early-mature Mixed species <i>Details in Observations</i>	To 20	0+	from 75 to 350 #	See plan			Inspection limited from canal banking. Predominantly Silver Birch with patches of Fern towards the waterside.	No action required at present  n/a	Partial removal as displayed at <b>Appendix 6</b> , to accommodate the proposed scheme.  'No-Dig' techniques required.	GOOD	GOOD	MOD	LOW	40+	1 C 2
G 8	Young to Early-mature Mixed species <i>Details in Observations</i>	To 15	0+	from 75 to 350 #	See plan			Limited inspection due to dense undergrowth. Group of pioneer species including Birch, Willow and Rowan, with infrequent Dog Rose and Oak.	No action required at present  n/a	Remove to accommodate the proposed scheme.	GOOD	GOOD	MOD	LOW to HIGH	40+	1 C 2
G 9	Young to Early-mature Mixed species <i>Details in Observations</i>	To 15	0+	from 75 to 350 #	See plan			Group of pioneer species predominantly consisting of Birch, Willow and Rowan.	No action required at present  n/a	Remove to accommodate the proposed scheme.	GOOD	GOOD	MOD	LOW to HIGH	40+	1 C 2
G 10	Young to Semi-mature Mixed species <i>Details in Observations</i>	to 12 #	0+	from 75 to 150 #	See plan			Sporadic patches of vegetation consisting of Dog Rose and Willow.	No action required at present  n/a	Remove to accommodate the proposed scheme.	GOOD	GOOD	LOW	HIGH	40+	1 C 2

## Appendix 2: Explanation of Tree Descriptions

### A2.1 Measurements/ Reference Information

A2.1.1 *REF NUMBER*. All items surveyed are allocated a reference number preceded with a letter, identifying the type of vegetation surveyed: T = an individual tree, G = a group of trees or an area of vegetation, W = woodland, H = a hedgerow.

A2.1.2 *SPECIES: COMMON AND BOTANICAL NAME*. The common and botanical names of the species present are noted. If the species is not clear or identifiable, then a general common name and genus will be noted.

A2.1.3 *AGE CLASS* of the tree is described as young, semi-mature, early-mature, mature, over-mature, veteran or dead.

A2.1.4 *HEIGHT* of the tree is measured in metres from the stem base to the top of the crown.

A2.1.5 *CROWN HEIGHT* is an indication of the height above ground level at which the crown begins.

A2.1.6 *STEM DIAMETER* is measured at 1.5 metres above (higher) ground level. Where the tree is multi-stemmed at this point; diameter measurements are taken for each stem. If more than five stems are present, an average stem diameter is taken. If for whatever reason it is not practical to measure multiple-stemmed trees in this way, the diameter is measured close to ground level, just above the root buttress.

A2.1.7 *CROWN SPREAD* is measured from the centre of the stem base to the tips of the branches to all four cardinal points.

A2.1.8 *HEIGHT AND DIRECTION OF LOWEST BRANCH*. The height and direction of the lowest significant branch is noted because of potential issues relating to clearances and the need for tree pruning.

A2.1.9 *NHBC WATER DEMAND*. The water demand of each tree is listed in accordance with current NHBC Standards. This is included to aid structural engineers, architects and other members of the design team as it determines foundation depth and other considerations with regard to trees.

### A2.2 Evaluations

A2.2.1 *PHYSIOLOGICAL CONDITION* is classed as good, fair, poor, or dead. This is an indication of the health and vitality of the tree and takes into account vigour, presence of disease and dieback.

A2.2.2 *STRUCTURAL CONDITION* is classed as good, fair or poor. This is an indication of the structural integrity of the tree and takes into account significant wounds, decay and quality of branch junctions.

A2.2.3 **LIFE EXPECTANCY** is classed as; 0, less than 10 years, 10+ years, 20+ years, or 40 + years. This is an indication of the minimum number of years before removal of the tree is likely to be required.

A2.2.4 **AMENITY VALUE**. A general indication is given in respect to the amenity/landscape value of the tree/group within the surrounding area.

A2.2.5 **PRIORITIES**. A priority rating is given concerning the time periods in which the recommended works should be undertaken. LOW priority works should be undertaken within 12 months of the survey, MOD (moderate) priority works should be undertaken within 6 months and HIGH priority works should be completed as soon as practically possible. If no works are recommended, N/A (not applicable) will be used.

### **A2.3 Retention Categories**

A2.3.1 **A (marked green on the Tree Constraints Plan) = Trees of high quality.**

These trees are of high quality and value with a good life expectancy (usually with an estimated remaining life expectancy of 40 years).

A2.3.2 **B (marked in blue on the Tree Constraints Plan) = Trees of moderate quality.**

These trees are of moderate quality and value with a reasonable life expectancy (usually with an estimated life expectancy of at least 20 years).

A2.3.3 **C (marked in grey on the Tree Constraints Plan) = Trees of low quality.**

These trees are of low quality and value but which are in adequate condition to remain or are young trees with a stem diameter below 15cm (usually with an estimated life expectancy of at least 10 years).

A2.3.4 Trees categorised as retention category 'A', 'B' or 'C' are then justified by being further divided into 3 subcategories:

1 = Mainly arboricultural qualities.

2 = Mainly landscape qualities.

3 = Mainly cultural values, including conservation value.

A2.3.5 **U (marked in red on the Tree Constraints Plan) = Trees usually unsuitable for retention due to poor condition.**

These trees are in such a condition that they cannot be realistically retained as living trees in the context of the current land use for longer than 10 years. This may be due to any of the following:

- 1) Failure is likely due to serious, irredeemable, structural defects.
- 2) Removal of other category U trees will render them exposed and unstable.
- 3) They are in serious, overall decline or are dead.
- 4) They are of low quality and suppressing adjacent trees of better quality.
- 5) Diseases are present which may affect the health of adjacent trees.

These trees should be removed or treated in such a way as to make them safe where they have high ecological value, such as in a woodland setting.

### **Appendix 3: General Guidelines**

- A3.1 All tree work should be undertaken to BS 3998: 2010 '*Recommendations for tree work*' or other recognised industry practice.
- A3.2 Staff carrying out the work must be qualified, experienced and ideally be Arboricultural Association approved contractors. They should be covered by adequate public liability insurance.
- A3.3 This report is based upon a visual inspection. The consultant shall not be responsible for events which happen after this time due to factors which were not apparent at the time, and the acceptance of this report constitutes an agreement with the guidelines and the terms listed therein.
- A3.4 Any defects seen by a contractor or the employer that were not apparent to the consultant must be brought to the consultant's attention immediately.
- A3.5 No liability can be accepted by JCA in respect of the trees unless the recommendations of this report are carried out under the supervision of JCA and within JCA's timescale.
- A3.6 It is advisable to have trees inspected by an arboricultural consultant on a regular basis.

## Appendix 4: Author Qualifications

### Principal Consultant and Managing Director

**Jonathan Cocking** *F.R.E.S., Tech. Cert. (Arbor.A), PDipArb (RFS) FArborA CBiol MSB. MICFor.* Jonathan is a Registered Consultant and Fellow of the Arboricultural Association and sits on its Professional Committee. He has 31 years' experience in the Arboricultural profession and served for eight years as Senior Arboriculturist with a large local authority before establishing JCA in 1997. Jonathan has since developed JCA's portfolio of services and its extensive client base. He is a Chartered Biologist, a Chartered Arboriculturalist and an Expert Witness with much experience of litigation work.

### Technical Director

**Toby Thwaites** *BSc (Hons), HND (Arboriculture), LANTRA Accredited PTI, MArborA.* Toby joined JCA in 1998 after graduating in Ecology at the University of Huddersfield and has since graduated in Arboriculture at the University of Central Lancashire. A former JCA team leader and Consulting Arboriculturist, Toby is now Technical Director and oversees all office and on-site activities at JCA and is on hand to offer technical support and advice.

### Operations Director

**Charles Cocking** *FdSc (Arboriculture), LANTRA Accredited PTI, MArborA.* Charles joined JCA in January 2014 having previously worked for the company on a part time basis during 2013. Charles obtained his Foundation Degree in Arboriculture at Askham Bryan College, York, and is a Professional Member of the Arboricultural Association. Charles now oversees all internal operations for the company.

### Arboricultural Projects Director

**Luke Wickham** *FdSc (Arboriculture and Urban Forestry), LANTRA Accredited PTI, MArborA.* Luke joined JCA in 2021 after obtaining his Foundation Degree in Arboriculture and Urban Forestry at Askham Bryan College. Having previously worked within the industry for the past 4 years, running his own small business and sub-contracting for local firms, Luke brings a sound knowledge and understanding of the practical and academic sides of the industry.

### Consulting Staff: Arboriculture

**Andrew Bussey** *LANTRA Accredited PTI, TechArborA.* Andrew started working in consultancy at JCA in 2006 having spent 12 years working as an arborist for various private companies before joining a Local Authority forestry team. He has various NPTC qualifications and is QTRA qualified.

**Emily Wilde** *FdSc (Arboriculture), LANTRA Accredited PTI, TechArborA.* Emily joined JCA having previously worked for various private tree surgery and consultancy companies over the past 8 years. She initially obtained a ND in Forestry & Arboriculture, followed by a FdSc in Arboriculture at Askham Bryan College, York. Emily has various NPTC certificates and is QTRA qualified.

**Mick Eltringham** *ND (Forestry), LANTRA Accredited PTI, TechArborA.* Mick joined JCA after spending 12 years working in the industry for various private companies in the north and south of England. He has also spent the last five years working as a consultant for two canopy research projects in the Amazon Rainforest, working with Oxford University and the University of Arizona. He has various NPTC Qualifications.

**Dan Kemp** *FdSc (Arboriculture), BTEC Dip (Arb), LANTRA Accredited PTI, MArborA.* Dan joined JCA in February 2019 with nearly 30 years' experience in arboriculture with extensive Botanical and Mycological expertise. He worked as a London Tree Officer for 12 years and in several arboricultural and horticultural management posts, specialising particularly in tree risk assessments and tree related subsidence.

**David de Peña** *BSc (Hons) Ecology and Conservation, TechArborA.* After earning his degree from Manchester Metropolitan University, David worked as an ecologist at various consultancies, contributing to a wide range of projects, including major infrastructure projects across the UK. More recently, David transitioned to arboriculture and served as a surveyor for Manchester City of Trees, where he participated in a project to quantify the value of Greater Manchester's woodlands and trees.

### Administrative Staff

**Catherine Cocking** Accounts Manager.  
**Saunders** Credit Control Manager  
**Adie Gray** I.T. Officer.

**Lorraine Spink** Administrative Assistant. **Kelly  
Alannah Chapman** Administrative Assistant




THIS PLAN IS TO BE PRINTED IN COLOUR AND READ IN CONJUNCTION WITH THE JCA ARBORICULTURAL REPORT (JCA REF: 22374a/LW)

### Root Protection Area: RPA

THE ROOT PROTECTION AREA SHOULD IDEALLY REMAIN UNDISTURBED IF THE TREE IS TO BE RETAINED.

THE DEVELOPMENT PROPOSALS SHOULD THEREFORE BE DESIGNED TO AVOID THE RPA OF ANY TREE WHICH IS TO BE RETAINED.

IF IT IS NECESSARY FOR THE DEVELOPMENT TO ENCRACH INTO THE RPA OF A TREE WHICH IS TO BE RETAINED THEN SPECIALIST CONSTRUCTION TECHNIQUES AND MATERIALS MUST BE CONSIDERED.



### Appendix 5: Tree Constraints Plan

ADDRESS: Land adjacent to Forge Lane, Dewsbury, West Yorkshire, WF12 9EX  
JCA REF: 22374b/LW

SCALE: 1:1000      PAPER SIZE: A2

SURVEYED BY: LW      DRAWN BY: LW      APPROVED BY: DK

#### BRITISH STANDARD 5837:2012: 4.5 RETENTION CATEGORIES

Detailed definitions of these categories are at Appendix 2 of our report. N.B. These categories do not necessarily represent or correspond to recommendations for action made in this report.

	CATEGORY A: 'RETENTION MOST DESIRABLE'
	CATEGORY B: 'RETENTION DESIRABLE'
	CATEGORY C: 'TREE WHICH COULD BE RETAINED'
	CATEGORY U: 'TREE FOR REMOVAL'
	STEM OF TREE TO BE RETAINED
	STEM OF TREE TO BE REMOVED
	ROOT PROTECTION AREA
	ROOT PROTECTION AREA (PRIOR TO OFF-SETTING)



Arboricultural & Ecological Consultants




THIS PLAN IS TO BE PRINTED IN COLOUR AND READ IN CONJUNCTION WITH THE JCA ARBORICULTURAL REPORT (JCA REF: 22374b/LW)

### Appendix 6: Arboricultural Implications Plan

ADDRESS: Land adjacent to Forge Lane, Dewsbury, West Yorkshire, WF12 9EX.  
JCA REF: 22374b/LW

SCALE : 1:1000      PAPER SIZE : A2

	TREE TO BE RETAINED
	TREE TO BE REMOVED
	STEM OF TREE TO BE RETAINED
	STEM OF TREE TO BE REMOVED
	ROOT PROTECTION AREA
	ROOT PROTECTION AREA ENCLOSED BY THE PROPOSED DEVELOPMENT: NO-DIG TECHNIQUES TO BE UTILISED



I hope that this report provides all the necessary information, but should any further advice be needed please do not hesitate to contact the author.

Signed



.....  
Luke Wickham FdSc (*Arboriculture and Urban Forestry*), LANTRA Accredited PTI,  
MArborA.

9<sup>th</sup> April 2025

For and on behalf of **JCA Ltd**

**Registered Office**

**Unit 80  
Bowers Mill  
Branch Road  
Barkisland  
Halifax  
HX4 0AD**

**Tel: 01422 376335  
Email: [info@jcaac.com](mailto:info@jcaac.com)**

**[www.jcaac.com](http://www.jcaac.com)**

# JCA Ltd. Arboricultural and Ecological Consultants

## Professional Tree and Ecology Advice nationwide

---

### ARBORICULTURAL SERVICES

---

#### Guidance for Architects and Developers

- British Standard 5837 Tree Surveys
- Arboricultural Implication Assessments (AIA)
- Arboricultural Method Statements (AMS)

---

#### Advice for Engineers, Loss Adjusters and Insurers

- Tree Surveys for Subsidence
- Heave Assessment
- Tree Root Identification

---

#### Advice for Local Authorities and Social Housing

- Tree Condition Surveys
- Specialist Decay Detection
- Landscape and Orchard Design

---

#### Tree Advice for the Legal Profession

- Subsidence Litigation
- Personal Injury and Accident Investigation
- Expert Witness, Planning Inquiries and Appeals

---

#### Veteran Tree Management

- Ancient Woodland Management
- Veteran Tree Management

---

#### Tree Health and Pest and Disease Management

- Pest and Disease Surveys
- Tree Health Checks
- Disease Mitigation and Control

---

### ECOLOGICAL SERVICES

---

#### Ecological Pre-Planning Services

- Phase 1 Habitat Surveys
- Great Crested Newt eDNA Sampling
- Protected Species: Bat, Wintering and Nesting Bird, Badger, Amphibian, Otter, Water Vole, White-Clawed Crayfish, Dormice and Reptile Surveys.
- Preparation for Environmental Impact Assessment (EIA)
- Invasive Species Surveys
- Code for Sustainable Homes

---

#### Ecological Post-Planning Services

- Biodiversity Enhancement Plans
- Protected Species Mitigation
- Ecological Management (Bat and Bird box installation and inspection)

---

#### HEAD QUARTERS:

Unit 80 Bowers Mill,  
Branch Road,  
Barkisland,  
Halifax, HX4 0AD.

Tel: 01422 376335  
Email: [info@jcaac.com](mailto:info@jcaac.com)  
Website: [www.jcaac.com](http://www.jcaac.com)

