



NOTES

1. Do not scale from this drawing.
2. This drawing is to be read in conjunction with all relevant Architects and Engineers drawings and specifications.
3. All works and materials to be in accordance with current British Standards and Building Regulations.
4. For drainage and highways details refer to Build Vision 900 Series drawings.
5. Class 'S' and Concrete bed and surround to be in accordance with pipe bedding details drawing.
6. All pipes to MIS 4-35-01 and to be kate marked structural walled plastic, clay or concrete pipes suitable for use in Highways.



ROAD 1: CENTRE LINE OF NEW HIGHWAY TO BE ADOPTED



ALL CONNECTIONS SOFFIT TO SOFFIT

VERTICAL SCALE 1:100
HORIZONTAL SCALE 1:100

- YORKSHIRE WATER NOTES**
- All adoptable sewer works and material to be in accordance with "Code for Adoption". The Relevant British/European and Yorkshire Water's Standards/Requirements/Addendum to the Mechanical and Electrical Specification and Kitemarked.
 - Manhole covers shall/must have a clear opening of 600mm and shall be Class D400 to BS EN 124 with 150mm deep frames in Highways.
 - Filled ground must be filled and consolidated under the supervision and to the satisfaction of Yorkshire Water before any sewer works are carried out.
 - Yorkshire Water is not obliged to accept filter drain/land drainage run-off into the public sewer network or adoptable drainage system (directly or in-directly). An alternative method of disposal of the land drainage run-off will therefore be required and you will have to liaise with the Local Authority, Land Drainage Section regarding the disposal of the filter drain/land drainage run-off.
 - The adoptable sewers should be a minimum of 1m and manholes 0.5m from kerb faces and service margins.
 - Sewers must have 5 metres clearance from trees and hedges or the width of the canopy at mature height.
 - Sewers to be laid in Class "S" Bedding (150mm granular bed and surround). Where depth of cover to top of the sewer is less than 1.2m in highways and verges (or less than 900mm in nonvehicular access areas) then a concrete slab should be provided above granular bed and surround.
 - Bedding and backfill material to conform to the requirement of Water Industry Specification 4-08-02 (Table A2).
 - Yorkshire Water policy is that Type "C" brick manholes and 1050mm diameter manhole rings are not preferred. Instead, it is preferred that you use a Type "S" manhole with 1200mm diameter or 1500mm diameter rings, with the opening sited over the channel where depth of cover to pipe soffit is 1 - 1.5m.
 - Adoptable plastic sewer pipes to be BS Kitemarked (certified to WS 4-35-01 and BS/EN13476). Adoptable plastic sewer pipes to be laid in maximum 3 metre lengths unless there is a specific operational need to lay longer lengths. Plastic channel sections in manholes are not acceptable and Yorkshire Water would require clay ware channel in manholes.
 - The minimum crushing strength for clay pipes should be as follows: 100mm dia. 40kN/m, 150mm dia. 40kN/m, 225mm dia. 45kN/m and 300mm dia. 72kN/m. The minimum crushing strength for concrete pipes should be - (Class 120 to EN 1916/BS5911-1 2002). Plastic pipes should conform to WS 4-35-01 and BS EN13476.
 - Where a B125 cover and frame has been approved, this must not be coated in plastic and must have lifting eyes suitably sized to accommodate standard lifting keys. Screw down covers are not acceptable.
 - There must be enough clearance at crossovers to accommodate bedding to both pipes, approx. 300mm : if crossover is near the rocker then the clearance needed may need to be increased.

**PRELIMINARY
NOT FOR CONSTRUCTION.**

Rev	Date	By	Checked	Remarks
P1	22.05.25	SJC		Preliminary Issue

Project		Burn Road Birchencliffe		
Client		Wiggett Construction Ltd.		
Drawing		Long Sections Sheet 1 of 3		
Number	1298-905	Rev	P1	
Scale	1:100@A1	Drawn	SJC	Checked
				Date May 2025

Build Vision
Consulting Engineers

Middle Cottage, Ben Kaye Row, Holmfirth HD9 1EF
Mobile Tel: 07799 823040
email: Sarah.Griggs@bvconsulting.co.uk