

LEGEND

- DW WINDSOR SEPHORA HALO RADIUS WITH CURVED DIRECT POST, POWDER COATED DB703 FINE TEXTURED. 3000K OUTPUT WITH 6M COLUMN ROOT MOUNT COLUMN (5.5M AGL.) SEE QUOTE 25108, CONTRACTOR TO CONFIRM NUMBERS AND SPEC PRIOR TO ORDERING. PROVIDE 200MM VERTICAL DUCT EMBEDDED IN CONCRETE FOR MOUNTING COLUMN ROOT IN. MIN 1 METER DEEP. FITTINGS TO HAVE INTEGRAL PHOTO CELL
- 450X450 INSPECTION CHAMBER, WITH HEAVY DUTY GALVANIZED STEEL LID WITH RECESS FOR BLOCK PAVED FINISH TO MATCH. CHAMBERS TO BE CONSTRUCTED USING IN SITU CONCRETE BASE AND STAKKAbOX OR SIMILAR APPROVED. BASE OF CHAMBER TO BE 600 DEEP (BELOW FINISHED GROUND LEVEL)
- ⊠ ALTRON – AW1545/5/UP 5 METER HIGH CCTV COLUMN WITH 400MM SQ CABINET BASE. MOUNTING TO BE IN LINE WITH MANUFACTURERS REQUIREMENTS, INCLUDE ALL BUILDERS WORKS FOR DUCT ENTRY AND CONCRETE SLAB BELOW GROUND. COLUMN TO BE FINISHED RAL DB703. PROVIDE LIGHTING COLUMN SERVICE CUTOUT IN BASE FOR POWER SUPPLY TO METAL CLAD TWIN SWITCHED SOCKET OUTLET.
https://www.altron.co.uk/urban_cabinet_based_poles.html
- ▭ LUCY ZODION STEEL SINGLE DOOR PILLAR – HDG8/3 LUCY REF THM0024658 836 H X 600 W X 240 D. WITH ROOT MOUNT AND BACK BOARD –
<https://www.cableservices.co.uk/product/lucy-fortress-steel-single-door-pillars/>
- 100M DIA POLYPIPE RIDGIDUCT, LAID IN SHARP SAND AT 450 COVER DEPTH WITH CABLE WARNING MARKER AT 200MM BELOW FINISHED GROUND LEVEL.

- GENERAL DRAWING NOTES**
1. All levels/dimensions to be checked on site by contractor.
 2. All items of works to be executed in a neat and workmanlike manner to the satisfaction of the University.
 3. Ensure adequate protection to all existing/new services and finishes.
 4. All works as per approved specification and to be in accordance with relevant current British Standards and code of practice.
 5. Any variations to the drawing/specification schedule of works to be approved by the University.
 6. This drawing to read in conjunction with specification/schedule of works.
 7. This drawing to be read in conjunction with drawings no.

- SPECIFICATION NOTES**
- A. The words 'Make Good' are to be read as including all necessary labour and new materials requested to match in every respect to the existing surrounding works.
 - B. All old materials described to be cleared away are to become the property of the contractor and are to be removed from site by him.
 - C. Drawings and specification as schedule/specification

**University of
HUDDERSFIELD**
Inspiring tomorrow's professionals

**University of
HUDDERSFIELD**
Inspiring tomorrow's professionals
Estates & Facilities
Queensgate Huddersfield HD1 3DH
Tel 01484 472351 Fax 01484 472481

Project
QUEENSGATE
LANDSCAPING
FORMER EDITH KEY SITE

Title
ELECTRICAL SERVICES
EXTERNAL SERVICES
LIGHTING CCTV & DUCTING

Drawn By PH	Checked By	Approved By
----------------	------------	-------------

Project Number PS2024-029	Building Drawing Revision - 1001 -
------------------------------	---------------------------------------

Date 30.04.2025	Scale 1:150
--------------------	----------------

