

Boundary Treatment Plan

Marsden, Gate Head

(Condition 3)

Timber Fencing:

The timber fencing will be 'Post and Rail' in design. All timber fencing materials will be sourced from local Timber Merchant, 'Timber Specialists, Huddersfield'. The timber is treated to prevent rotting and extend the life of the fence. See example here. Height to be 100cm.



Existing Dry Stone Wall:

All the existing dry-stone walls will be maintained and repaired if necessary. The walls are in relatively good condition, with a few loose stones having fallen off in the past. Any repairs will be made using the stone that is already on the site. Please see images of existing dry-stone walls on site. Height is approximately 100-120cm.

