

© 2025, BRYAN, HALL, BRYAN & HALL are trademarks of Bryan G Hall, Inc. or its affiliates.
 LinkedIn, the LinkedIn logo, the IN logo and INMail are registered trademarks or trademarks of LinkedIn Corporation and its affiliates in the United States and/or other countries.

Bryan G Hall Ltd. Registered in England & Wales Co No. 4104802

This drawing is copyright and shall not be reproduced nor used for any other purpose without the written permission of the Bryan G Hall Ltd. This drawing must be read in conjunction with all other related drawings and documentation.

It is the contractor's responsibility to ensure full compliance with the Building Regulations. Do not scale from this drawing, use figured dimensions only. It is the contractor's responsibility to check and verify all dimensions on site. Any discrepancies to be reported immediately. IF IN DOUBT ASK.

Materials not in conformity with relevant British or European Standards/Codes of practice or materials known to be deleterious to health & safety must not be used or specified on this project.

Bryan G Hall Limited has not checked or verified, and shall therefore not be liable for any inaccuracies which may be attributable to any base plan(s) reports, data or information provided by the client, or purchased by the consultant on the client's behalf, that may have been utilised within this drawing.

Bryan G Hall Limited shall not be liable for the use of this or any associated document, for any purpose, by any person other than that for which they were provided.

It remains the client's and/or its appointed contractor's responsibility to check for any discrepancies. Any anomalies discovered must be reported immediately to Bryan G Hall Limited for verification.

The locations of utilities apparatus, if shown, have been reproduced from plans supplied to Bryan G Hall Limited. Although care has been taken when duplicating this information, these locations are approximate only. No guarantee can be given by Bryan G Hall Limited for their accuracy. It is the client's or its appointed agent/contractor's responsibility to verify the exact locations on site by appropriate means prior to mechanical excavation.

- KEY:**
- Area of General Site Clearance
 - To include removal of vegetation, trees and hedges where required to facilitate the highway improvements
 - Length of existing Kerbing plus concrete bed and backing to be broken out and recycled for fill. Granite sets to be taken to store.
 - Existing tree or of vegetation within private development area to be taken down and removed off site. Roots grubbed up in accordance with MCHW Clause 202.
 - Existing overhead utility apparatus to be adjusted in accordance with utility provider discussions undertaken by others.
 - Existing redundant signage to be removed to tip off site.
 - Existing utility apparatus to be adjusted in accordance with utility provider discussions undertaken by others. Apparatus to be adjusted to new finished footway/carriageway level where appropriate
 - Area of existing tactile paving to be broken out to formation level and removed to tip off site.
 - Existing "keep left" bollards to be taken out and removed to tip off site, with any foundations removed accordingly.
 - Existing timber fence and fence post taken up and removed off site.

- NOTES:**
1. All services should be located on site prior to any works being carried out.
 2. The contractor is to hand dig any trial pits to locate any services which may be affected by the proposed works.
 3. All existing electrical disconnection's and any works involving electrical equipment are to be carried out by a qualified approved electrical engineer.
 4. All brick, Masonry and PCC Kerbs shall be taken away and recycled, where possible.
 5. Any signs which are to be taken down for re-use will require inspecting by the local inspecting officer prior to re-erecting.
 6. Where manhole covers are to be lowered, an inspection shall be undertaken prior to work commencing to check on its condition and whether the minimum number of brickwork courses above the slab can be achieved.
 7. All road markings affected by works to be reinstated in accordance with local council TRO.
 8. Any trees that are to be removed need to have roots grubbed up in accordance with MCHW Clause 202.
 9. Any contamination to be removed to certified waste disposal facility.
 10. For bituminous running surfaces, the removal of permanent road markings shall be by mechanical means or forced air abrasive (shot blasting) or Ultra High Pressure Water Jetting. In all cases the Contractor shall submit details of the proposed method for the Overseeing Organisation's consent.

Unrecorded Watercourses/ Springs- Where previously un-identified/unrecorded watercourses or springs are found on site during the construction phase, such details must be brought to the attention of Kirklees LLFA Paul Farndale Email: paul.farndale@kirklees.gov.uk together with your proposals for the management (collection, diversion etc.) of such features'

Site Investigation details can be found in the following reports - Phase 1 Geoenvironmental Desk Study, Ref. G-22-009, March 2022. Phase 2 Ground Investigation Report Ref G-22-009 April 2022

H	29.09.25	Plans updated in accordance with comments received from Kirklees Council 26 September 2025	IE
G	07.08.25	Works on Whitehall Road West updated	IE
F	02.07.25	Site layout updated	IE
E	12.02.25	Site layout updated	IE
D	05.07.24	Site layout updated	IE
C	10.06.24	Site layout updated	IE
B	23.05.24	Amendments made due to latest architects plan including visitor parking bays	IE
A	16.05.24	Site layout and associated updates made	IE

Rev: Date: Amendment: DRN CHK APR

BRYAN G HALL
 CONSULTING CIVIL & TRANSPORTATION PLANNING ENGINEERS
 LEEDS T 0113 246 1555 LONDON T 0203 532336
 Suite E15 | Josephs Well | www.bryanhall.co.uk
 Hanover Walk | LEEDS | L5 1AB | transportleeds@bryanhall.co.uk

Client: Orion Homes
 Status:
 Scale: 1:250
 Size: A1 - 594 x 841 Drawn: IE Chkd: NB Appvd:
 Project: Residential Development, Whitehall Road West, Birkenshaw
 Title: Site Clearance

Drawing No: 23/341/200/001 Revision: H
 Job No: 23-341 Date: 19.02.24

