

1.0 INTRODUCTION

- 1.1 The fabric of the building will be designed to qualify for a Secured by Design Bronze Award.

2.00 WINDOWS AND DOORS

- 2.1 Doors; stiles and rails 119mmx44mm, panels not less than 15 mm thick maximum size 230mm
- 2.2 Windows; casements not to exceed 1200mm x 1200mm frames 67mm x 56mm.
- 2.3 Glazing; laminated glass (PAS 24) to BSEN 356-2000 class P1A
- 2.4 Locking; doors electromagnetic locking to BSEN 14846 2008, windows multipoint espanulette locks.

3.0 INTRUDER ALARM SYSTEMD

- 3.1 An intruder alarm which conforms to BS8243:2021 the design, installation and configuration of intruder alarm systems will be installed.