

VENUS STATIC BOLLARD



The Terra Venus Bollards has been successfully impact tested to the British PAS 68 specification stopping 7.5t @ 30mph (48kph). Polyester Powder Coated as standard, with a range of sleeves available including stainless steel finishes.

STANDARD BOLLARD

- V/7500[N2]/48/90:0.0/0.0
- **Foundation Type C**
Embedment: 500mm
- **Height above ground:** 1000mm
- **Diameter:** 219mmø
- **Finish:** Polyester Powder Coated
- **Options:** Range of Aesthetic Sleeves, including stainless steel Removable

