

Window	Window Ref.	Window	Window Ref.	Window	Window Ref.
	H01 FF-W05 – Hardwood frame – Secure by Design PAS 24:2012 locking system – Fully weather sealed to BS EN6375-1 2009 – Mock sash casement window – Traditional butt hinged – 4:8:4 double glazed unit Painted to match existing externally (Cream RAL 9001)		H01 FF-W06 – Hardwood frame – Secure by Design PAS 24:2012 locking system – Fully weather sealed to BS EN6375-1 2009 – Mock sash casement window – Traditional butt hinged – 4:8:4 double glazed unit Painted to match existing externally (Cream RAL 9001)		H01 SF-W01 – Hardwood frame with recessed check reveal frame Secure by Design PAS 24:2012 locking system – Fully weather sealed to BS EN6375-1 2009 – 4:8:4 double glazed unit – Safety glass to be installed Painted to match existing externally (Cream RAL 9001)
Window	Window Ref.	Window	Window Ref.	Window	Window Ref.
	H01 FF-W08 – New timber sliding sash box window to match existing pattern & mechanism – 4:8:4 double glazed unit – Window operable – Hardwood Frame Painted to match existing externally (Cream RAL 9001)		H01 SF-W02 – Hardwood frame – Secure by Design PAS 24:2012 locking system – Fully weather sealed to BS EN6375-1 2009 – Mock sash casement window – Traditional butt hinged – 4:8:4 double glazed unit Painted to match existing externally (Cream RAL 9001)		H01 SF-W03 – Hardwood frame – Secure by Design PAS 24:2012 locking system – Fully weather sealed to BS EN6375-1 2009 – Mock sash casement window – Traditional butt hinged – 4:8:4 double glazed unit Painted to match existing externally (Cream RAL 9001)
Window	Window Ref.	Window	Window Ref.	ALL window openings to be checked on-site prior to the manufacturer of any windows All window to be constructed in hardwood timber casement frame. All windows to be upgraded with slender 16mm double glazing with heritage spacer (where required) to meet BSI standard BS EN 1279-3:2018. Windows to be given two coats of gloss paint Painted RAL 9001 (white) with two coats of satin gloss paint RAL 9001 to internal side of window Note: The height of any new masons opening will be 10mm bigger than shown Key: SG : Safety Glass OBS : Opaque Glass	
	H01 SF-W04 – Secure by Design PAS 24:2012 locking system – Fully weather sealed to BS EN6375-1 2009 – Mock sash casement window – Traditional butt hinged – 4:8:4 double glazed unit Painted to match existing externally (Cream RAL 9001)		H01 A-W01 – Hardwood frame – Secure by Design PAS 24:2012 locking system – Fully weather sealed to BS EN6375-1 2009 – 4:8:4 double glazed unit Painted to match existing externally (Cream RAL 9001)		

NOTES

1. No dimensions to be scaled.
IF IN DOUBT ASK.

2. All dimensions must be checked and verified on site by the Contractor prior to the commencement of works and Hinchliffe Architecture & Design Ltd. to be notified of any discrepancies.

3. The copyright of these drawings remains the property or Hinchliffe Architecture & Design Ltd. They must not be reproduced in any way without prior written consent from the originator (Hinchliffe Architecture & Design Ltd.)

B	01/08/25	CLIENT AMENDMENTS
A	01/08/25	FIRST ISSUE
Rev.	Date	Description

Status
LISTED BUILDING CONSENT

**hinchliffe**
architecture
& design

Hinchliffe A&D
24 Carr View Road
Holefirth
West Yorkshire
HD9 1JL017921 907142
01484 520 764
info@hinch-architecture.co.uk
www.hinch-architecture.co.uk

Client
MR & MRS B & R HESMONDHALGH

Project
OLDFIELD HOUSE
OLDFIELD ROAD
OLDFIELD
HONLEY, HOLMFIRTH
HD9 6RL

Drawing Title
PROPOSED WINDOW AND DOOR
DETAILS (SHEET 2 of 4)

Scale (at A1) 1:20	Date JUNE' 2025
Drg. no. 307-25-PL06	Rev. B