



CHAPMAN TAYLOR
GLOBAL ARCHITECTS & MASTERPLANNERS

Chapman Taylor LLP

BAM

D132KCH

Kirklees Cultural Heart Centre

IR430301-CTA-ZZ-XX-SP-A-010N10

N10 General fixtures/ furnishings/ equipment

Construction

C02

09-01-2025

The Grade II listed indoor market hall is set to undergo a comprehensive transformation, evolving into a combined indoor food hall and a state-of-the-art public library that will also house the West Yorkshire Archive Service (WYAS).



Contents

N10 General fixtures/ furnishings/ equipment	REVISED	1
C21X Stripping out	DELETED	4
F10 Brick/ block walling	DELETED	4
F30 Accessories/ sundry items for brick/ block/ stone walling	DELETED	4
G15X Steel frame section (SFS)	DELETED	4
H72 Aluminium strip/ sheet fully supported roof and wall coverings/ flashings	DELETED	4
J30 Liquid applied tanking/ damp proofing	DELETED	4
J31 Liquid applied waterproof roof coatings	DELETED	4
J42 Single layer polymeric sheet roof coverings	DELETED	4
K10 Gypsum board dry linings/ partitions/ ceilings	DELETED	4
K30 Panel partitions	DELETED	4
K32 Panel cubicles/ duct and wall linings/ screens	DELETED	4
K40 Demountable suspended ceilings	DELETED	4
K41 Raised access floors	DELETED	4
L10 Internal screens/ louvres	DELETED	4
L20 Doors/ shutters/ hatches	DELETED	4
L30 Stairs/ ladders/ walkways/ handrails/ balustrades	DELETED	4
L35 Fixed utilitarian access systems	DELETED	4
M10 Cement based levelling/ wearing screeds	DELETED	5
M12 Resin flooring	DELETED	5
M40 Stone/ concrete/ quarry/ ceramic tiling/ mosaic	DELETED	5
M41 Terrazzo tiling/ in situ terrazzo	DELETED	5
M50 Rubber/ plastics/ cork/ lino/ carpet tiling/ sheeting	DELETED	5
M60 Painting/clear finishing	DELETED	5
M60 Painting/clear finishing	DELETED	5
N11 Domestic kitchen fittings, furnishings and equipment	DELETED	5
N13 Sanitary appliances and fittings	DELETED	5
N25 Permanent access and safety equipment	DELETED	5
P10 Sundry insulation/ proofing work	DELETED	5
P20 Unframed isolated trims/ skirtings/ sundry items	DELETED	5
P21 Door/ window ironmongery	DELETED	5



Q41 Barriers/ guardrails	DELETED	5
Z10 Purpose made joinery	DELETED	5
Z11 Purpose made metalwork	DELETED	5
Z20 Fixings and adhesives	DELETED	5
Z21 Mortars	DELETED	6
Z22 Sealants	DELETED	6
Z31 Powder coatings	DELETED	6
Z33 Anodizing	DELETED	6
Z50X Air-tightness	DELETED	6



N10

General fixtures/ furnishings/ equipment **REVISED**

Products

15X Scope of Work

1. Generally: Complete the design and detailing in accordance with the indicative design shown on the drawings and the requirements of this specification and install general fixtures, fittings, furnishings, equipment etc as specified and as indicated on Architect's drawings.
 - 1.1. Work includes but is not restricted to: [__entrance matting __roller blinds ____].
2. Additional components: Allow for all ancillary works and components, fixings etc. necessary for the completion of the work.
3. Coordination: Coordinate the design with the requirements of adjoining work packages, their components and tolerances, including interface details, structural components etc.
4. Design information: Allow for the provision of design information as required, including information required by the CA, Building Control Officer etc.
5. Proprietary information: Allow for the provision of proprietary information, including Agreement or equivalent certification.
6. Health and Safety information: Allow for the provision of this information for the Construction Phase Health and Safety Plan and Health and Safety File. Comply with the duties of Designers under The Construction (Design and Management) Regulations.
7. Samples: Allow for the provision of samples, as specified, including incorporation of some samples into mock-ups and prototypes.
8. Control samples: Allow for the provision of control samples, being part of the finished work only where specified, and obtaining approval of appearance. Allow for providing additional control samples, as directed.
9. Protection: Allow for the provision of protection, as specified and as required to protect finished components from subsequent adjacent work, including additional and replacement protection where required by the progress of the works. Allow for removing such protection, when directed.
10. Maintenance information: Allow for the provision of this information for the Building Manual. All Building Manual documentation requirements must be reviewed, agreed and confirmed in writing with the Main Contractor at the earliest stage.

185 A Corner protection guards to basement walls and columns

1. Purpose: corner protection
2. Manufacturer: Aldea Group UK or similar
 - 2.1. Product reference: Moravia traffic-Line Heavy duty
3. Material: Rubber
4. Finish/ Colour: Black and yellow reflective bands
5. Accessories/ Other requirements: 100x 100mm 1200mm high, allow for preformed holes and fixings

192 A Cages- Smoke Ventilation Housing GMC-100 **REVISED**

1. Description: 2000mm high Galvanised Steel open mesh cage
2. Manufacturer: Contractors choice
 - 2.1. Product reference: Contractors choice
3. Form: Open top Two-sided
4. Dimensions: See Architects Design intent drawings



5. **Frame:** Mild Steel hollow section
 - 5.1. **Material:** Mild steel
 - 5.2. **Section size:** To contractors design
 - 5.3. **Finish/ Colour:** Galvanised steel
 - 5.4. **Infill panel :** mild steel mesh
 - 5.5. **Finish :** Galvanised
 - 5.6. **Gates :** Galvanised steel
 - 5.6.1.configuration : Single gates
 - 5.6.2.dimension : 1000 wide to centre line support post
 - 5.6.3.Locking : Padlock
 - 5.6.4.Accessories : hinges , floor bolts
6. **Other requirements:** Include all floor and wall fixings

242 Vertical window Blinds

1. **Description:** Mechanical vertical window blinds
2. **Manufacturer:** Umbra www.umbrashading.co.uk or similar approved.
 - 2.1. **Product reference:** Helios Roller Shades with cassette, fixed crank
3. **Type:** Heavy duty roller blind system with cassette
4. **Dimensions:** varies refer to design intent drawings
5. **Material:** Spectrum 5010 3% screen fabric for dimout
 - 5.1. **Finish/ Colour:** Fabric colour TBC
 - 5.2. **Hardware Colour :** RAL 9016
6. **Operation:** fixed crank handle -inherently complies with the BS EN 13120 child safety standard.
7. **Operating effort:** complies with the BS EN 13120 child safety standard
8. **Testing:** Appearance and tolerance
9. **Mechanism endurance:** As manufacturers warranty
10. **Accessories/ Other requirements:** - 20mm diameter aluminium hembar - RAL 9016
- 92.5mm x 100mm square cassette headbox – RAL 9016

245 Roof Blinds

1. **Description:** Roof blinds to fixed rooflights
2. **Standard:** To BS EN 13120.
3. **Manufacturer:** Umbra or similar www.umbrashading.co.uk
 - 3.1. **Product reference:** Helios RL
4. **Type:** Wire guided Rooflight system
5. **Dimensions:** Refer to design intent drawings
6. **Material:** Fabric Spectrum 5010 3% screen fabric
 - 6.1. **Finish/ Colour:** TBC (fabric)
 - 6.2. **Finish hardware colour :** RAL 9016
7. **Operation:** Motorised Somfy 240v Radio monitor
8. **Testing:** To manufacturers recommendations and installation requirements
9. **Mechanism endurance:** As manufacturers information
10. **Accessories/ Other requirements:** Robust 3mm side guide wired ,100mm x 92,5 L shaped fascia profiles



300 A Entrance matting

1. Description: To entrances
2. Manufacturer: Forbo Flooring Systems or equivalent approved
 - 2.1. Product reference: Nuway grid
3. Arrangement: Inset internal 17mm grid
4. Material: Rubber/ Textile
5. Pattern: refer to design layout
6. Colour: Subject to sample approval
7. Size: refer to design drawings
8. Wiper blade : Needlefelt/PVC backed textile
9. Pile material : 100% polypropylene (Burford) /100% polyamide (Coral)
10. Integral accessories: Allow for stainless steel perimeter framing
11. Substrate:: Screed on void former

Execution

710 Moisture content of wood and wood-based boards

1. Standard: To BS EN 942
2. Moisture content on delivery: 6-10%
3. Temperature and humidity: During delivery, storage, fixing and to handover maintain conditions to suit specified moisture contents of timber components.

770 Trims

1. Lengths: Wherever possible, unjointed between angles or ends of runs.
2. Running joints: Where unavoidable, obtain approval of location and method of jointing.
3. Angle joints: Mitred.

Completion

910 General

1. Doors and drawers: Accurately aligned, not binding. Adjusted to ensure smooth operation.
2. Ironmongery: Checked, adjusted and lubricated to ensure correct functioning.

920 Appliances

1. Test: Ensure that all functions and features work correctly.
2. Documentation: Submit guarantees, instruction manuals, etc.

Ω End of Section



C21X

Stripping out **DELETED**

F10

Brick/ block walling **DELETED**

F30

Accessories/ sundry items for brick/ block/ stone walling

DELETED

G15X

Steel frame section (SFS) **DELETED**

H72

Aluminium strip/ sheet fully supported roof and wall coverings/ flashings **DELETED**

J30

Liquid applied tanking/ damp proofing **DELETED**

J31

Liquid applied waterproof roof coatings **DELETED**

J42

Single layer polymeric sheet roof coverings **DELETED**

K10

Gypsum board dry linings/ partitions/ ceilings **DELETED**

K30

Panel partitions **DELETED**

K32

Panel cubicles/ duct and wall linings/ screens **DELETED**

K40

Demountable suspended ceilings **DELETED**

K41

Raised access floors **DELETED**

L10

Internal screens/ louvres **DELETED**

L20

Doors/ shutters/ hatches **DELETED**

L30

Stairs/ ladders/ walkways/ handrails/ balustrades **DELETED**

L35

Fixed utilitarian access systems **DELETED**



M10

Cement based levelling/ wearing screeds **DELETED**

M12

Resin flooring **DELETED**

M40

Stone/ concrete/ quarry/ ceramic tiling/ mosaic **DELETED**

M41

Terrazzo tiling/ in situ terrazzo **DELETED**

M50

Rubber/ plastics/ cork/ lino/ carpet tiling/ sheeting **DELETED**

M60

Painting/clear finishing **DELETED**

M60

Painting/clear finishing **DELETED**

N11

Domestic kitchen fittings, furnishings and equipment

DELETED

N13

Sanitary appliances and fittings **DELETED**

N25

Permanent access and safety equipment **DELETED**

P10

Sundry insulation/ proofing work **DELETED**

P20

Unframed isolated trims/ skirtings/ sundry items **DELETED**

P21

Door/ window ironmongery **DELETED**

Q41

Barriers/ guardrails **DELETED**

Z10

Purpose made joinery **DELETED**

Z11

Purpose made metalwork **DELETED**

Z20

Fixings and adhesives **DELETED**



Z21

Mortars DELETED

Z22

Sealants DELETED

Z31

Powder coatings DELETED

Z33

Anodizing DELETED

Z50X

Air-tightness DELETED



Specification created using NBS Chorus