




Autowave 2.0 Hardener

FOR PROFESSIONAL USE ONLY

Description		
Special additive for under the hood application, design, multi color application and to meet OEM specifications.		
	Gently shake the Autowave / Autowave 2.0 can prior to use	
	100	Autowave / Autowave 2.0
	10	Autowave 2.0 Hardener
	100	Autowave / Autowave 2.0 premix
	10-20	Activator WB
	Use Sikkens measuring stick 14 Blue	
	Spray gun set-up: Below 28°C: 1.2 – 1.3 mm Above 28°C: 1.3 – 1.4 mm	Application pressure: 1.7-2.2 bar at the air inlet HVLP max 0.6-0.7 bar at the air cap
	Application metallic colors: Closed wet coat – Light wet coat – Drop coat	Application solid colors: 2 x 1 coat
	Between coats: Until completely matt at 25°C	Prior to clearcoat application: Until completely matt at 25°C
	Clearcoat application See clearcoat T.D.S. Not needed for Under the hood	
	Use suitable respiratory protection Akzo Nobel Car Refinishes recommends the use of a fresh air supply respirator.	

Read complete TDS for detailed product information

Autowave 2.0 Hardener

FOR PROFESSIONAL USE ONLY

Description

Special Autowave additive for under the hood application, design, multi color application and to meet OEM specifications.

Products and additives

Autowave 2.0 Hardener

Basic Raw Materials:

Isocyanate resins

Mixing ratio by volume:

Add 10 parts of Autowave 2.0 Hardener to Autowave / Autowave 2.0 colors.
After stirring add the required amount of Activator WB

Potlife:

1½ hours

Note: Do not add Autowave 2.0 Hardener to Autowave colors containing Additive LP. This will decrease the potlife significantly

Application

See T.D.S. 5.0.2 / S1.09.03

Drying

Do not dry with IR

Product storage

Product shelf-life is determined when products are stored unopened at 20°C.
Avoid extreme temperature fluctuation.
Product shelf life data see TDS S9.02.01

Akzo Nobel Coatings LTD

Address: Unit 2B, Didcot Park
Churchward, Southmead Industrial Estate
Didcot, Oxfordshire, OX11 7HB
Tel: +44 (0)1235 862226

FOR PROFESSIONAL USE ONLY

IMPORTANT NOTE The information in this data sheet is not intended to be exhaustive and is based on the present state of our knowledge and on current laws: any person using the product for any purpose other than that specifically recommended in the technical data sheet without first obtaining written confirmation from us as to the suitability of the product for the intended purpose does so at his own risk. It is always the responsibility of the user to take all necessary steps to fulfil the demands set out in the local rules and legislation. Always read the Material Data Sheet and the Technical Data Sheet for this product if available. All advice we give or any statement made about the product by us (whether in this data sheet or otherwise) is correct to the best of our knowledge but we have no control over the quality or the condition of the substrate or the many factors affecting the use and application of the product. Therefore, unless we specifically agree in writing otherwise, we do not accept any liability whatsoever for the performance of the product or for any loss or damage arising out of the use of the product. All products supplied and technical advices given are subject to our standard terms and conditions of sale. You should request a copy of this document and review it carefully. The information contained in this data sheet is subject to modification from time to time in the light of experience and our policy of continuous development. It is the user's responsibility to verify that this data sheet is current prior to using the product.

Coatings brand names mentioned in this data sheet are trademarks of or are licensed to AkzoNobel.

Head Office

Akzo Nobel Car Refinishes B.V., PO Box 3 2170 BA Sassenheim, The Netherlands. www.sikkenscr.com