From: Farhad Khatibi
Sent: 03 November 2026 18:43
To: Planning ContactCentre
Cc: Nick Hirst
Subject: RE: Attached letter from Kirklees Council regarding application number 2025/93355 at location Land off, Woodward Court, Mirfield, WF14 0PY

Hi Katie

Please arrange for the inclusion of the following conditions:

1) Before the development commences a scheme detailing the location and cross sectional information together with the proposed design and construction details for all new retaining walls/ building retaining walls adjacent to the existing/proposed adoptable highway including PRoWs bordering the development site shall be submitted to and approved by the Highway Authority in writing. The approved scheme shall be implemented prior to the commencement of the proposed development and thereafter retained during the life of the development.

2) Before the development commences a scheme detailing the location and cross-sectional information together with the proposed design and construction details for all new surface water attenuation tanks/pipes/manholes located within the proposed highway footprint or influence zone of highway loading, whilst ensuring that oversize manholes in the highway are limited to 1.80m internal diameter, shall be submitted to and approved by the Highway Authority in writing. The approved scheme shall be implemented prior to the commencement of the proposed development and thereafter retained during the life of the development. See https://www.kirklees.gov.uk/beta/regeneration-and-development/pdf/highways-structural-procedures.pdf for further details and in particular, for the certification of oversize pcc manholes and their cover slabs, as advised in this document.

Important Notes:
All new storm water attenuation tanks/pipes/culverts with internal diameter/ spans exceeding 0.9m must be located off the adoptable highway. Any decision to locate these facilities within the adoptable highway footprint must be accompanied with a full risk evaluation report with particular reference to their proposed inspection, structural assessment and maintenance regime in compliance with the CDM Regulations 2015 requirements.
The adopting authority (i.e. Yorkshire Water) will also be required to produce and submit a legally binding agreement to the Highway Authority explicitly stating that they will be fulfilling their obligations in relation to the systematic and cyclical inspection and structural assessment of any attenuation structure located within the highway footprint, in full compliance with CS450-Inspection of Highway structures.

Furthermore, all new precast pipes/ culverts/storage tanks proposed for use within the footprint of an adoptable highway must comply with the Specification for Highway Works (SHW-Series 500 or

2500) and must be accredited with a BBA (The British Board of Agrément Roads and Bridges) or HAPAS (Highway Authority Product Approval Scheme) or equivalent certificate.

Regards

Farhad Khatibi

Bridges & Structures Manager
Structures Section
Highways and Streetscene
Kirklees Council

Highways and Streetscene | Highways Structures | Civic Centre 1 | High Street | Huddersfield | HD1 2NF

☏ **External:** 01484 221000 **Internal:** 74199
Mobile: None
✉ **Email:** farhad.khatibi@kirklees.gov.uk