

Qty 15 — Steel lighting column of 8.0 metre nominal height

Luminaire:	OrangeTEK Ignis Mini
Mounting Type:	Post top mounted at 0° tilt
Lumen Output:	5.58klm
Colour Temperature:	Neutral White (4000k)
Luminous Intensity:	G3

Qty 38 — Steel lighting column of 6.0 metre nominal height

Luminaire:	OrangeTEK Ignis Mini
Mounting Type:	Post top mounted at 0° tilt
Lumen Output:	2.27klm
Colour Temperature:	Neutral White (4000k)
Luminous Intensity:	G1

Qty 23 — 800mm solar bollard

Bollard:	Pro Solar Litecharga
Lumen Output:	0.06klm

ISOLUX CONTOUR KEY (AT GROUND LEVEL):

- 0.20 Isolux contour line
- 0.60 Isolux contour line
- 1.00 Isolux contour line
- 2.00 Isolux contour line



PRO SOLAR LITECHARGA SOLAR BOLLARD

The details provided on this drawing are subject to comments by all relevant approving authorities and/or any overseeing organisation. No construction works shall take place until technical approval has been obtained by the approving authority and/or any overseeing organisation.
It is to be understood that these drawings and the information shown are preliminary only and shall not be used for construction. This drawing should not be used for construction or procurement of materials in any way until technical approval is received.
Should the contractor commence work on site prior to obtaining technical approval, then it is entirely at their own risk and no liability shall be accepted by SHD Lighting Consultancy Ltd.

REV	DESCRIPTION	DATE	BY
R1	NEW LAYOUT AND REVISED S38 LIGHTING DESIGN 02/12/2025	10/12/2025	SRH
R0	INITIAL DESIGN FOR REVIEW AND COMMENT	28/11/2025	SRH

SHD
info@shdlighting.co.uk ☎ 07834 490 192 www.shdlighting.co.uk

PROJECT:	BLACKMOORFOOT ROAD				
DRAWING:	COMBINED LIGHT SPILL DESIGN				
CLIENT:	MILLER HOMES				
DRAWING NUMBER:	SHD2510-SHD-HLG-BLAC-DR-EO-Lighting Layout-R1			DRAWN:	SRH
	SHEET 1 OF 1			CHECKED:	SRH
				APPROVED:	
CONTRACT NUMBER:	SHD2510	DATE:	28/11/2025	SCALE @ A1	1:1000
				REVISION:	R1

PRELIMINARY DESIGN - NOT FOR CONSTRUCTION