



KEY

- 66.200 * Proposed Level.
- FOE Flag on edge retaining.
- GEO Geowall
- UB Underbuild (Extra facings below dpc)
- GB Precast concrete gravel board
- 1/106 Approx drive/path/garden gradient
- 3m "level" area

Rev	Details	Date	Drwn/Chk.
E	Hatching removed from frontage dry stone wall	6-1-26	AST
D	Amendments to plots 15, 23 & 27	12-12-25	AST
C	Updated to latest layout	4-12-25	AST
B	Layout updated.	4-11-25	AST
A	Layout updated.	22-7-25	AST

Newett Homes
Yew Tree Road
Birchencliffe, Huddersfield
External Works Plan

Dwg No. : STE/25/03/09 E
 Date : 10-3-25
 Scale : 1:200

SHAUNTONGE ENGINEERING

11 Broomhead Road, Wombwell, Barnsley, S73 0SA.
 Mobile 07528 278070 - Email shauntongeengineering@yahoo.co.uk

RISK ASSESSMENT: SIGNIFICANT RISKS THAT CANNOT BE DESIGNED OUT	LEVEL OF RISK (HM)	SUGGESTED ACTION
DEEP EXCAVATIONS ASSOCIATED WITH DEEP DRAINAGE WORKS	HIGH	ENSURE ALL EXCAVATIONS HAVE ADEQUATE TRENCH SUPPORTS AND ARE FENCED OFF TO PROTECT FROM FALLS.
HANDLING LARGE DIAMETER MANHOLE AND SOAKAWAY RINGS	HIGH	USE CORRECT LIFTING EQUIPMENT AND ENSURE OPERATIVES WEAR THE CORRECT PERSONAL PROTECTIVE EQUIPMENT.
CONTACT WITH SEWAGEWORKING IN CONFINED SPACES	MEDIUM	USE GAS DETECTORS/BREATHING EQUIPMENT AND ENSURE OPERATIVES WEAR THE CORRECT PERSONAL PROTECTIVE EQUIPMENT.
NOISE FROM MACHINERY	MEDIUM	OPERATIVES TO WEAR THE CORRECT EAR PROTECTION.
EXCAVATIONS NEAR TO UTILITIES	HIGH	UTILITY MAPS TO BE INSPECTED AND APPARATUS LOCATED USING APPROPRIATE EQUIPMENT PRIOR TO EXCAVATION.
EXCAVATIONS IN PUBLIC HIGHWAY	HIGH	ENSURE ALL EXCAVATIONS HAVE ADEQUATE TRENCH SUPPORTS AND ARE FENCED OFF TO PROTECT FROM FALLS. ENSURE THE CORRECT SIGNAGE/TRAFFIC CONTROL IS USED.

IT IS ASSUMED THAT WORKS ASSOCIATED WITH THIS DESIGN WILL BE UNDERTAKEN BY A PERSON(S) WHO ARE COMPETENT AND HAVE THE REQUIRED LEVEL OF EXPERIENCE AND EXPERTISE.