



KEY

- 50x150 Edging
- 125x255 HB 100mm face
- Drop kerb
- 125x150 BN 0-6mm face
- 125x150 BN 30mm face
- 150x150 Channel block laid flush
- 125x255 HB-BN Transition kerb
- 125x255 BN Kerb

Please refer to Road construction details for full specifications

RISK ASSESSMENT: SIGNIFICANT RISKS THAT CANNOT BE DESIGNED OUT	LEVEL OF RISK (VNI)	SUGGESTED ACTION
DEEP EXCAVATIONS ASSOCIATED WITH DEEP FOUNDATION WORKS	HIGH	ENSURE ALL EXCAVATIONS HAVE ADEQUATE TRUSS SUPPORTS AND ARE FENCED OFF TO PROTECT FROM FALLS
WALDING LARGE QUANTITY MATERIAL AND SOILWORKINGS	HIGH	USE CORRECT LIFTING EQUIPMENT AND SHIELD OPERATIVES
CONTACT WITH SERVICES/WORKING IN CONFINED SPACES	MEDIUM	USE GAS DETECTORS/RESPIRATING EQUIPMENT AND ENSURE OPERATIVES WEAR THE CORRECT PERSONAL PROTECTIVE EQUIPMENT
NOISE FROM MACHINERY	MEDIUM	OPERATIVES TO WEAR THE CORRECT EAR PROTECTION
EXCAVATIONS NEAR TO OTHERS	HIGH	UTILITY WAYS TO BE RESPECTED AND APPROPRIATE LOCATED USING APPROPRIATE EQUIPMENT FROM TO EXCAVATION
EXCAVATIONS IN PUBLIC HIGHWAY	HIGH	ENSURE ALL EXCAVATIONS HAVE ADEQUATE TRUSS SUPPORTS AND ARE FENCED OFF TO PROTECT FROM FALLS ENSURE THE CORRECT SIGNAGE/TRAFFIC CONTROL IS USED



B Layout updated 14-1-25 AST
A1 Layout updated 25-1-25 AST
Date DWI/CLK

Details
Newell Homes

Yew Tree Road
Birchenclyffe, Huddersfield

Section 38 Kerbing plan

Dwg No.: STE25/03/04 B

Date: 7-3-25

Scale: 1:500

Copyright © Shaun Tonge Engineering

SHAUN TONGE
ENGINEERING

11 Broomfield Road, Wortwell, Barnley, S73 0SA.
Mobile 01758 278070 Email Shauntongeengineering@bt.co.uk