

HILLCREST VIEW, GOLCAR

Kirklees Council

Proposed Equipment Schedule

31 July 2022



info@shdlighting.co.uk 07834 490 192 www.shdlighting.co.uk

SHD666-SHD-HLG-HILL-SH-EO-Lighting Schedule-R0

Proposed Unit No.	Easting Coordinates	Northing Coordinates	Location	Unit Description	Service Connection Type	Primary Isolator Detail	Secondary Isolator / Termination Type Detail
LC01	N/A	N/A	Refer to 'SHD666-SHD-HLG-HILL-DR-EO-Lighting Layout-R0' S38 street lighting design drawing	Proposed galvanised tubular steel lighting column of 6.0 metre nominal height with a planted base and glass flake epoxy root treatment Kirklees Council street lighting specification (Refer to 'HD-SD-13-01A-A4 Landscape' standard detail drawing) with post top mounted at 0° tilt. OrangeTek Ignis Mini 2.17km 14w 4000k LED luminaire with Lucy Zodion ZCELL 20 lux (1:1 ratio) photo electric control unit mounted in 7 pin NEMA socket. Refer to SHD666-SHD-HLG-HILL-DR-EO-Lighting Layout-R0' for dimming regime.	Proposed IDNO Supply Connection	IDNO approved double pole isolator	N/A
LC02	N/A	N/A	Refer to 'SHD666-SHD-HLG-HILL-DR-EO-Lighting Layout-R0' S38 street lighting design drawing	Proposed galvanised tubular steel lighting column of 6.0 metre nominal height with a planted base and glass flake epoxy root treatment Kirklees Council street lighting specification (Refer to 'HD-SD-13-01A-A4 Landscape' standard detail drawing) with post top mounted at 0° tilt. OrangeTek Ignis Mini 2.17km 14w 4000k LED luminaire with Lucy Zodion ZCELL 20 lux (1:1 ratio) photo electric control unit mounted in 7 pin NEMA socket. Refer to SHD666-SHD-HLG-HILL-DR-EO-Lighting Layout-R0' for dimming regime.	Proposed IDNO Supply Connection	IDNO approved double pole isolator	N/A
LC03	N/A	N/A	Refer to 'SHD666-SHD-HLG-HILL-DR-EO-Lighting Layout-R0' S38 street lighting design drawing	Proposed galvanised tubular steel lighting column of 6.0 metre nominal height with a planted base and glass flake epoxy root treatment Kirklees Council street lighting specification (Refer to 'HD-SD-13-01A-A4 Landscape' standard detail drawing) with post top mounted at 0° tilt. OrangeTek Ignis Mini 2.17km 14w 4000k LED luminaire with Lucy Zodion ZCELL 20 lux (1:1 ratio) photo electric control unit mounted in 7 pin NEMA socket. Refer to SHD666-SHD-HLG-HILL-DR-EO-Lighting Layout-R0' for dimming regime.	Proposed IDNO Supply Connection	IDNO approved double pole isolator	N/A

NOTE: NUMBERS SHOWN ON THE SCHEDULE AND DESIGN DRAWING ARE FOR IDENTIFICATION PURPOSES ONLY - ACTUAL COLUMN NUMBERS TO BE SPECIFIED BY LOCAL AUTHORITY LIGHTING DEPARTMENT OR OVERSEEING ORGANISATION.