

**Consultation Response from Alan Smith,
KC Waste Strategy (Refuse & Recycling)**

2026/90197 adj, 84, James Street, Golcar, Huddersfield, HD7 4HT

Erection of detached single storey dwelling

Date Responded: 17/02/2026

Responding Officer: Alan Smith

Responding Ref: WPS 26 005

1. Introduction

This response is provided by the Waste Collection Authority (WCA) and outlines operational requirements for waste storage and collection. These comments aim to support compliance with Kirklees Local Plan policies LP24 (d.vi), LP43, the Waste Management Design Guide and the Highway Design Guide SPD. The aim is to achieve a safe and efficient waste collection service.

Section 45(1)(a) of the Environmental Protection Act 1990 places a duty on the Waste Collection Authority (WCA) to arrange for the collection of household waste within its area. Regardless of whether a private contractor is engaged, the WCA must ensure that there is adequate on-site waste storage capacity, suitable access for collection vehicles, and that, should the responsibility for collection revert to the WCA in the future, the process can be carried out efficiently.

The Council takes the issue of bin blight seriously and encourages developers to ensure that the street scene for new developments is not spoilt by the poor design for refuse storage and collection.

Clarification is required about how this application will affect the bin storage areas confirmed in Planning Application 2014/91176 for 84 James Street.

2. Waste Storage Requirements

The dwelling must accommodate:

- **3 x 240 L wheeled bins for:**
 - Residual waste – collected on alternative weeks
 - Recyclable waste – collected on alternative weeks
 - Garden waste – paid for service collected fortnightly (or future Simpler Recycling legislation provision)
- **Bin space dimensions:**
 - floor space required is 940 mm x 780 mm per bin
- **Bin storage location:**
 - Must not obstruct highways or driveways
 - Be in rear gardens, gated access must be secure and wide enough for bins to pass through
 - No gradients steeper than 1:12 or steps

3. Bin Collection Points (BCPs)

- Must be shown on a layout plan for all properties
- No gradients steeper than 1:12 or steps from storage area to BCP
- Located adjacent to an adoptable highway

- Solid surface required, resistant to constant wear and tear
- The maximum drag out distance from bin storage area to BCP is 25 m (BS5906:2005)

4. Refuse Collection Vehicle (RCV) Access

- The WCA will not enter:
 - Private drives
 - Roads not built to an adoptable standard
 - Active construction sites
- Road layout must:
 - Enable looped access (preferred over cul-de-sacs)
 - Where applicable, turning heads must be suitable for an 11.85 m RCV
 - Turning areas must be made active to avoid them being used for additional parking
- Reversing distance for an RCV must not exceed 12 m (WISH guidance)

5. Requested Planning Conditions

- **Pre-Occupation Waste Strategy**
Prior to commencement the developer must submit for approval details for bin storage, screening, BCPs, and RCV access. The approved details shall be provided before first occupation and shall be so retained thereafter.

6. Policy Context

- **LP24 (d.vi):** Requires unobtrusive, well-designed waste facilities
- **LP43:** Supports waste minimisation and recovery
- **National Planning Policy for Waste (5.8):** Adequate storage facilities at residential premises

7. Design Guidance References

- [Waste Management Design Guide for New Developments](#)
- [Kirklees Highway Design Guide SPD](#)
- [Kirklees Local Plan Strategy and Policies](#)
- [Avoiding Rubbish Design Guide](#)
- [Building for a Healthy Life \(2020\)](#)
- [Building Regulations 2010 Part H6](#)
- [Safety Distances Between Waste Containers and Buildings](#)
- BS5906:2005 Waste Management in Buildings