

LEGEND

- Asphalt Concrete (Vehicular Grade)
- Asphalt Concrete (Pedestrian Grade)
- Permeable PCC Concrete Block Paving Type 1
- Permeable PCC Concrete Block Paving Type 2
- Permeable PCC Concrete Block Paving Type 3
- Concrete Hardstanding
- Asphalt Concrete Multi Use Games Area (HPE25)
- Cycle Parking (40 Spaces)
- Accessible Cycle Parking (2 spaces)
- External Canopy
- 1.8m high Timber Close Board Fence with Matching Lockable Gate (with other fence types)
- 3.0m high Sport Weldmesh Fencing (with matching lockable gates where indicated)
- 2.4m high Secure Weldmesh Fencing (with matching lockable gates where indicated)
- 1.8m high Secure Weldmesh Fencing (with matching lockable gates where indicated)
- 1.2m high Bow Top Fencing (with matching lockable gates where indicated)
- 900mm high Diamond Knee Rail
- Existing Fence Retained (Subject to condition)
- Active EV Charging Bays (4)
- Accessible Bays (2)
- Seats
- Benches
- Legacy Furniture Relocated (Subject to condition)
- Legacy Storage Units
- Legacy Cycle Storage Retained (Subject to condition)
- Adventure Play Equipment (Spec tbc.)
- Storage Container
- Removable Bollard
- Proposed Dwarf Wall
- Proposed Tree Planting
- Native Hedge Planting
- Species Rich Ornamental Planting
- Species Rich Native Shrub Planting
- Amenity Grass
- Existing Grassland & Vegetation Retained & Enhanced
- Existing Trees & Vegetation Retained
- Existing Trees & Vegetation Removed

- Existing spot level
- 0.000 Proposed spot level [footpath/ general]
- 125.800 Proposed spot level [carriageway]
- 125.800 Proposed spot level [soft landscape]
- 125.600 Proposed surface gradient [footpath/ general]
- 1:x Proposed surface gradient [carriageway]
- 1:x Proposed surface gradient [soft landscape]

NOTES

REVISION	DATE	BY	CHECKED	
C01	16.10.25	NB	KP	End of Stage 3
P04	11.11.25	GS	KP	Start Of Stage 4
P05	17.11.25	KP	JE	3no. existing trees removed for construction access (east boundary) 3 replacements proposed in the same location.
P01	19.05.25	HN	KP	First issue
P02	28.05.25	HN	KP	Revised in accordance with CEM6 feedback. 1.2m high timber fencing changed to 1.2m high bow top metal fencing
P03	16.06.25	KP	JE	Application boundary revised to include rugby field access. Car park turning head amended in accordance with latest swept path analysis. Planting numbers updated in accordance with BNG.

CLIENT	Bowmer + Kirkland		
PROJECT	Co-Op Academy Smithies Moor		
DRAWING TITLE	Site Landscaping Plan Sheet 1 of 2		
DRAWING No.	SRP1128-ONE-ZZ-XX-D-L-0011	REVISION	P05
STATUS	PRELIMINARY		
SCALE	1:200 @ A1	DATE 19.05.25	DRAWN BY HN

0 2 4 8 metres 1:200

ONE-ENVIRONMENTS

©One-Environments Ltd. This drawing is not to be scaled. All dimensions to be verified on site prior to commencement of works. Discrepancies, ambiguities and/or omissions between this drawing & information supplied by others must be reported immediately for clarification before proceeding