



N
O
T
E
S

ATTENTION IS DRAWN TO THE REQUIREMENTS OF THE CONSTRUCTION DESIGN AND MANAGEMENT REGULATIONS 2015 AND THE DUTIES AND RESPONSIBILITIES CONTAINED THEREIN

Key	Description
	Residential Street: 30mm thick 0/6mm NS dense surface course AC.6 dense surf 100/150
	Vehicular crossing: 25mm thick 0/6mm NS dense surface course AC.6 dense surf 100/150
	Footway: 25mm thick 0/6mm NS dense surface course AC.6 dense surf 100/150
	Black Paved Carriageway: 80mm thick block pavers on 30mm thick naturally occurring silica sand
	Hard margins: 80mm thick block pavers on 30mm thick naturally occurring silica sand
	Residential Street tie-in: 30mm thick 0/6mm NS dense surface course AC.6 dense surf 100/150
	Footway tie-in: 25mm thick 0/6mm NS dense surface course AC.6 dense surf 100/150

REFER TO DRAWING(S) 2298/03/04 FOR FULL CONSTRUCTION DETAILS

1. No water should be allowed to discharge from any private drives onto the adoptable highway.

2. All highway works are to be the subject of a Section 38 Agreement of the highways Act 1980.

3. Any coated base material in carriageway left exposed for more than seven days to be sealed using bituminous sealing grit.

4. Highway boundary to be indicated by back edgings laid flush or change of material on Private drives.

5. All vertical faces of joints involving flexible materials shall be treated with an approved joint sealant. This includes ironwork, and precast products. Overbanding will not be accepted.

6. Do not scale from this drawing.

SUBJECT TO THE APPROVAL OF ALL RELEVANT AUTHORITIES

D	IC	05.06.26	Updated to suit road and FFL updates.	MI
C	IC	27.04.26	Minor update on entrance works.	MI
B	IC	26.02.26	Minor updates.	MI
A	MI	29.01.26	Updated to suit planning layout 1187-EA-A-C301D	MI
/	IC	14.11.25	Issued for approval	AAA
Rev	By	Date	Revision	Appd.

ARP ASSOCIATES
Chartered Consulting Engineers

Northwest House • 5 & 6 Northwest Business Park • Servia Hill, Leeds • LS6 2QH
0113 245 8498 • 0113 244 3864 • leeds@arpassociates.co.uk • www.arpassociates.co.uk
ARP Associates is a trading division of ARP Geotechnical Ltd, a company registered in England and Wales with company number 3773831, whose registered office is at 5/6 Northwest Business Park, Servia Hill, Leeds LS6 2QH

TITLE

SECTION 38
SURFACING LAYOUT

PROJECT

COCKLEY HILL,
KIRKHEATON

CLIENT

GLEESON HOMES

DRAWING STATUS

PRELIMINARY

Scale

1:500 @ A1

Date

NOV 25

Drawn

IC

Chk.

MI

Drg. No.

2298/03/02.02

Rev

D