



**N O T E S**

ATTENTION IS DRAWN TO THE REQUIREMENTS OF THE CONSTRUCTION DESIGN AND MANAGEMENT REGULATIONS 2015 AND THE DUTIES AND RESPONSIBILITIES CONTAINED THEREIN

| Ref | Colour     | Description                                    | Kerb face Upstand |
|-----|------------|--|-------------------|
| 1   | Red        | 125 x 255 Hoff Battered Kerb                   | 100mm             |
| 2   | Orange     | 125 x 150 Bullnosed Kerb (Vehicle Crossing)    | 25mm              |
| 3   | Green      | 50 x 150 Edging                                | NA                |
| 4   | Blue       | Transition Taper Kerb                          | NA                |
| 5   | Pink       | 125 x 150 Bullnosed Kerb (Pedestrian Crossing) | 0-6mm             |
| 6   | Yellow     | 150 x 150 Channel Block                        | NA                |
| 7   | Light Blue | Transition Across Ramp                         | NA                |

REFER TO DRAWING(S) 2298/03/04 FOR FULL CONSTRUCTION DETAILS

1. Dropped kerbs and tactile pavings are required at the junctions to facilitate the movement of wheelchairs etc. The dropped kerbs to be laid with a 0-6mm upstand.
2. All highway works are to be the subject of a Section 38 Agreement of the highways Act 1980.
3. Any coated base material in carriageway left exposed for more than seven days to be sealed using bituminous sealing grit.
4. Highway boundary to be indicated by back edgings laid flush or change of material on Private drives.
5. All vertical faces of joints involving flexible materials shall be treated with an approved joint sealant. This includes ironwork, and precast products. Overbanding will not be accepted.
6. Do not scale from this drawing.

SUBJECT TO THE APPROVAL OF ALL RELEVANT AUTHORITIES

|     |    |          |   |       |
|-----|----|----------|---|-------|
| B   | IC | 26.02.26 | Updated to suit planning layout 1187-EA-A-C301D | MI    |
| A   | MI | 29.01.26 | Updated to suit planning layout 1187-EA-A-C301D | MI    |
| /   | IC | 14.11.25 | Issued for approval                             | MI    |
| Rev | By | Date     | Revision  | App'd |

**ARP** ARP ASSOCIATES  
Chartered Consulting Engineers

Northwest House • 5 & 6 Northwest Business Park • Servia Hill, Leeds • LS6 2QH  
0113 245 8498 • 0113 244 3864 • leeds@arpassociates.co.uk • www.arpassociates.co.uk

ARP Associates is a trading division of ARP Geotechnical Ltd, a company registered in England and Wales with company number 3778313, whose registered office is at 5/6 Northwest Business Park, Servia Hill, Leeds LS6 2QH

TITLE  
**SECTION 38  
KERBING LAYOUT**

PROJECT  
**COCKLEY HILL,  
KIRKHEATON**

CLIENT  
**GLEESON HOMES**

DRAWING STATUS  
**PRELIMINARY**

|            |        |       |    |
|------------|--------|-------|----|
| Scale      | Date   | Drawn | IC |
| 1:500 @ A1 | NOV 25 | Chk.  | MI |

|          |               |     |   |
|----------|---------------|-----|---|
| Org. No. | 2298/03/02.03 | Rev | B |
|----------|---------------|-----|---|

SUBJECT TO THE APPROVAL OF ALL RELEVANT AUTHORITIES