



**LAND ADJACENT
482 HALIFAX ROAD
HIGHTOWN
LIVERSEDGE
WF15 8EB**

Drainage Strategy

**DOCUMENT No:
25097-DSR-001-A**

5th JANUARY 2026

Issue Sheet.

Prepared	Date		Checked	Date
RR	05.01.26		MJM	05.01.26

Revisions	Comment	Date
A	Initial Issue	05.01.26

The report is based on the information that has been acquired and / or made available to Advant Engineers via the various searches and consultations undertaken as part of the Drainage Strategy. In some cases, anecdotal information has been relied upon, where documented evidence has been lacking.

The conclusions drawn in the above report are considered correct although any subsequent additional information may allow refinement of the conclusions.

All work carried out in preparing this report has utilised and is based upon Advant Engineers current professional knowledge and understanding of current UK standards and codes, technology and legislation. Changes in this legislation and guidance may occur at any time in the future and cause any conclusions to become inappropriate or incorrect.

This report has been prepared using information contained in maps and documents prepared by others. Advant Engineers can accept no responsibility for the accuracy of such information.

Table of Contents

Table of Contents.....3

1. Introduction.....4

2. Existing Site.....4

3. Proposed Development5

4. Drainage Strategy.....6

5. SUDS Elements8

6. SUDS Maintenance.....9

7. Flood Exceedance Events12

8. Conclusion12

APPENDIX A SEWER RECORDS.....13

APPENDIX B PROPOSED LAYOUT14

APPENDIX C GREENFIELD CALC.....15

APPENDIX D PROPOSED DRAINAGE LAYOUT16

APPENDIX E DRAINAGE CALCS17

APPENDIX F FLOOD EXCEEDANCE PLAN18

1. Introduction


- 1.1. Advant Engineers has been commissioned by Cedar Building Solutions, to undertake a Drainage Strategy in connection with the proposed development at the land off Halifax Road, Liversedge. The proposal consists of 2 new build dwellings with associated parking and access road.
- 1.2. This report should be read in conjunction with drawing 25097-101 and associated architectural and engineering drawings.

2. Existing Site

- 2.1. The site currently is a greenfield piece of land at the rear of No. 482 with no existing development and located off Halifax Road and access via a driveway that runs along the gable end of No.482, the overall site area is 1,194m² (0.119ha).
- 2.2. This site can be located at the following co-ordinates 418735E, 424056N and the nearest postcode is WF15 8EB and can be seen on the below extract.



- 2.3. No site investigation has been received at this point, we have therefore referred to the BGS website which describes the site as below.



- 2.4. There is a public surface water and combined sewers located under the public highway to the south of the site. (See Appendix A for sewer records).


3. Proposed Development

- 3.1. The proposed development is for 2 new build dwellings with associated parking and a new private driveway into the site. (See Appendix B for layout)

4. Drainage Strategy

4.1. Surface Water

- 4.2. The surface water drainage should be designed in accordance with the SUD hierarchy providing evidence to each step before moving on to the next one, the SUDS hierarchy is as follows:



- 4.3. In the first instance the reuse of water on site should be implemented, we have achieved this with the use of water butts in the rear gardens, however this on its own does not provide attenuation on site.
- 4.4. Based on the BGS website and the constrained nature of the site it is expected that infiltration may not be feasible, therefore we have discounted it at this point.
- 4.5. The next level on the hierarchy is discharge to a watercourse, as there are no watercourses in the vicinity of the site then this has been discounted as an option.
- 4.6. Next would be to discharge to a surface water sewer, it is proposed to discharge to the public surface water sewer via an existing connection located on the adjacent site at a controlled rate.

- 4.7. As the site is greenfield then greenfield rates should be utilised as the discharge rate back to the public surface water sewer, the greenfield rates for this site are as follows: (See Appendix C for calc).

$$\begin{aligned} \text{QBAR} &= 0.60 \text{ l/s} \\ 1 \text{ in } 1 \text{ Year} &= 0.50 \text{ l/s} \\ 1 \text{ in } 30 \text{ Year} &= 1.10 \text{ l/s} \\ 1 \text{ in } 100 \text{ Year} &= 1.30 \text{ l/s} \end{aligned}$$

- 4.8. The above rates would require such a small orifice that it would be at risk of blockages, we are therefore proposing to restrict the discharge to **0.5 l/s** which requires a 32mm orifice and attenuate the **1 in 100 Year + 40%** climate change rainfall event on site in the subbase of the permeable paving. (See Appendix D for Drainage Layout and Appendix E for drainage calcs).

4.9. Foul Drainage

- 4.10. The foul drainage is proposed to connect into the public foul sewer under Halifax Road via an existing connection on the adjacent site.

5. SUDS Elements

5.1. All new surface water drainage systems should implement SUDS features where reasonably possible, these features are incorporated to offer benefits in Water Quality, Water Quantity, Amenity and Biodiversity. Below we have considered each SUDS element and determined its use within this particular development

COMPONENT	SUITABILITY	REASON
Rainwater Harvesting	✓	Water butts have been proposed in each rear garden
Green Roof	X	Roof not suitable for a Green Roof.
Blue Roof	X	Roof not suitable for a Blue Roof.
Infiltration Systems	X	Ground conditions not suitable
Proprietary Treatment Systems	✓	Flow control to be installed.
Filter Strips	X	Ground conditions not suitable
Filter Drains	X	Ground conditions not suitable
Swales	X	Ground conditions not suitable
Bioretention Systems	X	Utilising permeable paving in place
Trees	✓	New trees are being proposed as part of the new landscaping
Rain Garden	X	More practical solutions are available.
Pervious Pavements	✓	Permeable paving on driveway and parking bays are being included.
Attenuation Storage Tanks	X	Permeable paving used for storage
Detention Basins	X	Permeable paving used for storage
Ponds and Wetlands	X	Permeable paving used for storage

6. SUDS Maintenance

- 6.1. Upon selection of the SUDS elements to be incorporated into the surface water drainage scheme then a maintenance plan needs to be adopted along with responsibility of the maintenance.
- 6.2. The responsibility can general be with 3 different bodies, it could be 'Private' which means the responsibility remains with the homeowner, it could be 'Public' which means it will be adopted and be the responsibility of the local authority or water authority, or it could be 'Management Company' which means a specialist company could be employed or created for the purpose of maintaining those elements, for the management company there would be an annual charge that the home owners would be expected to pay each year.

	PRIVATE	PUBLIC	MANAGEMENT
Rainwater Harvesting	✓		
Flow Control Device	✓		
Pervious Pavements	✓		

- 6.3. With each element the relevant responsible person(s) / company will need to undertake different tasks on varying frequencies to ensure the peak performance of the SUDS system and remove the risk of flooding or failure, the maintenance regime and regularity for each element are outlined in the tables below.

6.4. Rainwater Harvesting

Maintenance schedule	Required action	Typical frequency
Regular maintenance	Inspection of the tank for debris and sediment build-up, inlets/outlets/withdrawal devices, overflow areas, pumps, filters	Annually (and following poor performance)
	Cleaning of tank, inlets, outlets, gutters, withdrawal devices and roof drain filters of silts and other debris	Annually (and following poor performance)
Occasional maintenance	Cleaning and/or replacement of any filters	Three monthly (or as required)
Remedial actions	Repair of overflow erosion damage or damage to tank	As required
	Pump repairs	As required

6.5. Flow Control Device

An example of operation and maintenance requirements for a proprietary treatment system		
Maintenance schedule	Required action	Typical frequency
Routine maintenance	Remove litter and debris and inspect for sediment, oil and grease accumulation	Six monthly
	Change the filter media	As recommended by manufacturer
	Remove sediment, oil, grease and floatables	As necessary – indicated by system inspections or immediately following significant spill
Remedial actions	Replace malfunctioning parts or structures	As required
Monitoring	Inspect for evidence of poor operation	Six monthly
	Inspect filter media and establish appropriate replacement frequencies	Six monthly
	Inspect sediment accumulation rates and establish appropriate removal frequencies	Monthly during first half year of operation, then every six months

6.6. Pervious Pavements

Maintenance schedule	Required action	Typical frequency
Regular maintenance	Brushing and vacuuming (standard cosmetic sweep over whole surface)	Once a year, after autumn leaf fall, or reduced frequency as required, based on site-specific observations of clogging or manufacturer's recommendations – pay particular attention to areas where water runs onto pervious surface from adjacent impermeable areas as this area is most likely to collect the most sediment
Occasional maintenance	Stabilise and mow contributing and adjacent areas	As required
	Removal of weeds or management using glyphosate applied directly into the weeds by an applicator rather than spraying	As required – once per year on less frequently used pavements
Remedial Actions	Remediate any landscaping which, through vegetation maintenance or soil slip, has been raised to within 50 mm of the level of the paving	As required
	Remedial work to any depressions, rutting and cracked or broken blocks considered detrimental to the structural performance or a hazard to users, and replace lost jointing material	As required
	Rehabilitation of surface and upper substructure by remedial sweeping	Every 10 to 15 years or as required (if infiltration performance is reduced due to significant clogging)
Monitoring	Initial inspection	Monthly for three months after installation
	Inspect for evidence of poor operation and/or weed growth – if required, take remedial action	Three-monthly, 48 h after large storms in first six months
	Inspect silt accumulation rates and establish appropriate brushing frequencies	Annually
	Monitor inspection chambers	Annually

7. Flood Exceedance Events

- 7.1. Although the surface water drainage has been designed to accommodate the 1 in 100 year + 40% climate change rainfall event with no flooding, we have to consider events that exceed this and what happens to any flooding that may occur.
- 7.2. To illustrate this event, we have produced a Flood Exceedance Layout plan (See Appendix F for layout) and from this we can see that flood would occur at the flow control manhole and then would flow towards the road and then follow the road as per the original contours of the site.

8. Conclusion

- 8.1. Advant Engineers were commissioned by Cedar Building Solutions to undertake a Drainage Strategy for the proposed residential development at the land off Halifax Road, Liversedge. This report will be provided as supporting documentation as part of a planning application.
- 8.2. The site is currently greenfield, and it is 1,1194m² (0.119ha).
- 8.3. It is proposed to discharge the surface water to the public surface water sewer via an existing connection on the adjacent site.
- 8.4. The surface water will be restricted to 0.5 l/s for the 1 in 100 year + 40% climate change rainfall event with attenuation provided in the subbase of the permeable paving.
- 8.5. Foul drainage is to be discharged to the public combined sewer under Halifax Road via an existing connection on the adjacent site.
- 8.6. The flood exceedance event allows water flows to follow the road and match the existing undeveloped overland flows.
- 8.7. All public surface water/foul water drainage should be designed in accordance with the Water Authority and Sewers for Adoption.
- 8.8. All private surface water and surface water/foul water drainage should be designed in accordance with the current Building Regulations Part H.

**APPENDIX A
SEWER RECORDS**

YORKSHIRE WATER PROTECTION OF MAINS AND SERVICES

1. The position of Yorkshire Water Services Ltd (YWS) apparatus shown on the existing mains record drawing(s) indicates the **general** position and nature of our apparatus and the accuracy of this information cannot be guaranteed. Any damage to YWS apparatus as a result of your works may have serious consequences and you will be held responsible for all costs incurred. Prior to commencing major works, the exact location of apparatus must be determined on site, if necessary by excavating trial holes. The actual position of such apparatus and that of service pipes which have not been indicated must be established on site by contacting the Customer Helpline on 0845 124 24 24 for both water and sewerage.
2. The public sewer and water network is lawfully retained in its existing position and the sewerage and water undertaker is entitled to have it remain so without any disturbance. The provisions of section 159 of the Water Industry Act 1991 provides that the undertaker may "inspect, maintain, adjust, repair or alter" the network. Those rights are given to enable the undertaker to perform its statutory duties. Any development of the land or any other action that unacceptably hindered the exercise of those rights would be unlawful. The provisions contained in Section 185 of the Water Industry Act 1991 state that where it is reasonable to do so, a person may require the water supply undertaker to alter or remove a pipe where it is necessary to enable that person to carry out a proposed change of use of the land. The provisions contained in Section 185 also require the person making the request to pay the full cost of carrying out the necessary works.
3. Ground levels over existing YWS apparatus are to be maintained. Sewers in highways will **generally** be laid to give 1200mm of cover from finished ground level working to kerb races, other permanent identification of the limits of the road or to an agreed line and level. Substantial increases or decreases to this 1200mm depth of cover will result in the sewer being re-laid at your expense. Water mains and services will **generally** be laid with a minimum of 750mm depth of cover however some mains and services usually those installed over 50 years ago may have less ground cover.
4. If surface levels are to be decreased / increased significantly the effects on existing water supply apparatus will be carefully considered and if any alterations are necessary, the costs of the alterations will be recharged to you in full. Outlets on fire hydrants must be no more than 300mm below the new levels and all surface boxes must be adjusted as part of the scheme.
5. To enable future repair works to be carried out without hindrance; any pipe, cable, duct, etc. installed parallel to a water main or service pipe should not be installed directly over or within 300mm of a water main or service pipe or 1000mm of a waste water asset. Where a pipe, cable, duct, etc. crosses a main or service it should preferably cross perpendicular or at an angle of no less than 45° and with a minimum clearance of 150mm. These requirements apply to activities within an existing highway and are relevant to the installation of pipes, cables, ducts, etc. up to and including 250mm in diameter (*see illustration below*). Necessary protection measures for installations greater than 250mm in diameter and/or in private land will need to be agreed on an individual basis. Installations within a new development site must comply with the National Joint Utilities Group publication Volume 2: NJUG Guidelines On The Positioning Of Underground Utilities Apparatus For New Development Sites.
6. All excavation works near to YW apparatus should be by hand digging only.
7. Backfilling with a suitable material to a minimum 300mm above YW apparatus is required.
8. Adequate support must be provided where any works pass under YW apparatus.
9. Jointing chambers, lighting columns and other structures must be installed in such a way that future repair or maintenance works to YW apparatus will not be hindered.
10. Apparatus such as; railings, sign posts, etc. must not be placed in such a way that they prevent access to or full operation of controlling valves, hydrants or similar apparatus. YWS surface boxes must not be covered or buried. Any adjustment, alteration or replacement of manhole covers must be agreed on site prior to the commencement of the works with a YWS Inspector who may be contacted via our Call Centre on 0845 124 24 24.
11. Explosives shall not be used within 100 metres of any Yorkshire Water Services apparatus or installations.
12. Vibrating plant should not be used directly over any apparatus. Movement or operation by vehicles or heavy plant is not to be permitted in the immediate vicinity of YWS plant or apparatus unless there has been prior consultation and, if necessary, adequate protection provided without cost to YWS.
13. **Under no circumstances** should thrust boring or similar trenchless techniques commence until the actual position of the Company's mains/services along the proposed route have been confirmed by trial holes.
14. Any alterations to the highway should be notified following the procedures outlined in the New Road and Street Works Act 1991 Code of Practice; Measures Necessary Where Apparatus Is Affected By Major Works (Diversionary Works).
15. You will be held responsible for any damage or loss to YWS apparatus during and after completion of work, caused by yourselves, your servant or agent. Any damage caused or observed to YWS plant or apparatus should be immediately reported to YWS. Should YW incur any costs as a result of non-compliance with the above, all costs will be rechargeable in full.
16. You should ensure that nothing is done on the site to prejudice the safety or operation of YWS employees, plant or apparatus.
17. In accordance with the New Roads and Street Works Act 1991, Chapter 22, Part 3, Section 80. The location of any identified YW asset "which is not marked, or is wrongly marked, on the records made available" should be communicated back to Yorkshire Water. The location of the apparatus should be identified on copies of the supplied plans which should be returned to Yorkshire Water (Asset Records Team) with photographic supporting evidence where possible.
18. The Government has decided that responsibility for private sewers serving two or more properties and lateral drains (the section of pipe beyond the boundary of a single property, connecting it to the public sewer) will be transferred to the water companies on Oct 1 2011.


Private pumping stations will also transfer during the period 1 October 2011 – 1 Oct 2016. Records of these assets may not yet be shown on the existing mains record drawing(s). If you encounter any of these assets you must inform Yorkshire Water Services Ltd (YWS).

19. Please note that the information supplied on the enclosed plans is reproduced from Ordnance Survey material with the permission of the Ordnance Survey on behalf of the Controller of Her Majesty's Stationery Office, © Crown Copyright. Unauthorised reproduction infringes Crown Copyright and may lead to prosecution or civil proceedings. Licence Number 1000019559.
20. This information is for guidance only and the position and depth of any YW apparatus is approximate only. Likewise, the nature and condition of any YW apparatus cannot be guaranteed. YW has no responsibility for recording the locations of privately owned apparatus. As of 1 October 2011, there may be some lateral drains and/or public sewers which are not documented on YW records but may still be present. For the avoidance of doubt, this information is not a substitute for appropriate professional and/or legal advice. YW accepts no responsibility for any inaccuracy or omissions in this information. The actual position of YW apparatus must be determined on site by excavating trial holes by hand. YW requires a minimum of two working days' written notice of the intention to excavate any trial holes before any excavation can be undertaken. If there are any queries in this respect please contact Yorkshire Water on 0845 124 24 24.

Property Identifier





Sewer Legend




Please note that the direction of flow arrows may not always appear depending on the scale of the map.

Water Legend





Public Clean Water Network 01/08/2024 09:04:50 OS Grid Coordinates: 418482 : 423689 Map Name : SE1823NW svcGISSafeMovePD




Public Waste Water Network 01/08/2024 09:04:54 OS Grid Coordinates: 418482 : 423689 Map Name : SE1823NW svcGISSafeMovePD

**APPENDIX B
PROPOSED LAYOUT**



Proposed Site Plan

1 : 500




CLIENT
Cedar Building Solutions

PROJECT
Land Adj. to 482 Halifax Road
Hightown
Liversedge
WF15 8DX

DRAWING TITLE
Proposed Site Plan - Bungalows

STATUS
S4 - Planning

Proj Ref	Origin	Zone	Level	Type	Role	Num	Status	Rev
90097	BAS	00	00	DR	A	00100	S4	-
Sheet	Scale	Issue Date	Drwn by	Ckd by				
A3	1 : 500	13-03-23	CW	AB				



REV	DESCRIPTION	DATE	ISSUED BY
-----	-------------	------	-----------

ISSUE/REVISION HISTORY



Unit 9, Victoria Spring Business Park
Liversedge, West Yorkshire WF15 6BU

NOTES
Do not scale from this drawing. Only figured dimensions are to be taken from this drawing. Contractor must verify all dimensions on site before commencing any work or shop drawings. Report any discrepancies to the architect before commencing work. If this drawing exceeds the quantities taken in any way the architects are to be informed before the work is initiated. Work within the Construction (Design & Management) Regulations 2015 is not to start until a Health and Safety Plan has been produced. This drawing is copyright and must not be reproduced without consent of Barnes Architectural Services Ltd

DRAWING STATUS/TITLE KEY			
S0	Feasibility	S2	Sketch
L	Landscape	D4	Construction
S4	Planning	Z	Marketing
B	Building Survey	B3	As Built
D2	Tender	Z	Tenant
OS	Ordnance Survey		

**APPENDIX C
GREENFIELD CALC**


This is an estimation of the greenfield runoff rates that are used to meet normal best practice criteria in line with Environment Agency guidance “Rainfall runoff management for developments”, SC030219 (2013), the SuDS Manual C753 (CIRIA, 2015) and the non-statutory standards for SuDS (Defra, 2015). This information on greenfield runoff rates may be the basis for setting consents for the drainage of surface water runoff from sites.

Project details

Date	05/01/2026
Calculated by	Reship Raina
Reference	
Model version	2.2.2

Location

Site name	
Site location	



Site easting (British National Grid)	418758
Site northing (British National Grid)	424086

Site details

Total site area (ha)	0.1194	ha
----------------------	-------------------------------------	----

Greenfield runoff

Method

Method	IH124
--------	-------

IH124

	<u>My value</u>		<u>Map value</u>
SAAR (mm)	762	mm	762
How should SPR be derived?	WRAP soil type		
WRAP soil type	4		4
SPR	0.47		
QBar (IH124) (l/s)	0.6	l/s	

Growth curve factors

	<u>My value</u>		<u>Map value</u>
Hydrological region	3		3
1 year growth factor	0.86		
2 year growth factor	0.94		
10 year growth factor	1.45		
30 year growth factor	1.75		
100 year growth factor	2.08		
200 year growth factor	2.37		

Results


Method	IH124	
Flow rate 1 year (l/s)	0.5	l/s
Flow rate 2 year (l/s)	0.6	l/s
Flow rate 10 years (l/s)	0.9	l/s
Flow rate 30 years (l/s)	1.1	l/s
Flow rate 100 years (l/s)	1.3	l/s
Flow rate 200 years (l/s)	1.5	l/s

Please note runoff estimation is subject to significant uncertainty. Results are therefore normally reported to only 1 decimal place. Where 2 decimal places are provided, this does not indicate accuracy to this level, it has been adopted to prevent ‘zero’ figures from being reported. Outputs less than 0.01 l/s are reported as 0.01 l/s.

Disclaimer

This report was produced using the Greenfield runoff rate estimation tool (2.2.2) developed by HR Wallingford and available at [uksuds.com](https://www.uksuds.com/) (<https://www.uksuds.com/>). The use of this tool is subject to the UK SuDS terms and conditions and licence agreement, which can both be found at [uksuds.com/terms-conditions](https://www.uksuds.com/terms-conditions) (<https://www.uksuds.com/terms-conditions>). The outputs from this tool have been used to estimate Greenfield runoff rates. The use of these results is the responsibility of the users of this tool. No liability will be accepted by HR Wallingford, the Environment Agency, Centre for Ecology and Hydrology, Wallingford Hydrosolutions or any other organisation for the use of these data in the design or operational characteristics of any drainage scheme.

**APPENDIX D
PROPOSED DRAINAGE LAYOUT**



COVER AND INVERTS OF EXISTING SEWERS SHOULD BE CHECKED ON SITE PRIOR TO CONSTRUCTION

ALL RWP AND SVP'S TO BE CHECKED AGAINST ARCHITECTS LAYOUT PLANS

DATUM LEVEL OF 140.0m HAS BEEN USED, LEVELS SHOULD BE ADJUSTED UP RECEIPT OF EXTERNAL LEVELS DESIGN

DRAINAGE STRATEGY

SURFACE WATER

In accordance with the SuDS Hierarchy then infiltration should be considered in the first instance, based on the BGS website and the site constraints then is anticipated that soakaways will not be viable.

If soakaways do not work then the surface water should discharge to a water course wherever possible, as there are no watercourses within the vicinity of the site then this has been discounted.

We are therefore proposing to discharge to the public sewer under Halifax Road, at a controlled rate of 2.0 l/s with attenuation on site to store the 1 in 100 Year + 40% climate change rainfall event. (Refer to Advant Engineer's Drainage Strategy Report)

FOUL DRAINAGE

It is proposed to discharge the foul drainage to the existing public sewer under Halifax Road.

NOTES

1. THIS DRAWING IS PRODUCED FOR USE IN THIS PROJECT ONLY AND MAY NOT BE USED FOR ANY OTHER PURPOSE. THE CONSULTING ENGINEERS ACCEPT NO LIABILITY FOR THE USE OF THIS DRAWING OTHER THAN THE PURPOSE FOR WHICH IT WAS INTENDED IN CONNECTION WITH THIS PROJECT AS RECORDED ON THE TITLE BLOCK FIELDS 'PURPOSE FOR ISSUE' AND 'FILE STATUS CODE'.

2. THIS DRAWING MAY NOT BE REPRODUCED IN ANY FORM WITHOUT PRIOR WRITTEN AGREEMENT FROM ADVANT ENGINEERS.

3. DO NOT SCALE FROM THE DRAWING. USE WRITTEN DIMENSIONS ONLY.

4. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE SPECIFIED.

5. DISCREPANCIES MUST BE REPORTED BACK TO THE ENGINEER PRIOR TO CONSTRUCTION.

6. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ADVANT ENGINEERS DRAWINGS AND SPECIFICATIONS.

KEY

- EXISTING FW SEWER
- EXISTING SW SEWER
- PROPOSED SW SEWER
- PROPOSED FW SEWER
- PERMEABLE PAVING

A	INITIAL ISSUE	RR	05.01.26
REV	AMENDMENTS	BY	DATE

PRELIMINARY

STATUS	CHK'D
PRELIMINARY	MJM
FOR COMMENT	
FOR APPROVAL	
FOR CONSTRUCTION	
AS BUILT	

advant ENGINEERS

Unit 6 Benton Office Park, Bennett Avenue
Horbury, Wakefield, West Yorkshire, WF4 5RA
01924 654108
wakefield@advantengineers.co.uk

CLIENT

CEDAR BUILDING SOLUTIONS

CONTRACT

LAND ADJ. 482 HALIFAX ROAD
LIVERSEDGE
WF15 8EB

TITLE

PROPOSED DRAINAGE LAYOUT PLAN

DRAWN	RR	CHK'D	MJM
SCALE	1:200 @ A1	DATE	05.01.26

JOB No	DRG No	REV
25097	101	A

**APPENDIX E
DRAINAGE CALCS**

Network Details

Manhole Schedule

Manhole	Catchment Area (ha)	Diameter (m)	Type	CL (m)	IL (m)	Depth To Soffit (m)	Easting (m)	Northing (m)
S1	0.030	0.450	Unknown	140.000	139.250	0.650	-80.126	17.532
S2	0.018	0.450	Unknown	140.000	139.200	0.700	-77.197	20.323
S3	0.000	0.450	Unknown	140.000	139.050	0.850	-76.170	32.687
S4	0.000	1.200	Unknown	140.000	138.900	1.000	-67.147	34.301
S5	0.000	0.600	Unknown	140.000	138.850	1.050	-66.891	36.938

Pipe Schedule

Pipe Number	US Manhole	US IL (m)	DS Manhole	DS IL (m)	Shape	Dimension (m)	Length (m)	Gradient (1:x)	Roughness (mm)	US Depth To Soffit (m)	DS Depth To Soffit (m)
1.000	S1	139.250	S2	139.200	Circ	0.1mØ	4.046	81	0.600	0.650	0.700
1.001	S2	139.200	S3	139.050	Circ	0.1mØ	12.406	83	0.600	0.700	0.850
1.002	S3	139.050	S4	138.900	Circ	0.1mØ	9.167	61	0.600	0.850	1.000
1.003	S4	138.900	S5	138.850	Circ	0.1mØ	2.650	53	0.600	1.000	1.050

Permeable Paving Schedule

Permeable Paving	Assigned Manhole	Effective Storage Volume (m3)	CL (m)	IL (m)	Storage Infil Rate (m/hr)	Safety Factor	Easting (m)	Northing (m)
Permeable Paving 1	S1	30.484	140.000	139.620	0.00000000	2.00	-81.581	11.261

Outfall Details

Outfall Manhole S5 : Free Discharge


Flow Control Details

Controls within Manhole S4

Hydro-Brake® Optimum Control

Model Ref	Design Depth (m)	Design Flow (l/s)	Invert Offset (m)	FF Head (m)	FF Flow (l/s)	KF Head (m)	KF Flow (l/s)
SHE-0032-5000-1000-5000	1.000	0.500	0.000	0.143	0.347	0.289	0.296

Hydro-Brake® Optimum Control from S4 to S5



Simulation Settings

FSR: M5-60=19.00, R=0.35, Locale=England and Wales

Summer (Cv: 1.00), Winter (Cv: 1.00)

Global Time of Entry: 5.0 mins

Durations (mins): 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440, 2160, 2880, 4320, 5760, 7200, 8640, 10080

Return Periods (yrs) + Climate Change: (1, +0%), (30, +0%), (100, +0%), (100, +40%)

Manhole Flood Risk Freeboard: 0.300m

Simulated Rainfall Events

Storm	Average Intensity (mm/hr)	Runoff Continuity %	Flow Continuity %	Item Volume Continuity Errors
1Yr 15Min Winter	33.289	0.00	1.44	
1Yr 15Min Summer	33.289	0.00	1.55	
1Yr 30Min Winter	21.560	0.00	4.02	
1Yr 30Min Summer	21.560	0.00	3.94	
1Yr 60Min Winter	13.523	0.00	6.13	S3 0.33m3, S2 0.17m3, S1 0.13m3, S4 0.11m3
1Yr 60Min Summer	13.523	0.00	6.12	S3 0.33m3, S2 0.17m3, S1 0.13m3, S4 0.11m3
1Yr 120Min Winter	8.362	0.00	2.44	
1Yr 120Min Summer	8.362	0.00	2.37	
1Yr 180Min Winter	6.304	0.00	0.00	
1Yr 180Min Summer	6.304	0.00	0.00	
1Yr 240Min Winter	5.165	0.00	0.00	
1Yr 240Min Summer	5.165	0.00	0.00	
1Yr 360Min Summer	3.897	0.00	0.00	
1Yr 360Min Winter	3.897	0.00	0.00	
1Yr 480Min Winter	3.187	0.00	0.00	
1Yr 480Min Summer	3.187	0.00	0.00	
1Yr 600Min Winter	2.727	0.00	0.00	
1Yr 600Min Summer	2.727	0.00	0.00	
1Yr 720Min Winter	2.401	0.00	0.00	
1Yr 720Min Summer	2.401	0.00	0.00	
1Yr 960Min Summer	1.963	0.00	0.00	
1Yr 960Min Winter	1.963	0.00	0.00	
1Yr 1440Min Summer	1.479	0.00	0.00	
1Yr 1440Min Winter	1.479	0.00	0.00	
1Yr 2160Min Summer	1.115	0.00	0.00	
1Yr 2160Min Winter	1.115	0.00	0.00	
1Yr 2880Min Winter	0.913	0.00	0.00	
1Yr 2880Min Summer	0.913	0.00	0.00	
1Yr 4320Min Summer	0.689	0.00	0.00	
1Yr 4320Min Winter	0.689	0.00	0.00	
1Yr 5760Min Summer	0.565	0.00	0.00	
1Yr 5760Min Winter	0.565	0.00	0.00	
1Yr 7200Min Winter	0.484	0.00	0.00	
1Yr 7200Min Summer	0.484	0.00	0.00	
1Yr 8640Min Summer	0.427	0.00	0.00	
1Yr 8640Min Winter	0.427	0.00	0.00	
1Yr 10080Min Summer	0.383	0.00	0.00	
1Yr 10080Min Winter	0.383	0.00	0.00	
30Yr 15Min Summer	68.836	0.00	11.32	S3 0.58m3, S2 0.43m3, S1 0.38m3, S4 0.15m3
30Yr 15Min Winter	68.836	0.00	11.42	S3 0.58m3, S2 0.43m3, S1 0.38m3, S4 0.15m3
30Yr 30Min Summer	45.828	0.00	8.91	S3 0.61m3, S2 0.46m3, S1 0.41m3, S4 0.16m3
30Yr 30Min Winter	45.828	0.00	8.88	S3 0.61m3, S2 0.46m3, S1 0.41m3, S4 0.16m3
30Yr 60Min Summer	29.238	0.00	7.11	S3 0.63m3, S2 0.48m3, S1 0.44m3, S4 0.16m3
30Yr 60Min Winter	29.238	0.00	7.12	S3 0.63m3, S2 0.48m3, S1 0.43m3, S4 0.16m3
30Yr 120Min Summer	18.112	0.00	5.69	S3 0.63m3, S2 0.48m3, S1 0.41m3, S4 0.16m3
30Yr 120Min Winter	18.112	0.00	5.71	S3 0.63m3, S2 0.48m3, S1 0.41m3, S4 0.16m3
30Yr 180Min Summer	13.534	0.00	4.98	
30Yr 180Min Winter	13.534	0.00	5.00	
30Yr 240Min Summer	10.952	0.00	4.50	
30Yr 240Min Winter	10.952	0.00	4.51	
30Yr 360Min Winter	8.106	0.00	3.70	
30Yr 360Min Summer	8.106	0.00	3.71	
30Yr 480Min Summer	6.544	0.00	0.73	
30Yr 480Min Winter	6.544	0.00	0.58	

Simulated Rainfall Events

Storm	Average Intensity (mm/hr)	Runoff Continuity %	Flow Continuity %	Item Volume Continuity Errors
30Yr 600Min Summer	5.539	0.00	0.00	
30Yr 600Min Winter	5.539	0.00	0.00	
30Yr 720Min Winter	4.832	0.00	0.00	
30Yr 720Min Summer	4.832	0.00	0.00	
30Yr 960Min Summer	3.892	0.00	0.00	
30Yr 960Min Winter	3.892	0.00	0.00	
30Yr 1440Min Summer	2.866	0.00	0.00	
30Yr 1440Min Winter	2.866	0.00	0.00	
30Yr 2160Min Summer	2.108	0.00	0.00	
30Yr 2160Min Winter	2.108	0.00	0.00	
30Yr 2880Min Summer	1.693	0.00	0.00	
30Yr 2880Min Winter	1.693	0.00	0.00	
30Yr 4320Min Summer	1.242	0.00	0.00	
30Yr 4320Min Winter	1.242	0.00	0.00	
30Yr 5760Min Summer	0.996	0.00	0.00	
30Yr 5760Min Winter	0.996	0.00	0.00	
30Yr 7200Min Summer	0.839	0.00	0.00	
30Yr 7200Min Winter	0.839	0.00	0.00	
30Yr 8640Min Winter	0.730	0.00	0.00	
30Yr 8640Min Summer	0.730	0.00	0.00	
30Yr 10080Min Summer	0.648	0.00	0.00	
30Yr 10080Min Winter	0.648	0.00	0.00	
100Yr 15Min Summer	89.024	0.00	9.12	S3 0.61m3, S2 0.46m3, S1 0.41m3, S4 0.16m3
100Yr 15Min Winter	89.024	0.00	9.22	S3 0.61m3, S2 0.46m3, S1 0.41m3, S4 0.16m3
100Yr 30Min Summer	59.849	0.00	7.09	S3 0.64m3, S2 0.48m3, S1 0.44m3, S4 0.16m3
100Yr 30Min Winter	59.849	0.00	7.07	S3 0.64m3, S2 0.49m3, S1 0.44m3, S4 0.16m3
100Yr 60Min Summer	38.413	0.00	5.71	S3 0.66m3, S2 0.51m3, S1 0.47m3, S4 0.17m3
100Yr 60Min Winter	38.413	0.00	5.72	S3 0.67m3, S2 0.51m3, S1 0.47m3, S4 0.17m3
100Yr 120Min Summer	23.812	0.00	4.65	
100Yr 120Min Winter	23.812	0.00	4.67	
100Yr 180Min Summer	17.737	0.00	4.13	
100Yr 180Min Winter	17.737	0.00	4.14	
100Yr 240Min Summer	14.290	0.00	3.77	
100Yr 240Min Winter	14.290	0.00	3.78	
100Yr 360Min Summer	10.505	0.00	3.25	
100Yr 360Min Winter	10.505	0.00	3.26	
100Yr 480Min Summer	8.441	0.00	2.85	
100Yr 480Min Winter	8.441	0.00	2.85	
100Yr 600Min Summer	7.118	0.00	2.13	
100Yr 600Min Winter	7.118	0.00	2.04	
100Yr 720Min Summer	6.190	0.00	0.00	
100Yr 720Min Winter	6.190	0.00	0.00	
100Yr 960Min Summer	4.959	0.00	0.00	
100Yr 960Min Winter	4.959	0.00	0.00	
100Yr 1440Min Summer	3.622	0.00	0.00	
100Yr 1440Min Winter	3.622	0.00	0.00	
100Yr 2160Min Summer	2.640	0.00	0.00	
100Yr 2160Min Winter	2.640	0.00	0.00	
100Yr 2880Min Summer	2.107	0.00	0.00	
100Yr 2880Min Winter	2.107	0.00	0.00	
100Yr 4320Min Summer	1.530	0.00	0.00	
100Yr 4320Min Winter	1.530	0.00	0.00	
100Yr 5760Min Summer	1.218	0.00	0.00	
100Yr 5760Min Winter	1.218	0.00	0.00	
100Yr 7200Min Summer	1.019	0.00	0.00	
100Yr 7200Min Winter	1.019	0.00	0.00	
100Yr 8640Min Summer	0.882	0.00	0.00	
100Yr 8640Min Winter	0.882	0.00	0.00	
100Yr 10080Min Summer	0.781	0.00	0.00	
100Yr 10080Min Winter	0.781	0.00	0.00	
100Yr+40% 15Min Summer	124.633	0.00	6.84	S3 0.64m3, S2 0.49m3, S1 0.44m3, S4 0.16m3
100Yr+40% 15Min Winter	124.633	0.00	6.91	S3 0.65m3, S2 0.49m3, S1 0.44m3, S4 0.16m3
100Yr+40% 30Min Summer	83.789	0.00	5.43	S3 0.68m3, S2 0.53m3, S1 0.48m3, S4 0.17m3
100Yr+40% 30Min Winter	83.789	0.00	5.42	S3 0.68m3, S2 0.53m3, S1 0.48m3, S4 0.17m3
100Yr+40% 60Min Summer	53.779	0.00	4.47	
100Yr+40% 60Min Winter	53.779	0.00	4.48	
100Yr+40% 120Min Summer	33.337	0.00	3.73	
100Yr+40% 120Min Winter	33.337	0.00	3.74	

Simulated Rainfall Events

Storm	Average Intensity (mm/hr)	Runoff Continuity %	Flow Continuity %	Item Volume Continuity Errors
100Yr+40% 180Min Summer	24.832	0.00	3.35	
100Yr+40% 180Min Winter	24.832	0.00	3.36	
100Yr+40% 240Min Summer	20.006	0.00	3.09	
100Yr+40% 240Min Winter	20.006	0.00	3.10	
100Yr+40% 360Min Summer	14.706	0.00	2.71	
100Yr+40% 360Min Winter	14.706	0.00	2.72	
100Yr+40% 480Min Summer	11.818	0.00	2.42	
100Yr+40% 480Min Winter	11.818	0.00	2.43	
100Yr+40% 600Min Summer	9.966	0.00	2.18	
100Yr+40% 600Min Winter	9.966	0.00	2.18	
100Yr+40% 720Min Summer	8.665	0.00	1.97	
100Yr+40% 720Min Winter	8.665	0.00	1.97	
100Yr+40% 960Min Summer	6.943	0.00	1.28	
100Yr+40% 960Min Winter	6.943	0.00	1.25	
100Yr+40% 1440Min Summer	5.071	0.00	0.00	
100Yr+40% 1440Min Winter	5.071	0.00	0.00	
100Yr+40% 2160Min Summer	3.696	0.00	0.00	
100Yr+40% 2160Min Winter	3.696	0.00	0.00	
100Yr+40% 2880Min Summer	2.949	0.00	0.00	
100Yr+40% 2880Min Winter	2.949	0.00	0.00	
100Yr+40% 4320Min Summer	2.142	0.00	0.00	
100Yr+40% 4320Min Winter	2.142	0.00	0.00	
100Yr+40% 5760Min Summer	1.705	0.00	0.00	
100Yr+40% 5760Min Winter	1.705	0.00	0.00	
100Yr+40% 7200Min Summer	1.427	0.00	0.00	
100Yr+40% 7200Min Winter	1.427	0.00	0.00	
100Yr+40% 8640Min Summer	1.235	0.00	0.00	
100Yr+40% 8640Min Winter	1.235	0.00	0.00	
100Yr+40% 10080Min Winter	1.093	0.00	0.00	
100Yr+40% 10080Min Summer	1.093	0.00	0.00	

Simulation Results

Return Period (yrs) + Climate Change (%):

1yr+0%

Manholes

Manhole	Critical Storm	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Flood (m3)	Status
S1	600 min Summer	382	139.637	0.387	0.292		Surcharged
S2	600 min Summer	382	139.637	0.437	0.438		Surcharged
S3	600 min Summer	382	139.636	0.586	0.437		Surcharged
S4	600 min Summer	383	139.636	0.736	0.436		Surcharged
S5	600 min Summer	383	138.864	0.014	0.436		Outfall

Conduits

Pipe No.	Critical Storm	Peak (mins)	US Manhole	DS Manhole	Flow Depth (m)	Max Velocity (m/s)	Max Flow (l/s)	Flow / Capacity	Status
1.000	1440 min Winter	831	S1	S2	0.100	0.358	0.559	0.083	Surcharged
1.001	15 min Summer	11	S2	S3	0.100	0.857	3.437	0.518	Surcharged
1.002	15 min Summer	8	S3	S4	0.100	0.676	2.318	0.300	Surcharged
1.003	600 min Summer	383	S4	S5	0.014	0.651	0.436	0.052	OK

Permeable Paving Storage

Permeable Paving	Critical Storm	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Flood (m3)	Surface Runoff (m3)	Status
Permeable Paving 1	360 min Summer	218	139.643	0.023	0.535			OK

Return Period (yrs) + Climate Change (%):

30yr+0%

Manholes

Manhole	Critical Storm	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Flood (m3)	Status
S1	480 min Summer	363	139.717	0.467	0.290		Flood Risk
S2	480 min Summer	363	139.717	0.517	0.457		Flood Risk
S3	480 min Summer	363	139.717	0.667	0.457		Flood Risk
S4	480 min Summer	363	139.716	0.816	0.457		Flood Risk
S5	480 min Summer	364	138.864	0.014	0.457		Outfall

Conduits

Pipe No.	Critical Storm	Peak (mins)	US Manhole	DS Manhole	Flow Depth (m)	Max Velocity (m/s)	Max Flow (l/s)	Flow / Capacity	Status
1.000	4320 min Winter	2246	S1	S2	0.100	0.351	0.729	0.109	Surcharged
1.001	15 min Winter	7	S2	S3	0.100	0.847	4.331	0.653	Surcharged
1.002	15 min Winter	6	S3	S4	0.100	0.735	2.501	0.323	Surcharged
1.003	480 min Summer	364	S4	S5	0.014	0.660	0.457	0.055	OK

Permeable Paving Storage

Permeable Paving	Critical Storm	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Flood (m3)	Surface Runoff (m3)	Status
Permeable Paving 1	480 min Summer	363	139.717	0.097	0.289			OK

Return Period (yrs) + Climate Change (%):

100yr+0%

Manholes

Manhole	Critical Storm	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Flood (m3)	Status
S1	480 min Winter	403	139.767	0.517	0.296		Flood Risk
S2	480 min Winter	403	139.766	0.566	0.469		Flood Risk
S3	480 min Winter	403	139.766	0.716	0.469		Flood Risk
S4	480 min Winter	403	139.765	0.865	0.469		Flood Risk
S5	480 min Winter	403	138.864	0.014	0.468		Outfall

Conduits

Pipe No.	Critical Storm	Peak (mins)	US Manhole	DS Manhole	Flow Depth (m)	Max Velocity (m/s)	Max Flow (l/s)	Flow / Capacity	Status
1.000	10080 min Summer	5210	S1	S2	0.100	0.353	0.637	0.095	Surcharged
1.001	15 min Winter	9	S2	S3	0.100	0.906	4.470	0.674	Surcharged
1.002	15 min Winter	5	S3	S4	0.100	0.815	2.960	0.382	Surcharged
1.003	480 min Winter	403	S4	S5	0.015	0.665	0.468	0.056	OK

Permeable Paving Storage

Permeable Paving	Critical Storm	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Flood (m3)	Surface Runoff (m3)	Status
Permeable Paving 1	480 min Winter	405	139.767	0.147	0.300			OK

Return Period (yrs) + Climate Change (%):

100yr+40%

Manholes

Manhole	Critical Storm	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Flood (m3)	Status
S1	600 min Winter	530	139.860	0.610	0.311		Flood Risk
S2	600 min Winter	528	139.860	0.660	0.490		Flood Risk
S3	600 min Winter	529	139.859	0.809	0.490		Flood Risk
S4	600 min Winter	529	139.858	0.958	0.490		Flood Risk
S5	600 min Winter	529	138.865	0.015	0.490		Outfall


Conduits

Pipe No.	Critical Storm	Peak (mins)	US Manhole	DS Manhole	Flow Depth (m)	Max Velocity (m/s)	Max Flow (l/s)	Flow / Capacity	Status
1.000	8640 min Winter	4205	S1	S2	0.100	0.349	0.616	0.092	Surcharged
1.001	15 min Winter	8	S2	S3	0.100	0.883	5.923	0.892	Surcharged
1.002	15 min Winter	8	S3	S4	0.100	0.847	3.294	0.426	Surcharged
1.003	600 min Winter	529	S4	S5	0.015	0.674	0.490	0.059	OK

Permeable Paving Storage

Permeable Paving	Critical Storm	Peak (mins)	Level (m)	Depth (m)	Inflow (l/s)	Flood (m3)	Surface Runoff (m3)	Status
Permeable Paving 1	600 min Winter	531	139.860	0.240	0.309			OK

**APPENDIX F
FLOOD EXCEEDANCE PLAN**



COVER AND INVERTS OF EXISTING SEWERS SHOULD BE CHECKED ON SITE PRIOR TO CONSTRUCTION

ALL RWP AND SVP'S TO BE CHECKED AGAINST ARCHITECTS LAYOUT PLANS

DATUM LEVEL OF 140.0m HAS BEEN USED, LEVELS SHOULD BE ADJUSTED UP RECEIPT OF EXTERNAL LEVELS DESIGN

DRAINAGE STRATEGY

SURFACE WATER

In accordance with the SuDS Hierarchy then infiltration should be considered in the first instance, based on the BGS website and the site constraints then is anticipated that soakaways will not be viable.

If soakaways do not work then the surface water should discharge to a water course wherever possible, as there are no watercourses within the vicinity of the site then this has been discounted.

We are therefore proposing to discharge to the public sewer under Halifax Road, at a controlled rate of 2.0 l/s with attenuation on site to store the 1 in 100 Year + 40% climate change rainfall event. (Refer to Advant Engineer's Drainage Strategy Report)

FOUL DRAINAGE

It is proposed to discharge the foul drainage to the existing public sewer under Halifax Road.

NOTES

1. THIS DRAWING IS PRODUCED FOR USE IN THIS PROJECT ONLY AND MAY NOT BE USED FOR ANY OTHER PURPOSE. THE CONSULTING ENGINEERS ACCEPT NO LIABILITY FOR THE USE OF THIS DRAWING OTHER THAN THE PURPOSE FOR WHICH IT WAS INTENDED IN CONNECTION WITH THIS PROJECT AS RECORDED ON THE TITLE BLOCK FIELDS 'PURPOSE FOR ISSUE' AND 'FILE STATUS CODE'.
2. THIS DRAWING MAY NOT BE REPRODUCED IN ANY FORM WITHOUT PRIOR WRITTEN AGREEMENT FROM ADVANT ENGINEERS.
3. DO NOT SCALE FROM THE DRAWING. USE WRITTEN DIMENSIONS ONLY.
4. ALL DIMENSIONS ARE IN MILLIMETRES UNLESS OTHERWISE SPECIFIED.
5. DISCREPANCIES MUST BE REPORTED BACK TO THE ENGINEER PRIOR TO CONSTRUCTION.
6. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ADVANT ENGINEERS DRAWINGS AND SPECIFICATIONS.

KEY

FLOOD EXCEEDANCE EVENT

FLOOD FLOW PATH

A	INITIAL ISSUE	RR	05.01.26
REV	AMENDMENTS	BY	DATE

PRELIMINARY

STATUS	CHK'D
PRELIMINARY	MJM
FOR COMMENT	
FOR APPROVAL	
FOR CONSTRUCTION	
AS BUILT	

advant ENGINEERS

Unit 6 Benton Office Park, Bennett Avenue
Horbury, Wakefield, West Yorkshire, WF4 5RA
01924 654108
wakefield@advantengineers.co.uk

CLIENT

CEDAR BUILDING SOLUTIONS

CONTRACT


LAND ADJ. 483 HALIFAX ROAD LIVERSEDGE WF15 8EB

TITLE

FLOOD EXCEEDANCE LAYOUT PLAN

DRAWN	RR	CHK'D	MJM
SCALE	1:200 @ A1	DATE	05.01.26

JOB No	DRG No	REV
25097	102	A



Unit 6

Benton Office Park

Bennett Avenue

Horbury, Wakefield

West Yorkshire

WF4 5RA

01924 654108

mail@advantengineers.co.uk

www.advantengineers.co.uk