



## Specification Sheet

### Electric Roller Shutter Doors

Electrically operated roller shutter doors made from galvanised steel. Includes 3-phase motor pre-wired with a 5 pin 16 amp CE plug and 3 button low voltage slave station. Can also be manually operated using supplied hand chain. Fitted with galvanised steel posts for fast fitment to temporary building.

#### Size

- » Sizes are dependent on building size and customer requirements

#### Materials

- » **Curtain:** Galvanised steel lath with nylon and heavy duty cast steel endlocks
- » **Bottom Rail:** T-section galvanised steel fitted with wraparound rubber weather seal.
- » **Guides:** 100mm heavy duty galvanised steel channels fixed to 75mm x 75mm x 3mm galvanised steel angles.

- » **Roller Brackets:** 406mm<sup>2</sup> x 6mm heavy duty mild steel plates finished in red oxide primer.
- » **Roller Assembly:** 125mm diameter heavy-duty steel roller with internal counterbalance springs driven by 51t spur gear. All finished in red oxide primer.

#### Operation

- » 3-phase flange mount motor with 4 integral limits and manual override with interlock switch and high level change over system including 8m of hand chain. 18t cut pinion gear mounted to motor drive shaft.

#### Spaciotempo UK

Dovefields, Dovefields Industrial Estate  
Uttoxeter, Staffordshire ST14 8HU

T : 01889 569 569 | [www.spaciotempo.co.uk](http://www.spaciotempo.co.uk)

## Electric Roller Shutter Doors

ST/SPEC/0009/01