



## Specification Sheet

### D1 Single Personnel Door

This is a steel hinged doorset primarily for 'emergency exit' use only. Includes internal panic latch (full width bar) and external locking handle with key and fast fix frame extensions for temporary building use.

#### Frame

- » Factory finished in powder coat PPC BS10 A05 (Goosewing Grey) with ripple finish
- » Frame material 1.5mm cold rolled steel

- » Exidor 302 outside key access device with euro cylinder key
- » Hold open door stay

#### Leaf

- » Magnelis (self colour)
- » Leaf material 1.2mm aluzinc
- » Overall door thickness 55mm

#### Hardware

- » Exidor 296 rim panic latch

### D1 Single Personnel Door

ST/SPEC/0003/01

#### Spaciotempo UK

Dovefields, Dovefields Industrial Estate  
Uttoxeter, Staffordshire ST14 8HU

T : 01889 569 569 | [www.spaciotempo.co.uk](http://www.spaciotempo.co.uk)