

**Sent:** 03 June 2026 18:35

**Subject:** RE: Attached letter from Kirklees Council regarding application number 2026/90880 at location Liley Hall Farm, 3, Liley Lane, Upper Hopton, Mirfield, WF14 8EG

Please arrange for the inclusion of the following condition:

- 1) Before the development commences a scheme detailing the location and cross-sectional information together with the proposed design and construction details for all new surface water attenuation tanks/pipes/manholes located within the proposed highway footprint or influence zone of highway loading, whilst ensuring that oversize manholes in the highway are limited to 1.80m internal diameter, shall be submitted to and approved by the Highway Authority in writing. The approved scheme shall be implemented prior to the commencement of the proposed development and thereafter retained during the life of the development. See <https://www.kirklees.gov.uk/beta/regeneration-and-development/pdf/highways-structural-procedures.pdf> for further details and in particular, for the certification of oversize pcc manholes and their cover slabs, as advised in this document.

**Important Notes:**

All new storm water attenuation tanks/pipes/culverts with internal diameter/ spans exceeding 0.9m must be located off the adoptable highway. Any decision to locate these facilities within the adoptable highway footprint must be accompanied with a full risk evaluation report with particular reference to their proposed inspection, structural assessment and maintenance regime in compliance with the CDM Regulations 2015 requirements.

The adopting authority (i.e. Yorkshire Water) will also be required to produce and submit a legally binding agreement to the Highway Authority explicitly stating that they will be fulfilling their obligations in relation to the systematic and cyclical inspection and structural assessment of any attenuation structure located within the highway footprint, in full compliance with CS450- Inspection of Highway structures.

Furthermore, all new precast pipes/ culverts/storage tanks proposed for use within the footprint of an adoptable highway must comply with the Specification for Highway Works (SHW-Series 500 or 2500) and must be accredited with a BBA (The British Board of Agrément Roads and Bridges) or HAPAS (Highway Authority Product Approval Scheme) or equivalent certificate.

Regards

**Farhad Khatibi**

Bridges & Structures Manager  
Structures Section  
Highways and Streetscene

Kirklees Council

Highways and Streetscene | Highways Structures | Civic Centre 1 | High Street | Huddersfield | HD1 2NF

☎ **External:** 01484 221000 **Internal:** 74199

**Mobile:** None

✉ **Email:** [farhad.khatibi@kirklees.gov.uk](mailto:farhad.khatibi@kirklees.gov.uk)

