



- Half battered kerb
- Channel Block
- Palisade Fence
- Service Yard
175mm PAV2 concrete slab, A252 mesh to base,
500g DPM on 150mm MOT1 on 450mm 6F2.
- HGV Tarmac Spec
150mm 6F2 base layers with top layer MOT 1,
100mm Macadam road base,
50mm Rolled asphalt base course,
45mm Rolled asphalt wearing course
with 20mm coated chippings.
- Car Park Tarmac Spec
150mm 6F2 base layers with top layer MOT 1,
60mm thick 28mm nominal macadam base course,
30mm thick SMA wearing course.
- Pedestrian Walkways
150mm of DTP specified granular sub-base (Type 1)
60mm of 6mm nominal size dense bitumen macadam basecourse
20mm of sand asphalt with "harden red" chippings as wearing course

B	Yard sub-base updated	CS	26 02 16
A	Works in Building 'A' yard added.	CS	26 01 29
Rev	Note	Initial	Date
3 Richmond House, Caldene Business Park, Mytholmroyd, Hebden Bridge, West Yorkshire, HX7 5QJ 01422 883317 enquiries@tdjagger.ltd.uk www.tdjagger.ltd.uk			
Client	JLB Group		
Project	Turnbridge Mills Quay Street Huddersfield		
Drawing	External Works		
Date	Nov 2025	Drawn	TJ
Checked	-	Scale	1:250@A1
Dwg No.	3310 73	Revision	B
Drawings are to scale indicated for planning purposes. No scaling permitted for construction purposes. Information on this drawing is copyright. All rights reserved. No part of this work may be reproduced or transmitted in any form by any means, either electronically, mechanically, by photocopying, recording or otherwise stored in any retrieval system of any nature, without the express consent of T D Jagger Ltd.			
Don't Ignore Health & Safety			 It Might Just Save Your Life