

Unit 1, Windsor Industrial Estate, Rupert Street, Birmingham. B7 4PR  
Telephone: 0121 327 7775  
Email: [sales@nortonindustrialdoors.co.uk](mailto:sales@nortonindustrialdoors.co.uk)  
[www.nortonindustrialdoors.co.uk](http://www.nortonindustrialdoors.co.uk)

### ***ND7000 Hand Chain Manually Operated Industrial Roller Shutter Door***

*Our traditional hand chain manually operated roller shutter doors are suitable for factories warehouses where security and cost effectiveness is required and local power supplies are not available or customer preference. Sprocket or gear driven with anti fall back safety brakes and various curtain types. All of our hand chain manually operated traditional roller shutter doors are manufactured in our UK based factory and are installed by our experienced NVQ qualified engineers.*

#### ***Product Specification:***

***Curtain:*** Single skin steel 76mm concave with interlocking quirks and pressed or cast endlocks to prevent lateral movement, wind endlocked where required for wider doors.

***Endplates:*** Galvanised laser cut folded steel predrilled supported with 76mm x 50mm x 5mm steel angle

***Guides:*** 65mm or 100mm continuous channels (wind endlocked section available)

***Tube:*** Seamless steel in various diameters to counteract deflection dependent on curtain widths and weight

***Operation:*** Counterbalance torsion spring assisted with anti fall back safety brake

***Controls:*** Steel haul chain

***Canopies:*** Hood covers or fascias manufactured from 0.9mm galvanised steel

***Finish:*** Galvanised steel with powder coating options available.

***Additional Options:*** Various types of locking options to add security where required

*Further data available on request*



**24 HOUR EMERGENCY SERVICE**