

# **Consultee Comments for Planning Application 2026/91537**

## **Application Summary**

Application Number: 2026/91537

Address: Salendine Filling Station, New Hey Road, Salendine Nook, Huddersfield, HD3 3UZ

Proposal: Extension of existing sales building; removal of existing jet wash and erection of jet washers and associated plant; installation of electric vehicle charging points; siting of air, water and vacuum bays; reconfiguration of parking bays; new external artificial lighting; installation of postal parcel lockers; relocation of structure to accommodate signage; erection of retaining wall; soft landscaping; installation of drainage channel; re siting of waste storage areas and associated works

Case Officer: Joanna Rednall

## **Consultee Details**

Name: Agnes Boryn- Kirklees DOCO, West Yorkshire Police

Address: Huddersfield Police Station, Castlegate, Huddersfield, HD1 2NJ

On behalf of: West Yorkshire Police

## **Comments**

Thank you for your request for consultation on the above application. The comments are made with the intention of reducing opportunities for future crime and antisocial activity which addresses our collective responsibilities outlined in Section 17 of the Crime and Disorder Act 1998, by creating safe and secure developments where people will want to reside, visit or work.

The recommendations are supported by the following guidance:

NPPF National Planning Policy Framework (Section 8. Promoting healthy and safe communities) <https://www.gov.uk/government/publications/national-planning-policy-framework--2>

Kirklees Council Planning and development policy

<https://www.kirklees.gov.uk/beta/planning-and-development.aspx>

Kirklees Development Plan <https://www.kirklees.gov.uk/beta/planning-policy/local-plan.aspx>

Secured by Design [www.securedbydesign.com](http://www.securedbydesign.com)

Crime Prevention Through Environmental Design (CPTED)

This advice is given as a view as to what measures might reduce the risk of crime; there can be no guarantee that the recommendations will prevent crime.

Before any measures are implemented you are advised to consider current Health and Safety Legislation, Planning Permission and consult with your local Fire Safety Officer or any statutory body that may require notification or consultation.

### **Acquisitive Crime and Antisocial Behaviour Threat and Risk**

The level of security at the site should align with any identified threat and risk and the proposed business of the end users. Therefore, it is advisable to adopt a pragmatic approach towards security requirements and take note of the crime and incident information listed below.

Risks of not considering security at an early stage:

1. Inadequate protection
2. Increased risk
3. Wasted resources due to theft/ damage/ antisocial behaviour, etc.
4. Delay, disruption and cost caused by retrofitting security measures post attack/ incident.
5. Reputational damage.

### **Current crime statistics in the locality:**

I have conducted a search using WYP crime data and mapping tool. The search covered offences committed between 05/08/2025 and 05/08/2026. The search criteria included burglary business, robbery, arson, criminal damage and vehicle crime (interference, theft of, theft from) for the area of partial postcode HD3 3\*.

This returned 146 offences: 3x arson, 8x burglary business, 61x criminal damage (4x non-dwelling, 9x dwelling, 34x motor vehicle, 14x non-specific), 8x robbery, 17x vehicle interference, 30x theft from vehicle, 19x theft of vehicle.

Additionally, due to the development including a petrol station and shop, a further search was conducted for make off without payment and theft from shop offences within the same timespan and area. This returned 9 make offs without payment and 130 retail crimes.

### **Current ASB statistics in the locality:**

I have conducted a search using WYP incident data and mapping tool. The search covered ASB/ nuisance type incidents which occurred in HD3 3\* area between 05/08/2025 and 05/08/2026. This returned 80 incidents, 5 of which were in the vicinity of the premises. The matters of note related to inconsiderate/ obstructive parking, vehicles revving engines and fireworks.

**West Yorkshire Police have no objection in principle to this application. We respectfully request the inclusion of a PLANNING CONDITION for SECURITY MEASURES in the interests of crime prevention and community safety.**

### **Recommended security measures, supported by SBD Non-residential Guide 2025:**

Please note national standards and specifications are often updated, please ensure that the latest version of the security standards and specifications specified in this document are adhered to.

#### **Construction phase security**

Unfortunately, there are many crimes which occur during the construction phase (including enabling works) of a development. Secured by Design recommend that security should be considered throughout the life cycle of the development and be in place prior and during the construction phase. For example, this should include robust perimeter fencing of the site and (where appropriate) a monitored alarm system (by a company or individual who can provide a response) for site cabins and those structures facilitating the storage of materials and fuel.

The developer is advised that signage should be displayed across the development (i.e. on the perimeter fencing) and should contain the emergency contact details and point of contact. This will allow both the public and staff members to report suspicious behaviour and circumstances.

Mobile or part-time video surveillance systems (VSS) can be used as an effective aid to the security of a site and can act as a deterrent to criminal activity.

#### **Hostile Vehicle Mitigation**

Where there is a risk of motor vehicles being used to attack premises or an ATM etc, the standards for vehicle security bollards are:

ISO 22343-1, or

IWA 14-1, or

PAS 68.

ISO 22343-2 provides guidance on the appropriate selection, installation and use of such bollards and shall be referenced in the first instance.

#### **External furniture and litterbins**

External furniture shall be of a robust vandal and graffiti resistant design.

Furniture shall be fixed into the ground in order to prevent its theft and reduce the possibility of it being used as either a climbing aid or as a tool to break through the shell

of a building. External furniture shall not be located at or close to a building line or a boundary if there is a possibility of it being used as a climbing aid.

Litterbins can sometimes be used to assist climbing and/ or the contents used to start fires. It is preferable that these bins are of a type that can be locked onto a fixed base some distance from the buildings. Under no circumstances must litterbins be wall mounted beneath windows or on walls that are themselves covered in combustible material.

### CCTV/ VSS

Although video surveillance systems (VSS) are not a solution to all security problems, they can help deter criminals and assist with the identification of offenders after a crime has been committed. If a VSS has a recording facility only, it can be a useful investigative tool whereas a monitored system allows a real-time reaction to criminal activity. Video surveillance systems are also often very useful in mitigating against risk where other forms of security are not feasible.

It is important that an operational requirement for VSS is drawn up for non-residential premises in accordance with their specific use and that the objectives for the VSS are clearly established before a tendering process is started.

The VSS must record at a minimum of 25 frames per second so events can be watched, monitored and reviewed easily. Staff shall be sufficiently trained to operate the system and be able to make recordings available to Police on request and an operational requirement must take account of this fact. The system should have capacity to store images for at least 30 days, be installed to BS EN 62676 (Video surveillance systems for use in security applications) and compatible with planned lighting system. Please consider vandal-resistant housings for easily accessible cameras and wiring to prevent damage and loss of evidence.

Video surveillance systems shall be registered with the Information Commissioner's Office (ICO) and be compliant with guidelines in respect to Data Protection and Human Rights legislation. Further information is available at this website:

<https://www.ico.org.uk>

The data controller must ensure that all VSS images that can be used to identify individuals are used, stored and disclosed in line with the GDPR principles.

CCTV/ VSS should be installed by NSI/ SSAIB approved contractor.

### Intruder and hold-up alarm systems

Intruder and hold-up alarm systems shall meet the requirements of BS EN 50131 (Intrusion and hold-up systems) and EN 50136 (Alarm transmission systems and equipment). All installations shall be in accordance with the current electrical regulations. If an immediate police response is required, installers must meet the requirements of the National Police Chiefs' Council (NPCC) policy document – Guidelines on Police Requirements & Response to Security Systems are available at:

<http://www.policesecuritysystems.com/national-police-chiefs-council-security-systems-policy>.

Intruder alarm should be installed by NSI/ SSAIB approved contractor.

#### External lighting

In terms of security, the objective of lighting non-residential units after dark is to deter or detect an intruder.

Lighting design shall be co-ordinated with a video surveillance system and landscaping, designed to avoid any conflicts and to ensure that the lighting is sufficient to support a VSS. Light fittings shall be protected where vulnerable to vandalism.

A lighting scheme shall provide uniformed lighting levels with good colour rendition and be sufficient to cater for lawful after dark activity around the industrial or warehouse unit and site. It shall not cause glare or light pollution and shall support both formal and informal surveillance of the site.

External illumination when the building is unoccupied is recommended for entrance gates and routes to the main entrance and doors, car parks (if occupied by vehicles) and observable building elevations. Bollard lighting is not recommended due to low light spill and vulnerability to criminal damage.

#### Safes and strongrooms

Commercial safes and strongrooms should be certified to one of the following minimum standards, or above:

BS EN 1143-1:2019, or

LPS 1183 Part 1 Issue 4.3.

The required resistance grade for a safe is determined by the value of the contents of the safe. Insurers will define their own ratings depending on the performance of the safes and the situation in which the safes and strongrooms are to be used. It is therefore very important to communicate with insurers prior to selecting a safe or strongroom.

Kind regards,

Agnieszka Boryn  
Designing Out Crime Officer  
Kirklees District