

Technical Results

Description	Medium-grained Sandstone Durable with good weathering qualities	
Country of Origin	UK	
Geological Type	Carboniferous, Millstone Grit	
Colour	Buff / Yellow some faint Pink / Brown Iron Intrusions	
Density	2190 kg/m ³	
Compressive Strength	71 MPa	BS EN 1926 (1999)
Water Absorption	5.40 %	BS EN 13755
Porosity	16.90 %	BS EN 1936
Durability	Pass. Change in Flexural Strength 0.4 %	BS EN 1341 (2001)
Slip Resistance	Dry 94 Wet 79	BS EN 1341 (2000)
Abrasion Resistance	26.8 Moderate (Offices etc.)	BS EN 1341 (2000)
Acid Immersion	Pass	BRE 141
Breaking Load at Dowel Hole (parallel to edge)	Dry 3.47kN	BS EN 13364 (2002)
Average Block Size	1500L x 800W x 700H	