

PLANTING SCHEDULE

Native Shrub Mix

Abbrev.	Name	Girth/Dia. cm	Height cm	Root Zone	Specification	Mix %	No./m²	Area m²	Number
C san	Cornus sanguinea		40-60	B	1+1; Transplant - seed raised; branched; 2 brks	10.0	3	57.6	173
C mon	Crataegus monogyna		60-80	B	1+1; Transplant - seed raised	15.0	1	86.4	86
I a	Ilex aquifolium		40-60	2L	Leader with laterals	10.0	3	57.6	173
L vu	Ligustrum vulgare		40-60	B	0/1; Cutting; branched; 2 brks	10.0	3	57.6	173
P sp	Prunus spinosa		60-80	B	1+1; Transplant - seed raised; branched; 2 brks	15.0	3	86.4	259
R arv	Rosa arvensis		60-80	B	1+1; Transplant - seed raised; branched; 2 brks	10.0	2	57.6	115
R can	Rosa canina		60-80	B	1+1; Transplant - seed raised; branched; 3 brks	15.0	2	86.4	173
V op	Viburnum opulus		40-60	B	1+1; Transplant - seed raised; branched; 2 brks	15.0	2	86.4	173
					Sub-totals	100.0		576	1325

Planting Mix

Abbrev.	Name	Girth/Dia. cm	Height cm	Root Zone	Specification	Mix %	No./m²	Area m²	Number
A sco	Asplenium scolopendrium			1.5-2L	Full pot	12.5	4	9	36
C al 'S'	Cornus alba 'Sibirica'		40-60	3L	Branched; 3 brks	15.0	2	10.8	22
D f-m	Dryopteris filix-mas			1.5-2L	Full pot	15.0	2	10.8	22
E a r	Euphorbia amygdaloides robbiae			2L	Full pot	10.0	5	7.2	36
L sy	Luzula sylvatica			2L	Full pot	12.5	4	9	36
M a 'A'	Mahonia aquifolium 'Apollo'		15-20	2L	Branched; 2 brks	10.0	5	7.2	36
V d	Viburnum davidii		20-30	2L	Bushy; 2 brks	15.0	3	10.8	32
V mi 'G J'	Vinca minor 'Gertrude Jekyll'	20-30D		2L	Several shoots; 3 brks	10.0	5	7.2	36
					Sub-totals	100.0		72	256

OUTLINE SPECIFICATION:

GENERAL

All works to be in accordance all relevant British Standards and the Landscape Consultant's planting plans and specification (to be issued) and in compliance with the National Landscape Specification (NBS) 1998, latest revision.

SETTING OUT

All dimensions and levels should be checked and adjusted on site. Contractor responsible for care around all services. Do not scale from this drawing.

SITE PREPARATION

Building rubble in excess of 50mm dimension to be removed, compaction ripped 150mm deep or broken out by JCB back-actor leaving surface rough. Ensure free drainage.

TOPSOIL

Multipurpose topsoil BS:3882 medium loam, not more than slightly stoney, pH 5.7-7.5. Depth 450mm all planting areas. 150mm to all other areas. Provide Declaration of Analysis of topsoil to Employer's Agent.

TOPSOIL - MEADOW

Specific purpose topsoil to BS:3882, low fertility. 150mm depth to be used. Supplier to provide certification of testing.

TREE PIT

Transplants 300mmØ x 300mm depth

PREPARATORY HERBICIDE

Weed allowed to grow and treated with up to three applications of weed killer prior to cultivation or planting during the fallow period.

GRASSING

Grassing between April-October. Cultivate to prepare seed bed. Finished seed bed levels 25mm above pavings and kerb edges. Stones pick to 25mm. Pre-seeding fertiliser 50g/m2. Grass mix chosen for low maintenance requirements:- GRASS SEED MIX from Emorsgate:

EM2 Standard General Purpose Meadow Mixture sown at 4g/m2

PLANTS

General

Plant material in accordance with the HTA's National Plant Specification 1997. All plants container grown, well formed and free from disease. Plant handling to CPSE Plant Handling Code.

Quality as supplied by:

Johnson's of Whitley Ltd, York YO26 8AQ. Tel: 01423 330234. Or other nursery listed in the Horticultural Trades Association Nursery Certification Scheme.

Planting

Plant November to March. Planting areas cultivated 150 mm deep and stone picked of material greater than 50mm. Plant material pit planted 300 x 300 x 200 minimum. Approved planting compost incorporated into the soil during planting.

Backfill mix	Enmag	P4	Compost
Shrubs	35g	5g	10 litres
Transplants	35g	5g	10 litres

Backfill mix (30%) incorporated into topsoil (70%) during planting.

MULCH

Total cover coarse bark mulch to shrub areas, Melcourt Bark Nuggets 75mm deep.

AFTERCARE

24 months aftercare by planting contractor. Including grass and meadow cutting, weed, pest and disease control, pruning and watering. Weed control by residual herbicide or hand weeding as necessary to achieve a weed free condition. Watering in periods of drought to ensure establishment and continued thriving of planting.

DEFECTS LIABILITY

Twenty-four months on plant material and grass. Replacements in November in year of loss.

ONGOING MAINTENANCE

Continue to maintain for five years from completion of planting by hand weeding and spot treatment of weed killer to any weed in planted areas until plants close canopies. Replace failures for 5 years.

IMPLEMENTATION PROGRAMME:

First planting season following construction

LANDSCAPE MANAGEMENT:

Site Owner to implement 5-year management plan to cover the following regular, seasonal and annual maintenance operations:

Shrubs:

Remove litter
Water monthly April to September in periods of drought
Maintain plant beds weed free
Remove dead plants
Trim planting to prevent encroachment onto paths
Prune planting clear of all signage and sightlines
Prune hedges once annually
Firm up rocked plants
Eradicate any occurrence of Japanese Knotweed

Meadow Grass

Cut twice annually in spring and autumn
Remove litter

Plant failures

Replace any dead plants in following planting season (Nov - Mar).

FOR PLANNING

WEDDLES

MAIL@WEDDLES.CO.UK LANDSCAPE
WEDDLES.CO.UK ARBORICULTURE
0114 250 1181 GARDEN DESIGN
UNIT 4 WESTBROOK COURT
SHEFFIELD, S11 8YZ ECOLOGY

Job ASHBROW ROAD, HUDDERSFIELD

Title
PLANTING SCHEDULE AND
MANAGEMENT PLAN

scale@A3	drawn	date	drawing number	revision
N/A	JM	APR 26	2212-002	-