ARBORICULTURAL CONDITION REPORT at: Huddersfield Grammar School Luck Lane Marsh Huddersfield West Yorkshire HD1 4QX

Client:
Huddersfield Grammar School

Client Address:
Luck Lane
Marsh
Huddersfield
West Yorkshire
HD1 4QX

Client Telephone:
01484 424549

JCA Ref:
23001/AJB



JCA Limited
Arboricultural & Ecological Consultants

Contents

1. Introduction 3
1.1 Purpose of the Report 3
1.2 Terms of Reference 3
1.3 Scope of the Report 3
1.4 Survey Details 3
2. Status of the Trees 4
3. Discussion & Recommendations 5

Appendix 1: Tree Descriptions and Recommendations 8
Appendix 2: Arboricultural Terms of Reference 9
Appendix 3: Author Qualifications 11
Appendix 4: General Guidelines 12
Appendix 5: Site Plan 13

© JCA Limited 2025

1. Introduction

1.1 Purpose of the Report

1.1.1 This report details the findings of an expert arboricultural condition survey and risk assessment of the trees at **Huddersfield Grammar School**, **Luck Lane**, **Marsh**, **Huddersfield**.

1.1.2 This report details the relevant arboricultural information which is required to inform the owners of the condition of their trees and provides specific management actions that, once undertaken, demonstrate that a duty of care has been taken with regards to tree management.

1.2 Terms of Reference

1.2.1 JCA Limited are instructed by **Huddersfield Grammar School** to visit the site, inspect the trees and prepare our findings and any recommendations in a report.

1.2.2 For this purpose, we have used an Ordnance Survey plan onto which the trees have been plotted in relation to their surroundings. The tree locations are indicative however and this plan should not be scaled from.

1.3 Scope of the Report

1.3.1 This report, and any recommendations made are compiled in accordance with current industry standards and best arboricultural practice.

1.3.2 The trees have been inspected to assess and, if necessary, reduce their potential risk of harm.

1.4 Survey Details

1.4.1 The survey was conducted during August 2025 by **Andrew Bussey** *LANTRA Accredited PTI, TechArborA*.

1.4.2 Inspection was made visually from ground level, in order to assess the trees condition and potential to cause harm.

1.4.3 Where necessary, management recommendations have been made. This may include tree removal, pruning, future monitoring or the need for a further detailed inspection, such as climbed inspections or decay detection surveys.


1.4.4 Measurements were obtained using clinometers, specialist tapes or electronic distometers. Where this was not possible measurements were estimated.

© JCA Limited 2025

2. Status of the Trees

2.1 A check was made with **Kirklees Metropolitan Council** in August 2025 to determine whether any of the trees surveyed as part of this report are subject to any statutory controls.

2.2 We are informed that there are several Tree Preservation Orders (TPO's) in force on site, which are identified as **03/79/w5, 03/79/w6, 03/79/w7, 03/79/a1, 03/79/ t27** and **03/79/t28**. These cover all the trees growing around the perimeter of the site and several individual trees/groups of trees located more centrally (per the image below).



2.3 Due to the various TPO's present on site, it is recommended that a further check is made prior to any tree works being organised.

2.4 **No work must be undertaken to those trees subject to a Tree Preservation Order until an approved Works to Protected Trees application has been granted.**

2.5 Prior to any works being undertaken to trees, those instructing and proposing to carry out the work should satisfy themselves that all appropriate consents are in place to prevent a potential breach of legislation.

© JCA Limited 2025

3. Discussion & Recommendations

3.1 In total **377** items of vegetation were surveyed (**375** individual trees and **2** groups of trees). In addition to the surveyed vegetation, **27** trees were observed to have been removed since the previous arboricultural inspection (as previously advised) and have been recorded as such.

3.2 Full details of all the trees surveyed are recorded in the tables at **Appendix 1**. Please refer to **Appendix 2** for a full explanation of the tables and to the Site Plan at **Appendix 5** for locations.

3.3 **T87, T120, T132, T136, T137, T146, T242, T264, T311, T313B, T313C, T322, T342, T384, T385, T391** and **T400** have been recommended for removal for arboricultural reasons as a matter of **low** or **moderate** priority, as detailed at **Appendix 1**.

3.4 **T6, T10, T11, T14, T92, T113, T122, T135, T146, T178, T191, T228, T243, T251, T255, T257, T264, T288, T298, T312, T325** and **T380** require pruning to reduce their potential risk of harm or for general tree management purposes as a matter of **low** or **modertate priority**, as detailed at **Appendix 1**.

3.5 Where trees are situated close to services, road signs, streetlights, or where they overhang roads, paths or boundaries, they will require monitoring and occasional maintenance. This should maintain visibility and safe public access. Such work is ongoing and should be conducted on a regular basis.

3.6 A number of trees were noted to have structural or physiological defects, as detailed at **Appendix 1**. Although these trees were considered to be in an acceptable condition at the time of the inspection, the defects observed may lead to their early demise or render them unsafe in the future. As such, it is recommended that these trees be monitored and re-inspected on an annual or biennial basis (as detailed at **Appendix 1**), to assess if their condition is still acceptable.

3.7 Ash dieback is a highly destructive fungal disease affecting Ash trees. Progress of the disease within infected trees can lead to dead or dying branches becoming brittle and falling. It can also leave the trees more susceptible to other diseases or pathogens which can result in major limb or stem failure. Timescales for decline are difficult to define and are dependent on multiple physiological and environmental factors. It is recommended that healthy trees are not felled in anticipation of the disease to allow the opportunity for recovery or the development of resistant strains, but also to protect their ecological value to the surrounding landscape. Regular monitoring and appropriate management strategies can be put in place to facilitate the retention of Ash trees whilst limiting potential hazards.

3.8 A full detailed inspection of **T24, T38, T41, T61, T62, T64, T70, T74, T81, T82, T114, T115, T173, T198, T209, T210, T211, T213, T214, T215, T216, T258, T261, T262, T263, T265, T278, T285, T286, T287, T363, T364, T368, T369, T371** and **T382**, was inhibited by the presence of Ivy, epicormic shoots or vegetation, as detailed at **Appendix 1**. It is advised that these trees are re-inspected for defects once the Ivy, epicormic shoots or vegetation has been removed.

© JCA Limited 2025

3.9 Following the completion of the works prescribed in this report, in the interest of risk management, we recommend that the trees are re-surveyed as per the recommended schedule. Ideally, each new inspection should be undertaken during a different season to observe defects, pests and diseases that are only evident at certain times of the year. We further advise the ongoing monitoring and maintenance of the trees to mitigate risks associated with changing environmental factors.

3.10 Whilst JCA Limited conducts thorough tree surveys, our assessments and recommendations are based on the conditions observed at the time of the survey. Extreme weather conditions, including severe storms and the impacts of climate change, can lead to unforeseen tree failures. As such, we cannot be held responsible for any tree failures or related incidents that occur as a result of such extreme weather events.

3.11 We would be happy to assist should you have any queries regarding the points raised in **Section 3**.

© JCA Limited 2025

Appendices

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 1	Early-mature Sycamore *Acer pseudoplatanus*	14	4	29	4	Single stemmed and vertical with a balanced crown. The crown overhangs the car park. Occasional pruning wounds (generally occluding well). Minor deadwood in the crown and a minor wound on the stem at 1m noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
G 2	Semi-mature Leyland Cypress *X Cupressocyparis leylandii*	To 10	0	17	2	A group of three vertical trees. No major visible defects.	GOOD	GOOD	40+	HIGH	No action required.	N/A	A	2
T 3	Early-mature Common Beech *Fagus sylvatica*	18	3	75	13	Single stemmed and vertical with a balanced crown. The crown overhangs the car park and driveway. Occasional pruning wounds due to crown lifting, generally occluding well. Deadwood (minor) an occasional tear wounds noted.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 4	Semi-mature Common Holly *Ilex aquifolium*	8	2	19	3	Twin stemmed at ground level with a tight union noted. The crown overhangs the car park. Occasional pruning wounds due to crown lifting (generally occluding well).	GOOD	GOOD	40+	HIGH	No action required.	N/A	A	2
T 5	Mature Common Ash *Fraxinus excelsior*	20	9	76	14	Twin stemmed at ground level with vertical stems and a balanced crown. The crown overhangs the driveway and the car park. Multiple pruning wounds due to crown lifting (occluding slowly). Large pruning wounds with occasional cavities forming. Minor Ash Die-back noted.	FAIR	FAIR	20-40	HIGH	Monitor the cavities and the Ash Die-back annually.	MOD	B	1
T 6	Early-mature Sycamore *Acer pseudoplatanus*	18	6	76	8	Single stemmed and vertical with a balanced crown. The crown overhangs the driveway. Multiple pruning wounds due to crown lifting (occluding slowly) and some with the onset of decay. Deadwood (minor) and basal bark wounds noted.	FAIR	FAIR	20-40	HIGH	Remove the deadwood. Monitor biennially.	LOW	B	2
T 7	Mature Sycamore *Acer pseudoplatanus*	18	5	89	11	Single stemmed and vertical with a balanced crown. The crown overhangs the driveway. Multiple pruning wounds. Previously topped now with mature regrowth. Minor basal wounds noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 8	Early-mature Common Holly *Ilex aquifolium*	14	3	32	6	Single stemmed and vertical with a balanced crown. The crown overhangs the driveway. Occasional pruning wounds due to crown lifting (generally occluding well). Occasional bark wounds.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 9	Semi-mature Common Holly *Ilex aquifolium*	9	4	22	6	Twin stemmed at 0.3m with a slightly unbalanced crown; a suppressed specimen. The crown overhangs the driveway. Occasional pruning wounds due to crown lifting (generally occluding well). Bark wounds noted. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 10	Mature Common Beech *Fagus sylvatica*	21	4	83	14	Twin stemmed at 1.2m with vertical stems. The crown overhangs the driveway and the car park. Multiple pruning wounds due to crown lifting (occluding slowly). Major rubbing limbs from 2.5m to 8m with significant wounding; a potential failure point. Crown reduce to limit the potential for failure.	FAIR	FAIR	20-40	HIGH	Reduce the crown by 6m in height and blend the sides to re-balance.	MOD	B	1
T 11	Mature Sycamore *Acer pseudoplatanus*	20	6	89	12	Single stemmed and vertical with a balanced crown. The crown overhangs the driveway and car park. Occasional pruning wounds due to crown lifting (generally occluding well). Previously topped; now with mature regrowth. A sparse crown suggests the tree may be in decline. Moderate deadwood noted.	FAIR	FAIR	10-20	HIGH	Remove the deadwood. Monitor annually.	MOD	B	1
T 12	Early-mature Common Oak *Quercus robur*	21	5	77	14	Single stemmed and vertical with a balanced crown. The crown overhangs the car park and building. Multiple pruning wounds due to crown lifting (occluding slowly).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 13	Early-mature Sessile Oak *Quercus petraea*	21	4	59	10	Single stemmed and vertical with a balanced crown. The crown overhangs the car park and the building. Occasional pruning wounds due to crown lifting (generally occluding well). Deadwood (minor) and a minor basal wound noted. No major visible defects.	GOOD	GOOD	40+	HIGH	No action required.	N/A	A	2
T 14	Early-mature Common Ash *Fraxinus excelsior*	17	11	54	8	Twin stemmed at 5m with vertical stems. The crown overhangs the car park and the boundary. Multiple pruning wounds due to crown lifting (generally occluding well). A sparse crown with deadwood noted. A cavity is present at a height of circa 7m. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Remove the deadwood. Monitor the sparse crown, Ash Dieback and the cavity annually.	MOD	B	1
T 15	Mature Sycamore *Acer pseudoplatanus*	20	4	89	13	Single stemmed and vertical with a balanced crown. The crown overhangs the car park. No major visible defects.	GOOD	GOOD	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 16	Early-mature Common Beech *Fagus sylvatica*	21	2	85	10	Single stemmed and vertical with a balanced crown. The crown overhangs the car park. No major visible defects.	GOOD	GOOD	20-40	HIGH	No action required.	N/A	A	2
T 17	Early-mature Sycamore *Acer pseudoplatanus*	16	4	41	8	Single stemmed and vertical with an unbalanced crown; a suppressed specimen. The crown overhangs the boundary.	GOOD	FAIR	20-40	HIGH	Monitor biennially.	LOW	B	2
T 18	This tree has now been removed.													
T 19	Early-mature Common Ash *Fraxinus excelsior*	18	8	39	7	Single stemmed and vertical with a balanced yet sparse crown. The crown overhangs the car park. Minor Ash Dieback noted.	FAIR	FAIR	20-40	HIGH	Monitor biennially.	LOW	B	2
T 20	This tree has now been removed.													
T 21	Mature Common Ash *Fraxinus excelsior*	22	5	75	15	Twin stemmed at 4m with vertical stems. The crown overhangs the car park and the boundary. Over extended branches noted to the north. Moderate Ash Dieback noted.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 22	Early-mature Sycamore *Acer pseudoplatanus*	12	5	30	5	Single stemmed and vertical. A suppressed specimen. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 23	Early-mature Common Beech *Fagus sylvatica*	15	2	37	7	Single stemmed and vertical with a balanced crown. Close to the car park. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 24	Early-mature Sycamore *Acer pseudoplatanus*	19	4	37	6	Single stemmed and vertical with a balanced crown. Dense vegetation at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation then re-inspect.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 25	Early-mature Sycamore *Acer pseudoplatanus*	15	9	35	8	Single stemmed and vertical with an unbalanced crown. A suppressed specimen.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 26	Mature Sycamore *Acer pseudoplatanus*	21	10	85	12	Single stemmed and vertical with a balanced crown. Dense vegetation at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 27	Early-mature Sycamore *Acer pseudoplatanus*	17	3	30	6	Single stemmed and vertical with an unbalanced crown. A suppressed specimen.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 28	Early-mature Sycamore *Acer pseudoplatanus*	18	8	55	6	Single stemmed and vertical with an unbalanced crown. A suppressed specimen.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 29	Early-mature Sycamore *Acer pseudoplatanus*	19	7	39	8	Twin stemmed at ground level with vertical stems. The crown, which is slightly unbalanced, overhangs the road.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 30	This tree has now been removed.													
T 31	Early-mature Sycamore *Acer pseudoplatanus*	16	5	33	6	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the road. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 32	Early-mature Sycamore *Acer pseudoplatanus*	21	16	37	6	Single stemmed and vertical with a slightly unbalanced crown. A drawn up specimen close to the car park. Dense vegetation at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 33	Early-mature Common Ash *Fraxinus excelsior*	23	17	34	7	Single stemmed and vertical with a slightly unbalanced crown. A drawn up specimen close to the car park. Dense vegetation at the base prevented a detailed inspection. Minor Ash Dieback noted.	FAIR	FAIR	20-40	HIGH	Monitor biennially.	MOD	B	2
T 34	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	16	2	36	9	Single stemmed and vertical with a balanced crown. The ground level has been raised around the base.	FAIR	FAIR	<10	HIGH	Monitor annually.	HIGH	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 35	Early-mature Sycamore *Acer pseudoplatanus*	21	17	41	8	Single stemmed and vertical with a balanced crown. A drawn up specimen. Dense vegetation at the base prevented a detailed inspection.	FAIR	DEAD	20-40	HIGH	No action required.	N/A	A	2
T 36	Mature Sycamore *Acer pseudoplatanus*	22	16	73	8	Single stemmed and vertical with a balanced crown.	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 37	Early-mature Sycamore *Acer pseudoplatanus*	19	4	65	9	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the road. Vegetation at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 38	Early-mature Common Beech *Fagus sylvatica*	17	4	54	8	Single stemmed and vertical with a balanced crown. Deadwood noted. Dense vegetation at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation then re-inspect.	HIGH	B	1
T 39	Early-mature Sycamore *Acer pseudoplatanus*	16	4	37	7	Single stemmed and vertical with an unbalanced crown; a suppressed specimen. The crown overhangs the road. Deadwood noted (minor).	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 40	Early-mature Common Beech *Fagus sylvatica*	19	3	38	6	Single stemmed and vertical with a balanced crown. Close to the road. Deadwood noted (minor). No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 41	Early-mature Sycamore *Acer pseudoplatanus*	18	4	36	7	Single stemmed and vertical with an unbalanced crown. Close to the road. Epicormic growth and dense vegetation at the base prevented a detailed inspection.	FAIR	FAIR	10-20	HIGH	Remove the epicormic growth and the vegetation then re-inspect.	HIGH	B	1
T 42	Semi-mature Sycamore *Acer pseudoplatanus*	11	6	26	6	Single stemmed and vertical with an unbalanced crown; a suppressed specimen. The crown overhangs the footpath and road.	FAIR	FAIR	40+	HIGH	No action required.	N/A	A	2
T 43	This tree has now been removed.													
T 44	Early-mature Common Ash *Fraxinus excelsior*	18	13	51	11	Single stemmed and vertical with a balanced crown. The ground level has been raised around the base. Minor Ash Dieback noted.	FAIR	FAIR	<10	HIGH	Monitor annually.	HIGH	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 45	Early-mature Norway Maple *Acer platanoides*	18	5	52	9	Single stemmed and vertical with a balanced crown. The crown overhangs the car park. The ground level has been raised around the base. A vertical wound noted to the lower stem.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 46	Early-mature Common Ash *Fraxinus excelsior*	18	5	31	8	Single stemmed and vertical with an unbalanced crown. The crown overhangs the car park. The ground level has been raised around the base. Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	HIGH	B	2
T 47	Semi-mature Sycamore *Acer pseudoplatanus*	13	9	16	3	Single stemmed and vertical with a balanced crown. The crown overhangs the car park. The ground level has been raised around the base.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	HIGH	B	2
T 48	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	15	4	27	7	Single stemmed and vertical with a balanced crown. The crown overhangs the car park. The ground level has been raised around the base.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	HIGH	B	1
T 49	Semi-mature Sycamore *Acer pseudoplatanus*	14	3	20	5	Single-stemmed and vertical with a balanced crown. No evidence of significant pruning. No major visible defects.	GOOD	GOOD	20-40	MOD	No action required.	N/A	A	2
T 50	Early-mature Common Ash *Fraxinus excelsior*	21	13	41	9	Single stemmed and vertical with a balanced crown. Previously topped. The crown overhangs the car park. The ground level has been raised around the base. A bark wound noted to the lower stem.	FAIR	FAIR	10-20	HIGH	Monitor annually.	HIGH	B	1
T 51	This tree has now been removed.													
T 52	This tree has now been removed.													
T 53	Early-mature Common Ash *Fraxinus excelsior*	22	15	37	9	Single stemmed and vertical with a balanced crown. Minor Ash Dieback noted.	FAIR	FAIR	20-40	HIGH	Monitor biennially.	MOD	B	2
T 54	Early-mature Sycamore *Acer pseudoplatanus*	22	18	29	7	Single stemmed and slightly leaning with an unbalanced crown.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 55	Mature Sycamore *Acer pseudoplatanus*	22	10	70	9	Single stemmed and vertical with a balanced crown.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 56	Semi-mature Sycamore *Acer pseudoplatanus*	17	11	24	4	Single stemmed and vertical with a slightly unbalanced crown.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 57	Early-mature Sycamore *Acer pseudoplatanus*	18	13	27	4	Single stemmed and vertical with an unbalanced crown.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 58	Semi-mature Sycamore *Acer pseudoplatanus*	15	7	21	4	Twin stemmed at the base with vertical stems and a slightly unbalanced crown. The crown overhangs the road.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 59	Semi-mature Sycamore *Acer pseudoplatanus*	10	6	17	3	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the road. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 60	Semi-mature Sycamore *Acer pseudoplatanus*	13	6	26	5	Single stemmed and vertical with a balanced crown. The crown overhangs the road.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 61	Early-mature Common Lime *Tilia europaea*	20	2	48	9	Single stemmed and vertical with a balanced crown. The crown overhangs the road. Ivy and epicormic growth at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the epicormic growth and the Ivy then re-inspect.	HIGH	B	1
T 62	Early-mature Common Beech *Fagus sylvatica*	17	3	29	7	Single stemmed and vertical with a balanced crown. The crown overhangs the road. Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1
T 63	Early-mature Lawson Cypress *Chamaecyparis lawsoniana*	16	2	27	3	Single stemmed and vertical with a balanced crown. Close to the road. Ivy at the base. Appears to be in an acceptable condition at present.	GOOD	FAIR	40+	HIGH	No action required.	N/A	A	2
T 64	Early-mature Common Beech *Fagus sylvatica*	15	3	27	6	Single stemmed and vertical with a balanced crown. The crown overhangs the road. Occasional pruning wounds due to crown lifting. Ivy on the stem.	GOOD	GOOD	40+	HIGH	Remove the Ivy then re-inspect.	LOW	B	2
T 65	Early-mature Silver Birch *Betula pendula*	20	10	28	5	Single stemmed and vertical with a balanced crown. A drawn up specimen. The crown overhangs the road.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 66	Early-mature Common Oak *Quercus robur*	12	3	27	7	Single stemmed with a slight lean and a slightly unbalanced crown; a suppressed specimen. Close to the road. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 67	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	8	1	23	5	Single stemmed and vertical with a slightly unbalanced crown. Close to the road. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 68	Early-mature Common Ash *Fraxinus excelsior*	3	1.5	29	2	Twin stemmed at 1.5m. Previously topped.	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2
T 69	Mature Sycamore *Acer pseudoplatanus*	17	6	71	11	Single stemmed and vertical with a balanced crown. The crown overhangs the road and the footpath. Multiple pruning wounds due to crown lifting (occluding slowly) and cavities in the stem on the old pruning wounds.	FAIR	FAIR	20-40	HIGH	Monitor the cavities annually.	LOW	B	1
T 70	Early-mature Poplar *Populus sp.*	16	8	43	7	Single stemmed with a slight lean and a slightly unbalanced crown. Close to the road. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	10-20	HIGH	Remove the Ivy then re-inspect.	HIGH	B	1
T 71	Semi-mature Leyland Cypress *X Cupressocyparis leylandii*	11	2	18	2	Single stemmed and vertical with a balanced crown. Close to the road. No major visible defects.	GOOD	GOOD	40+	HIGH	No action required.	N/A	A	2
T 72	Early-mature Leyland Cypress *X Cupressocyparis leylandii*	17	2	38	3	Single stemmed and vertical with a balanced crown. Close to the road. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 73	Early-mature Common Holly *Ilex aquifolium*	12	0.5	23	6	Multiple stemmed at ground level with a balanced crown. Close to the road. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 74	Early-mature Sycamore *Acer pseudoplatanus*	13	5	31	4	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the road. Occasional pruning wounds due to crown lifting. Ivy prevented a detailed inspection. The ground level has been raised around the base.	FAIR	FAIR	10-20	HIGH	Remove the Ivy then re-inspect.	MOD	B	1
T 75	Semi-mature Sycamore *Acer pseudoplatanus*	16	5	27	6	Single stemmed and vertical with a slightly unbalanced crown. Close to the road. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 76	Semi-mature Sycamore *Acer pseudoplatanus*	9	2	14	4	Single stemmed and vertical with a slightly unbalanced crown. Close to the road. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 77	Semi-mature Leyland Cypress *X Cupressocyparis leylandii*	8	1	17	2	Single stemmed and vertical with a balanced crown. Close to the road. No major visible defects.	GOOD	GOOD	20-40	HIGH	No action required.	N/A	A	2
T 78	Early-mature Silver Birch *Betula pendula*	16	2	27	5	Single stemmed and vertical with a balanced crown. Close to the road. Branch tip die-back noted.	GOOD	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 79	Semi-mature Sycamore *Acer pseudoplatanus*	8	3	15	3	Single stemmed and vertical with a slightly unbalanced crown. Close to the road. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 80	Early-mature Sycamore *Acer pseudoplatanus*	15	6	37	7	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the road. Ground level raised at the base.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 81	Early-mature Sycamore *Acer pseudoplatanus*	15	4	26	6	Twin stemmed at 0.5m with vertical stems. Dense vegetation at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation then re-inspect.	HIGH	B	1
T 82	Early-mature Sycamore *Acer pseudoplatanus*	17	6	47	8	Twin stemmed at 3.5m with vertical stems. The crown overhangs the road. Multiple pruning wounds due to crown lifting. Epicormic growth and dense vegetation at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the epicormic growth and the vegetation then re-inspect.	MOD	B	1
T 83	Early-mature Common Hawthorn *Crataegus monogyna*	8	3	22	2	Multiple stemmed at 1m with vertical stems and a slightly unbalanced crown. Close to the road. Occasional pruning wounds due to crown lifting. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 84	Early-mature Sycamore *Acer pseudoplatanus*	14	7	26	5	Twin stemmed at ground level with vertical stems and a slightly unbalanced crown. Close to the road. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 85	Early-mature Sycamore *Acer pseudoplatanus*	14	5	29	5	Single stemmed and vertical with a balanced crown. Close to the road. Occasional pruning wounds due to crown lifting. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 86	Dead Elm *Ulmus sp.*	8	8	29	0	A dead standing stem close to the benches.	DEAD	DEAD	<10	MOD	No action required.	N/A	A	n/a
T 87	Early-mature Common Beech *Fagus sylvatica*	8	2	32	12	Single-stemmed and leaning with an unbalanced crown; poor form. A significant bark wound is present at a stem junction. Limited long term future.	FAIR	POOR	<10	MOD	Remove to ground level.	MOD	R	n/a
T 88	Early-mature Whitebeam *Sorbus aria*	12	6	26	5	Single stemmed and vertical with a balanced crown. Occasional pruning wounds due to crown lifting (generally occluding well). No major visible defects.	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2
T 89	Early-mature Common Lime *Tilia europaea*	18	3	54	11	Single stemmed and vertical with a balanced crown. Occasional pruning wounds due to crown lifting. Deadwood (minor) and over extended branches noted.	GOOD	FAIR	40+	HIGH	No action required.	N/A	A	2
T 90	Early-mature Mountain Ash *Sorbus aucuparia*	12	6	26	3	Single stemmed and vertical with a slightly unbalanced crown. No major visible defects.	GOOD	FAIR	10-20	MOD	No action required.	N/A	A	2
T 91	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	33.3	40	15	11	A topped standing stem with regrowth.	POOR	POOR	<10	MOD	Monitor biennially.	LOW	B	2
T 92	Early-mature Common Ash *Fraxinus excelsior*	19	2.5	39	9	Single stemmed and vertical with a slightly unbalanced crown. Close to the road. Occasional pruning wounds, moderate deadwood and tear wounds observed. Minor Ash Dieback noted.	FAIR	FAIR	20-40	HIGH	Crown clean to remove the deadwood. Monitor biennially.	MOD	B	2
T 93	Semi-mature Common Beech *Fagus sylvatica*	9	2	12	3	Single stemmed and vertical with a balanced crown. Close to the road. No major visible defects.	GOOD	GOOD	40+	MOD	No action required.	N/A	A	2
T 94	Early-mature Common Ash *Fraxinus excelsior*	17	9	37	11	Single stemmed and vertical with a slightly unbalanced crown. Close to the road. Deadwood (minor) and minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 95	Early-mature Sycamore *Acer pseudoplatanus*	17	7	27	6	Single stemmed and vertical with a balanced crown. Close to the road. Occasional pruning wounds due to crown lifting (generally occluding well). Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 96	Early-mature Sycamore *Acer pseudoplatanus*	17	9	37	8	Single stemmed and vertical with a balanced crown. The crown overhangs the road. Occasional pruning wounds due to crown lifting. Squirrel damage noted throughout.	FAIR	FAIR	20-40	HIGH	Monitor the Squirrel damage biennially.	LOW	B	2
T 97	Early-mature Common Oak *Quercus robur*	17	8	37	9	Single stemmed and vertical with an unbalanced crown. The crown overhangs the road. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 98	This tree has now collapsed.													
T 99	Early-mature Whitebeam *Sorbus aria*	8	3	26	4	Single stemmed and vertical with a balanced crown; a suppressed specimen. Occasional pruning wounds due to crown lifting (generally occluding well). Deadwood noted (minor).	GOOD	FAIR	10-20	MOD	No action required.	N/A	A	2
T 100	Early-mature Common Ash *Fraxinus excelsior*	19	13	33	6	Single stemmed and vertical with a balanced crown. Occasional pruning wounds due to crown lifting (occluding slowly). Deadwood (minor) and minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 101	Semi-mature Common Beech *Fagus sylvatica*	9	3	26	5	Single stemmed and vertical with a balanced crown. Occasional pruning wounds and bark wounding with decay at 0.4m noted.	FAIR	FAIR	20-40	MOD	Monitor the progress of the decay.	MOD	B	1
T 102	Early-mature Common Lime *Tilia europaea*	17	7	34	7	Single stemmed and vertical with a balanced crown. Occasional pruning wounds and minor deadwood noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 103	Early-mature Common Ash *Fraxinus excelsior*	17	13	26	5	Single stemmed and vertical with a slightly unbalanced crown. Occasional pruning wounds due to crown lifting (occluding slowly). Minor deadwood and minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 104	Early-mature Common Ash *Fraxinus excelsior*	17	9	43	9	Multiple stemmed at 2.5m with vertical stems. Occasional pruning wounds due to crown lifting. An area of missing bark with the onset of decay from ground level to 1m noted. Minor Ash Dieback observed.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 105	Mature Sycamore *Acer pseudoplatanus*	18	2.5	65	9	Single stemmed and vertical with an unbalanced crown. Occasional pruning wounds due to crown lifting (occluding slowly). A mechanical wound with minor decay noted on the underside of the lowest branch.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 106	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	12	3	26	4	Single stemmed and vertical with an unbalanced crown. Wounding with decay forming at the base.	FAIR	FAIR	<10	MOD	Monitor annually.	MOD	B	1
T 107	Early-mature Common Lime *Tilia europaea*	18	8	39	7	Single stemmed and vertical with a balanced crown. Multiple pruning wounds due to crown lifting (occluding slowly). Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 108	Early-mature Common Ash *Fraxinus excelsior*	18	10	29	6	Single stemmed and vertical with a balanced crown. Drawn up specimen. Basal bark wounds with the onset of decay. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 109	Early-mature Common Ash *Fraxinus excelsior*	18	10	34	6	Single stemmed and vertical with a balanced crown. A drawn up specimen. Occasional pruning wounds due to crown lifting (occluding slowly). Bark wounding with decay at 1m. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 110	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	18	3	45	9	Twin stemmed at 2m with minor included bark. The crown overhangs the road. Occasional pruning wounds due to crown lifting. Early Bleeding Canker of Horse Chestnut with linear bark cracking noted.	FAIR	FAIR	10-20	HIGH	Monitor the progress of the Bleeding Canker of Horse Chestnut annually.	MOD	B	1
T 111	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	17	2	27	5	Single stemmed and vertical with a slightly unbalanced crown. The tree is showing the early symptoms of Bleeding Canker of Horse Chestnut.	FAIR	FAIR	20-40	MOD	Monitor the progress of the Bleeding Canker of Horse Chestnut annually.	MOD	B	1
T 112	Early-mature Common Ash *Fraxinus excelsior*	19	5	45	9	Twin stemmed at 3m with vertical stems and a slightly unbalanced crown. The crown overhangs the road. Epicormic growth in the crown suggests possible stress. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 113	Early-mature Elm *Ulmus sp.*	7	5	45	4	A 1.5m tall stump with poorly attached regrowth.	FAIR	FAIR	<10	HIGH	Remove the regrowth to avoid potential failure into the road.	MOD	B	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 114	Semi-mature Common Hawthorn *Crataegus monogyna*	7	1	24	3	Single stemmed with a slight lean with a slightly unbalanced crown. The crown overhangs the footpath. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	2
T 115	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	17	5	41	9	Single stemmed and vertical with a balanced crown. The crown overhangs the road. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1
T 116	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	19	3	42	11	Twin stemmed at 1m with vertical stems. The tree is showing the early symptoms of Bleeding Canker of Horse Chestnut.	FAIR	FAIR	10-20	HIGH	Monitor the progress of the Bleeding Canker of Horse Chestnut annually.	MOD	B	1
T 117	Early-mature Sycamore *Acer pseudoplatanus*	17	3	45	8	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the sports field. Occasional pruning wounds due to crown lifting. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 118	Early-mature Common Lime *Tilia europaea*	19	7	38	7	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 119	Early-mature Sycamore *Acer pseudoplatanus*	19	2	40	11	Twin stemmed at 3m with vertical stems and an unbalanced crown. The crown overhangs the sports field. Occasional pruning wounds due to crown lifting. Minor deadwood and over extended branches noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 120	Early-mature Common Beech *Fagus sylvatica*	18	3	37	9	Twin stemmed at 1m with vertical stems. The crown overhangs the sports field. Decay forming at the base with significant dark exudates to the stem. Limited long term future.	POOR	FAIR	<10	HIGH	Remove.	LOW	R	n/a
T 121	Semi-mature Common Lime *Tilia europaea*	12	9	12	3	Single stemmed and vertical with a balanced crown. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 122	Early-mature Common Ash *Fraxinus excelsior*	17	9	33	9	Single stemmed and vertical with a balanced crown. The crown overhangs the sports field. Deadwood and minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Remove the deadwood. Monitor annually.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 123	Early-mature Common Beech *Fagus sylvatica*	17	4	37	9	Twin stemmed at 1.5m and slightly leaning with an unbalanced crown. The crown overhangs the sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 124	Early-mature Common Holly *Ilex aquifolium*	12	0	27	8	Multiple stemmed at ground level with vertical stems. No major visible defects.	GOOD	GOOD	20-40	MOD	No action required.	N/A	A	2
T 125	Early-mature Common Oak *Quercus robur*	18	3	39	9	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the sports field. Cavities in the stem and a large tear wound at 9m noted.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 126	Early-mature Whitebeam *Sorbus aria*	11	2	21	4	Single stemmed and vertical with a balanced crown; a suppressed specimen. Close to the footpath. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 127	Early-mature Mountain Ash *Sorbus aucuparia*	12	1	27	5	Single stemmed and vertical with a slightly unbalanced crown. Close to the footpath. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 128	Early-mature Sycamore *Acer pseudoplatanus*	17	7	43	9	Single stemmed and vertical with a balanced crown. The crown overhangs the road. Previously topped and now with mature re-growth. Some decay likely at the topping points.	FAIR	FAIR	20-40	LOW	Monitor annually.	MOD	B	1
T 129	Early-mature Common Ash *Fraxinus excelsior*	18	4	29	6	Single stemmed and vertical with a balanced crown. Cavities in the stem. Cavities at ground level and 6m. Minor Ash Dieback noted.	GOOD	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 130	Semi-mature Common Ash *Fraxinus excelsior*	6	6	23	0	A dead standing stem. Acceptable to retain at present due to its position in relation to targets.	DEAD	DEAD	<10	LOW	No action required.	N/A	A	2
T 131	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	17	4	31	8	Single stemmed and vertical with a balanced crown. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 132	Mature Common Horse Chestnut *Aesculus hippocastanum*	19	3	65	9	Twin stemmed at ground level with vertical stems. The crown overhangs the sports field. Bleeding Canker of Horse Chestnut noted with significant bark cracking with decay and significant dieback to the crown.	POOR	POOR	<10	HIGH	Remove.	MOD	R	N/A

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 133	Early-mature Common Lime *Tilia europaea*	18	7	40	9	Single-stemmed and vertical with a balanced crown. No evidence of significant pruning. No major visible defects.	GOOD	GOOD	40+	LOW	No action required.	N/A	A	2
T 134	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	14	2	37	7	Single stemmed and vertical with an unbalanced crown; a suppressed specimen. The crown overhangs the sports field. Bleeding Canker of Horse Chestnut noted.	FAIR	FAIR	10-20	HIGH	Monitor the progress of the Bleeding Canker of Horse Chestnut annually.	MOD	B	1
T 135	Early-mature Common Ash *Fraxinus excelsior*	21	3	68	12	Twin stemmed at 2m with vertical stems and a slightly unbalanced crown. The crown overhangs the sports field. Occasional pruning wounds, major deadwood and over extended branches observed. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Crown clean to remove the deadwood. Monitor biennially.	MOD	B	2
T 136	Semi-mature Common Ash *Fraxinus excelsior*	11	11	21	0	A dead tree.	DEAD	DEAD	<10	MOD	Remove.	MOD	R	n/a
T 137	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	11	2	19	4	Single stemmed and vertical with a slightly unbalanced crown. A cavity at the base with worsening decay. Limited long term future.	FAIR	POOR	<10	MOD	Remove.	MOD	R	n/a
T 138	Early-mature Common Ash *Fraxinus excelsior*	19	11	29	8	Single stemmed and vertical with a slightly unbalanced crown. Close to the road. The ground level has been raised at the base. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 139	Semi-mature Common Lime *Tilia europaea*	9	2	12	4	Single stemmed and vertical with a balanced crown. The ground level has been raised at the base.	FAIR	FAIR	10-20	LOW	Monitor annually.	MOD	B	1
T 140	Early-mature Common Ash *Fraxinus excelsior*	19	11	28	6	Single stemmed and vertical with a balanced crown. The ground level has been raised at the base. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 141	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	17	1	33	7	Single stemmed and vertical with a balanced crown. The ground level has been raised at the base.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 142	This tree has now been removed.													

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 143	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	16	2	23	5	Single stemmed and vertical with an unbalanced crown. A cavity in the stem and early symptoms of Bleeding Canker of Horse Chestnut observed. The ground level has been raised at the base.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 144	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	5	5	27	0	A dead standing stem. Acceptable to retain at present due to its position in relation to targets.	DEAD	DEAD	<10	LOW	Monitor annually.	MOD	B	1
T 145	Early-mature Common Ash *Fraxinus excelsior*	20	14	35	7	Single stemmed and vertical with a balanced crown. A drawn up specimen. Occasional pruning wounds due to crown lifting (generally occluding well). Minor deadwood and minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 146	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	13	3	26	6	Single stemmed and vertical. A cavity with decay from ground level to 2m noted. Limited long term future.	FAIR	POOR	<10	MOD	Remove.	LOW	R	n/a
T 147	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	13	2	27	6	Single stemmed and vertical with a balanced crown. A cavity in the stem at 1m with worsening decay noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 148	Early-mature Common Ash *Fraxinus excelsior*	19	8	34	6	Twin stemmed at 2m, vertical with a slightly unbalanced crown. Minor deadwood and tear wounds noted. Minor Ash Dieback observed.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 149	Early-mature Common Ash *Fraxinus excelsior*	21	8	36	9	Single stemmed with a slight lean and a balanced crown. The crown overhangs the road. Occasional pruning wounds (occluding slowly). Previously topped with suspected decay forming at the topping points. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 150	Early-mature Elm *Ulmus sp.*	17	3	36	8	Single stemmed and vertical with an unbalanced crown. The crown overhangs the boundary. Deadwood noted (minor).	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 151	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	8	2	13	3	Twin stemmed at 1m with vertical stems and a slightly unbalanced crown. Cavities in the stem with minor decay forming at 0.5m.	FAIR	FAIR	10-20	MOD	Monitor annually.	MOD	B	1
T 152	Early-mature Common Ash *Fraxinus excelsior*	17	8	37	8	Twin stemmed at 2.5m with vertical stems. The crown overhangs the boundary. Minor deadwood and minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 153	Early-mature Elm *Ulmus sp.*	14	2	25	5	Single stemmed with a slight lean with a slightly unbalanced crown. Deadwood noted (minor).	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2
T 154	Early-mature Sycamore *Acer pseudoplatanus*	17	4	27	6	Single stemmed with a slight lean with an unbalanced crown. The crown overhangs the sports field. Multiple bark wounds are present on the main stem.	GOOD	FAIR	10-20	MOD	Monitor biennially.	LOW	B	2
T 155	Early-mature Common Ash *Fraxinus excelsior*	18	10	35	6	Single stemmed with a slight lean and an unbalanced crown. Minor deadwood and minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 156	Semi-mature Elm *Ulmus sp.*	8	1	23	3	Twin stemmed at 2m with vertical stems and a slightly unbalanced crown. The crown overhangs the boundary. Deadwood noted (minor).	GOOD	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 157	Mature Common Ash *Fraxinus excelsior*	18	3	84	11	Multiple stemmed at 1.5m with vertical stems. The crown overhangs the boundary. Decay forming on a tear wound at 5m to the northern limb. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 158	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	9	2	33	9	Single stemmed with a slight lean and an unbalanced crown; a suppressed specimen. The crown overhangs the sports field. Occasional pruning wounds, tear wounds with the onset of decay forming and over extended branches noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 159	Semi-mature Common Beech *Fagus sylvatica*	7	2	19	5	Twin stemmed at 1m with a slight stem lea; a suppressed specimen. Minor decay forming at 1m. In an acceptable condition at this time.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 160	Early-mature Sycamore *Acer pseudoplatanus*	18	3	43	9	Single stemmed and vertical with a balanced crown. The crown overhangs the sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 161	Early-mature Common Hawthorn *Crataegus monogyna*	8	2	15	4	Twin stemmed at ground level with vertical stems. The crown overhangs the boundary. Bark wounds and minor deadwood noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 162	Semi-mature Sycamore *Acer pseudoplatanus*	12	2	17	4	Single stemmed with slight lean and a slightly unbalanced crown. The crown overhangs the sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 163	Semi-mature Sycamore *Acer pseudoplatanus*	12	2	17	4	Single stemmed with an unbalanced crown. The crown overhangs the sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 164	Early-mature Sycamore *Acer pseudoplatanus*	15	2	27	7	Single stemmed with a slight lean with a slightly unbalanced crown. The crown overhangs the boundary. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 165	Early-mature Sycamore *Acer pseudoplatanus*	19	7	44	9	Single stemmed and vertical with an unbalanced crown. The crown overhangs the boundary. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 166	Semi-mature Sycamore *Acer pseudoplatanus*	12	3	18	5	Single stemmed and leaning with an unbalanced crown; a suppressed specimen. The crown overhangs the sports field. Minor ivy on the stem.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 167	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	16	1	37	7	Single stemmed and vertical with an unbalanced crown. The crown overhangs the boundary. Tear wounds with decay noted.	FAIR	FAIR	10-20	HIGH	Monitor the progress of the decay forming at the tear wounds annually.	MOD	B	1
T 168	Semi-mature Sycamore *Acer pseudoplatanus*	9	3	17	5	Single stemmed and leaning with an unbalanced crown; a suppressed specimen. The crown overhangs the boundary. Deadwood noted (minor).	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2
T 169	Mature Common Lime *Tilia europaea*	21	4	73	12	Single stemmed and vertical with a balanced crown. The crown overhangs the boundary and the sports field. Occasional pruning wounds and minor deadwood noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 170	Semi-mature Sycamore *Acer pseudoplatanus*	8	2	23	4	Single stemmed with a slight lean and an unbalanced crown; a suppressed specimen. The crown overhangs the sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 171	Early-mature Sycamore *Acer pseudoplatanus*	17	1	38	7	Single stemmed with a slight lean with an unbalanced crown. The crown overhangs the boundary. Ivy on the stem. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 172	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	12	1	26	5	Single stemmed with a slight lean and an unbalanced crown; a suppressed specimen. The crown overhangs the boundary. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 173	Over-mature Sycamore *Acer pseudoplatanus*	16	1	42	7	Single stemmed with a slight lean and a slightly unbalanced crown; a suppressed specimen. The crown overhangs the boundary. Dense vegetation at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation then re-inspect.	HIGH	B	1
T 174	Mature Common Ash *Fraxinus excelsior*	22	6	91	13	Twin stemmed at 2m with vertical stems. The crown overhangs the boundary and the sports field. Dense vegetation at the base prevented a detailed inspection. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	HIGH	B	2
T 175	Semi-mature Sycamore *Acer pseudoplatanus*	7	1	16	4	Single stemmed with a slight lean and an unbalanced crown; a suppressed specimen. The crown overhangs the sports field. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 176	Semi-mature Sycamore *Acer pseudoplatanus*	7	1	13	3	Single stemmed and vertical with a slightly unbalanced crown; a suppressed specimen. The crown overhangs the sports field. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 177	Semi-mature Sycamore *Acer pseudoplatanus*	6	1	14	3	Single stemmed with a slight lean and an unbalanced crown. The crown overhangs the sports field. Very minor decay forming at 0.75m.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 178	Early-mature Common Lime *Tilia europaea*	15	4	27	7	Single stemmed and vertical with an unbalanced crown. The crown overhangs the boundary. Epicormic growth in the crown and moderate deadwood noted.	FAIR	FAIR	10-20	HIGH	Remove the deadwood.	LOW	B	2
T 179	Early-mature Common Lime *Tilia europaea*	17	3	37	7	Single stemmed with a slight lean with an unbalanced crown. The crown overhangs the boundary and sports field. Occasional pruning wounds due to crown lifting (occluding slowly). Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 180	Mature Sycamore *Acer pseudoplatanus*	19	4	82	13	Single stemmed and vertical with a balanced crown. The crown overhangs the boundary and sports field. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 181	Mature Common Ash *Fraxinus excelsior*	21	4	94	14	Twin stemmed at 3m with vertical stems. The crown overhangs the boundary and sports field. Tear wound at 6m with the onset of decay observed. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 182	Semi-mature Mountain Ash *Sorbus aucuparia*	6	1	13	3	Single stemmed with a slight lean and a slightly unbalanced crown; a suppressed specimen. No major visible defects.	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 183	Semi-mature Common Ash *Fraxinus excelsior*	8	3	23	7	Single stemmed with a significant lean and an unbalanced crown due to suppression. The crown overhangs the sports field. Decay forming at 1m. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 184	Early-mature Common Lime *Tilia europaea*	18	7	48	9	Single stemmed and leaning with an unbalanced crown. The crown overhangs the sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 185	Early-mature Sycamore *Acer pseudoplatanus*	16	4	46	9	Single stemmed and vertical with a balanced crown. The crown overhangs the boundary. Occasional pruning wounds and monitor deadwood noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 186	Early-mature Norway Maple *Acer platanoides*	15	3	41	8	Single stemmed with a slight lean and a slightly unbalanced crown. The crown overhangs the sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 187	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	7	1	15	5	Single stemmed and vertical with a balanced crown; a suppressed specimen. The crown overhangs the boundary. Deadwood noted (minor).	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 188	Mature Common Ash *Fraxinus excelsior*	21	2	94	13	Single stemmed with a slight lean and a balanced crown. The crown overhangs the sports field. Decay forming at 2m. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	LOW	B	2
T 189	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	13	3	32	7	Single stemmed and vertical with a slightly unbalanced crown; a suppressed specimen. The crown overhangs the sports field. Occasional pruning wounds and minor deadwood noted.	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 190	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	9	1	23	4	Single stemmed and vertical with an unbalanced crown; a suppressed specimen. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 191	Early-mature Common Lime *Tilia europaea*	21	6	30	11	Multiple stemmed at ground level with a significant included union. leaning with an unbalanced crown which is biased toward the sports field. Decay forming at the base. This tree in now very exposed due to the recent failure of the adjacent tree.	FAIR	FAIR	<10	HIGH	Pollard at 4m.	MOD	B	2
T 192	This tree has now been removed.													

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 193	This tree has now been removed.													
T 194	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	18	1	73	9	Twin stemmed at 5.5m with vertical stems. The crown overhangs the sports field. Early symptoms of Bleeding Canker of Horse Chestnut.	FAIR	FAIR	10-20	HIGH	Monitor the progress of the Bleeding Canker of Horse Chestnut annually.	LOW	B	1
T 195	Early-mature Common Lime *Tilia europaea*	16	0.5	59	12	Twin stemmed at ground level with vertical stems. The crown overhangs the sports field. Occasional pruning wounds. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 196	Mature Sycamore *Acer pseudoplatanus*	18	2	79	11	Twin stemmed at 4m with a slight lean and a balanced crown. The crown overhangs the sports field. Occasional pruning wounds and minor deadwood noted.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 197	Early-mature Common Ash *Fraxinus excelsior*	18	2	53	13	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the sports field. Occasional pruning wounds, minor deadwood and minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 198	Mature Sycamore *Acer pseudoplatanus*	20	2	119	13	Twin stemmed at 2m with vertical stems. The crown overhangs the sports field. Dense vegetation at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation then re-inspect.	MOD	B	1
T 199	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	11	1	23	7	Twin stemmed at 0.5m with an unbalanced crown; a suppressed specimen. Occasional pruning wounds due to crown lifting, crossing branches and minor deadwood noted.	FAIR	FAIR	10-20	MOD	No action required.	N/A	A	2
T 200	Early-mature Sycamore *Acer pseudoplatanus*	13	2	27	6	Single stemmed with a slight lean and an unbalanced crown. The crown overhangs the boundary. Occasional pruning wounds and minor deadwood noted.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 201	Early-mature Common Lime *Tilia europaea*	20	15	35	6	Single stemmed and vertical with an unbalanced crown. A drawn up specimen. Close to the boundary. Deadwood noted (minor).	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 202	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	19	2	52	8	Single stemmed and vertical with an unbalanced crown. Occasional pruning wounds and early symptoms of Bleeding Canker of Horse Chestnut observed.	FAIR	FAIR	20-40	MOD	Monitor the progress of the Bleeding Canker of Horse Chestnut annually.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 203	Early-mature Common Lime *Tilia europaea*	22	3	49	8	Single stemmed with a slight lean and a balanced crown. The crown overhangs the sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 204	Mature Common Ash *Fraxinus excelsior*	21	2	89	11	Single stemmed and vertical with a slightly unbalanced crown. Occasional pruning wounds. Dense vegetation at the base prevented a detailed inspection. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 205	Semi-mature Common Ash *Fraxinus excelsior*	11	1	15	4	Single stemmed with a slight lean and an unbalanced crown. The crown overhangs the sports field. Minor deadwood and minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 206	Semi-mature Common Ash *Fraxinus excelsior*	9	2	21	6	Single stemmed with a slight lean and a slightly unbalanced crown. The crown overhangs the sports field. Occasional pruning wounds and minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 207	Semi-mature Common Horse Chestnut *Aesculus hippocastanum*	7	1	21	6	Twin stemmed at ground level with a slight lean and an unbalanced crown; a suppressed specimen. Occasional pruning wounds and minor deadwood noted.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 208	Early-mature Common Lime *Tilia europaea*	16	7	26	5	Single stemmed and vertical with an unbalanced crown. Epicormic growth on the stem and occasional pruning wounds noted.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 209	Early-mature Common Lime *Tilia europaea*	21	14	32	7	Single stemmed and vertical with a balanced crown. A drawn up specimen. Occasional pruning wounds noted. Ivy on stem.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	LOW	B	2
T 210	Early-mature Sycamore *Acer pseudoplatanus*	18	2	51	9	Single stemmed and vertical with an unbalanced crown. The crown overhangs the boundary. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1
T 211	Mature Common Ash *Fraxinus excelsior*	20	9	77	12	Single stemmed and vertical with a balanced crown. The crown overhangs the sports field. Dense Ivy and understorey vegetation prevented a detailed inspection. Occasional pruning wounds and minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Remove the vegetation and Ivy then re-inspect. Monitor biennially.	MOD	B	2
T 212	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	11	1	32	8	Single stemmed and vertical with an unbalanced crown; a suppressed specimen. The crown overhangs the boundary. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 213	Mature Sycamore *Acer pseudoplatanus*	19	4	76	8	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the boundary. Occasional pruning wounds. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	HIGH	B	1
T 214	Early-mature Sycamore *Acer pseudoplatanus*	21	3	47	8	Single stemmed and vertical with an unbalanced crown. The crown overhangs the boundary. Occasional pruning wounds. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	HIGH	B	1
T 215	Early-mature Common Ash *Fraxinus excelsior*	21	14	46	7	Twin stemmed at 4m and vertical. A drawn up specimen. Dense Ivy prevented a detailed inspection. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Remove the Ivy then re-inspect. Monitor biennially.	MOD	B	2
T 216	Semi-mature Sycamore *Acer pseudoplatanus*	14	4	22	6	Single stemmed with a slight lean and an unbalanced crown; a suppressed specimen. The crown overhangs the boundary. Ivy on the stem.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	LOW	B	2
T 217	Early-mature Sycamore *Acer pseudoplatanus*	21	5	68	11	Twin stemmed at 3.5m with vertical stems. Decay forming at a tear wound from 3.5m to 5m.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 218	Early-mature Common Lime *Tilia europaea*	12	0	37	11	Single stemmed with a significant lean and an unbalanced crown; a suppressed specimen. The crown overhangs the sports field. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	1
T 219	Early-mature Sycamore *Acer pseudoplatanus*	19	3	32	8	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 220	Early-mature Sycamore *Acer pseudoplatanus*	19	15	26	5	Single stemmed and vertical with a balanced crown. A drawn up specimen. Close to the boundary. Decay forming at the base.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 221	Early-mature Sycamore *Acer pseudoplatanus*	20	10	28	7	Single stemmed and vertical with a sparse crown. A drawn up specimen. The crown overhangs the boundary. Deadwood noted (minor).	FAIR	FAIR	10-20	HIGH	Monitor the sparse crown annually.	MOD	B	1
T 222	Semi-mature Common Holly *Ilex aquifolium*	9	0	21	4	Twin stemmed at ground level with vertical stems. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 223	Early-mature Common Ash *Fraxinus excelsior*	5	3	39	2	Single stemmed. Previously pollarded to 4m with young regrowth. Minor Ash Dieback noted.	FAIR	FAIR	10-20	MOD	Monitor biennially.	LOW	B	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 224	Early-mature Sycamore *Acer pseudoplatanus*	17	3	37	7	Twin stemmed at 1.5m. The crown is slightly unbalanced and overhangs the boundary. Occasional pruning wounds, minor deadwood and epicormic growth noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 225	Early-mature Common Lime *Tilia europaea*	19	3	38	8	Single stemmed and vertical with a balanced crown. The crown overhangs the boundary. Decay to stem at 1.5m to 3m.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 226	This tree has now been removed.													
T 227	Semi-mature Sycamore *Acer pseudoplatanus*	12	8	17	3	Single stemmed with a slight lean and a slightly unbalanced crown. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 228	Mature Common Oak *Quercus robur*	21	2	83	12	Single stemmed and vertical with a balanced crown. The crown overhangs the sports field. Major deadwood noted; several dead branches in the lower crown are over the sports pitch.	GOOD	FAIR	20-40	HIGH	Remove the dead branches.	MOD	B	2
T 229	Semi-mature Sycamore *Acer pseudoplatanus*	8	2	10	4	Single stemmed and vertical with a balanced crown. No major visible defects.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 230	Semi-mature Sycamore *Acer pseudoplatanus*	13	2	21	5	Twin stemmed at 2m; vertical with a slightly unbalanced crown. The crown overhangs the sports field. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 231	Semi-mature Common Ash *Fraxinus excelsior*	6	1	12	3	Single stemmed and vertical with a slightly unbalanced crown. Minor Ash Dieback noted.	FAIR	GOOD	10-20	MOD	Monitor biennially.	LOW	B	2
T 232	Semi-mature Common Holly *Ilex aquifolium*	8	0	18	5	Twin stemmed at 0.5m with a slight lean and a slightly unbalanced crown. Bark wounding with decay from ground level to 1m.	FAIR	FAIR	10-20	MOD	Monitor annually.	LOW	B	1
T 233	This tree has now been removed.													
T 234	Early-mature Common Holly *Ilex aquifolium*	8	1	13	5	Twin stemmed at ground level with an unbalanced crown; a suppressed specimen. Minor basal bark wounds observed.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 235	Over-mature Sycamore *Acer pseudoplatanus*	17	4	69	9	Single stemmed and vertical with a balanced crown. Occasional pruning wounds due to crown lifting (occluding slowly). Decay forming at the base and on an old pruning wound at 1.5m.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 236	Early-mature Common Oak *Quercus robur*	18	5	46	8	Single stemmed and vertical with a balanced crown. The crown overhangs the boundary. Occasional pruning wounds due to crown lifting (occluding slowly). Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 237	Early-mature Sycamore *Acer pseudoplatanus*	15	5	35	7	Twin stemmed at 1.5m with vertical stems. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 238	Early-mature Common Lime *Tilia europaea*	19	3	27	6	Single stemmed and vertical with a balanced crown. A drawn up specimen. The crown overhangs the boundary. Occasional pruning wounds due to crown lifting, generally occluding well.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 239	Early-mature Sycamore *Acer pseudoplatanus*	17	4	25	5	Single stemmed and vertical with an unbalanced crown. The crown overhangs the boundary. Occasional pruning wounds due to crown lifting. Dense vegetation at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation then re-inspect.	MOD	B	1
T 240	Early-mature Common Holly *Ilex aquifolium*	13	0	27	5	Single stemmed and vertical with a slightly unbalanced crown. Occasional pruning wounds. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 241	Early-mature Common Holly *Ilex aquifolium*	8	0	23	4	Twin stemmed at ground level with a slight lean and an unbalanced crown; a suppressed specimen. Occasional pruning wounds. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 242	Early-mature Common Ash *Fraxinus excelsior*	17	2	37	8	Single stemmed with a significant lean with an unbalanced crown. The crown overhangs the sports field. Occasional pruning wounds, minor deadwood and minor Ash Dieback noted. The root plate appears to have risen since the tree survey undertaken in 2023.	FAIR	POOR	<10	HIGH	Remove.	MOD	R	N/A
T 243	Early-mature Sycamore *Acer pseudoplatanus*	18	3	43	7	Single stemmed and vertical with an unbalanced crown. The crown overhangs the sports field. Occasional pruning wounds and moderate deadwood in the lower crown noted.	GOOD	FAIR	20-40	HIGH	Remove the larger deadwood.	MOD	B	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 244	Early-mature Sycamore *Acer pseudoplatanus*	19	8	49	10	Twin stemmed at 4m with vertical stems. Occasional pruning wounds and minor deadwood noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 245	Semi-mature Sycamore *Acer pseudoplatanus*	8	1	16	3	Single stemmed and vertical with an unbalanced crown; a suppressed specimen. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 246	Early-mature Elm *Ulmus sp.*	21	7	46	8	Formerly twin stemmed; now single stemmed as the co-dominant stem has snapped out.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 247	Early-mature Common Lime *Tilia europaea*	18	6	27	7	Single stemmed and vertical with a balanced crown. The crown overhangs the boundary. Dense vegetation at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation then re-inspect.	MOD	B	1
T 248	Early-mature Sycamore *Acer pseudoplatanus*	19	2.5	51	9	Single stemmed and vertical with an unbalanced crown. The crown overhangs the sports field. Occasional pruning wounds and minor deadwood noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 249	This tree has now been removed.													
T 250	Semi-mature Common Holly *Ilex aquifolium*	8	0	12	4	Multiple stemmed at ground level with vertical stems. No major visible defects.	GOOD	GOOD	20-40	MOD	No action required.	N/A	A	2
T 251	Early-mature Sycamore *Acer pseudoplatanus*	17	7	27	5	Single stemmed and vertical with an unbalanced crown. The crown overhangs the footpath. Major deadwood noted over the footpath.	FAIR	FAIR	20-40	HIGH	Remove the deadwood.	MOD	B	2
T 252	Early-mature Common Lime *Tilia europaea*	8	2	24	5	Twin stemmed at 1m with a slight lean and a balanced crown; a suppressed specimen. Previously topped. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 253	Early-mature Sycamore *Acer pseudoplatanus*	18	8	37	7	Single stemmed and vertical with a balanced crown. The crown overhangs the boundary. Occasional pruning wounds due to crown lifting (occluding slowly) and minor deadwood noted.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 254	This tree has now been removed.													

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 255	Early-mature Elm *Ulmus sp.*	20	10	33	9	Single stemmed and vertical with a balanced crown. A drawn up specimen. The crown overhangs the footpath. Large deadwood in the lower crown over the footpath.	FAIR	FAIR	10-20	HIGH	Remove the deadwood.	MOD	B	2
T 256	Semi-mature Field Maple *Acer campestre*	8	2	17	6	Twin stemmed at 1.5m and vertical with a slightly unbalanced crown; a suppressed specimen. The crown overhangs the footpath. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 257	Early-mature Common Oak *Quercus robur*	16	2	37	8	Single stemmed and vertical with an unbalanced crown. The crown overhangs the sports field. Epicormic growth on the stem and in the crown resulted in a limited inspection. Deadwood noted in the crown.	FAIR	FAIR	20-40	HIGH	Remove the larger deadwood and the epicormic growth from the stem and the crown.	MOD	B	2
T 258	Early-mature Common Lime *Tilia europaea*	21	4	43	8	Single stemmed with a slight lean and a slightly unbalanced crown. The crown overhangs the sports field. Dense Ivy at the base prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1
T 259	Early-mature Common Beech *Fagus sylvatica*	17	2	26	6	Single stemmed and vertical with a balanced crown. The crown overhangs the sports field. No major visible defects.	GOOD	GOOD	20-40	HIGH	No action required.	N/A	A	2
T 260	This tree has now been removed.													
T 261	Semi-mature Field Maple *Acer campestre*	14	3	17	4	Single stemmed and vertical with a slightly unbalanced crown. A drawn up specimen. The crown overhangs the sports field. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1
T 262	Early-mature Sycamore *Acer pseudoplatanus*	16	5	26	6	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the footpath. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1
T 263	Early-mature Common Lime *Tilia europaea*	19	3	47	7	Single stemmed and vertical with a balanced crown. The crown overhangs the building and footpath. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	HIGH	B	1
T 264	Early-mature Sycamore *Acer pseudoplatanus*	17	2	63	8	A dead tree. The crown overhangs the sports field.	DEAD	DEAD	<10	HIGH	Remove.	MOD	R	N/A
T 265	Early-mature Common Hornbeam *Carpinus betulus*	13	1	23	8	Multiple stemmed at ground level with an unbalanced crown; a suppressed specimen. The crown overhangs the sports field. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 266	Mature Sycamore *Acer pseudoplatanus*	19	3	87	12	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the building and the sports field. Cavities forming in old pruning wounds; one large pruning wound on the main stem at 6m has decay.	GOOD	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 267	Early-mature Sycamore *Acer pseudoplatanus*	17	3	46	10	Twin stemmed at 3m and vertical with an unbalanced crown. The crown overhangs the sports court. Occasional pruning wounds due to crown lifting (occluding slowly). Minor basal wounds noted. No major visible defects.	GOOD	GOOD	20-40	HIGH	No action required.	N/A	A	2
T 268	Mature Sycamore *Acer pseudoplatanus*	21	6	83	11	Single stemmed and vertical with a balanced crown. The crown overhangs the building and the footpath. Multiple pruning wounds due to crown lifting, tear wounds and cavities forming at old pruning wounds noted.	FAIR	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 269	Early-mature Common Holly *Ilex aquifolium*	9	3	26	4	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the footpath. Multiple pruning wounds due to crown lifting (generally occluding well). No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 270	Early-mature Common Holly *Ilex aquifolium*	8	4	24	4	Single stemmed and vertical with a balanced crown. The crown overhangs the building. Occasional pruning wounds due to crown lifting (generally occluding well). No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 271	Early-mature Common Holly *Ilex aquifolium*	10	4	26	6	Twin stemmed at ground level with vertical stems. The crown overhangs the footpath. Occasional pruning wounds due to crown lifting (generally occluding well). No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 272	Early-mature Common Holly *Ilex aquifolium*	11	4	24	4	Single stemmed and vertical with a balanced crown. The crown overhangs the footpath. Occasional pruning wounds due to crown lifting (generally occluding well). No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 273	Semi-mature Common Holly *Ilex aquifolium*	9	4	13	4	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the footpath. Occasional pruning wounds due to crown lifting (generally occluding well). No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 274	Early-mature Common Holly *Ilex aquifolium*	8	3	24	4	Multiple stemmed at ground level with vertical stems. The crown overhangs the footpath. A sparse upper crown suggests the tree may be in decline.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 275	Semi-mature Common Holly *Ilex aquifolium*	7	2	16	4	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the footpath. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 276	Early-mature Common Holly *Ilex aquifolium*	10	2	25	4	Twin stemmed at ground level with vertical stems. The crown overhangs the footpath. Occasional pruning wounds due to crown lifting (generally occluding well). No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 277	Early-mature Common Holly *Ilex aquifolium*	11	3	15	4	Twin stemmed at ground level with vertical stems. The crown overhangs the footpath. Occasional pruning wounds due to crown lifting (generally occluding well). No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 278	Early-mature Common Holly *Ilex aquifolium*	9	3	25	4	Multiple stemmed at ground level with vertical stems. The crown overhangs the footpath. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1
T 279	Early-mature Common Holly *Ilex aquifolium*	11	3	27	4	Single stemmed and vertical with a balanced crown. The crown overhangs the footpath. Occasional pruning wounds due to crown lifting (occluding slowly).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 280	Semi-mature Common Holly *Ilex aquifolium*	6	2	12	3	Twin stemmed at 0.3m with vertical stems. The crown overhangs the footpath. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 281	Semi-mature Common Holly *Ilex aquifolium*	5	2	13	3	Twin stemmed at ground level with vertical stems. The crown overhangs the footpath. No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 282	Semi-mature Common Holly *Ilex aquifolium*	5	2	15	3	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the footpath. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 283	Early-mature European Larch *Larix decidua*	18	4	37	11	Single stemmed and vertical with a balanced crown. The crown overhangs the footpath and the building. Occasional pruning wounds due to crown lifting (occluding slowly) and minor deadwood noted. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 284	This tree has now been removed.													

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 285	Early-mature Common Beech *Fagus sylvatica*	18	4	37	9	Single stemmed and vertical with a balanced crown. The crown overhangs the boundary. Dense vegetation prevented a detailed inspection.	FAIR	FAIR	10-20	HIGH	Remove the vegetation then re-inspect.	LOW	B	2
T 286	Early-mature Common Beech *Fagus sylvatica*	19	2	42	11	Single stemmed and vertical with a balanced crown. The crown overhangs the boundary. Occasional pruning wounds due to crown lifting (generally occluding well). Minor deadwood noted. Not fully inspected due to vegetation.	FAIR	FAIR	20-40	HIGH	Remove the vegetation then re-inspect.	LOW	B	2
T 287	Early-mature Sycamore *Acer pseudoplatanus*	18	5	73	9	Single stemmed and vertical with a balanced crown. The crown overhangs the boundary. Basal bark wounds noted. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1
T 288	Mature Common Ash *Fraxinus excelsior*	21	9	72	10	Twin stemmed at 3m with vertical stems. The crown overhangs the building and the footpath. Occasional pruning wounds due to crown lifting. Moderate deadwood noted and minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Remove the deadwood. Monitor annually.	MOD	B	1
T 289	Early-mature Common Beech *Fagus sylvatica*	17	3	65	10	Single stemmed and vertical with a balanced crown. The crown overhangs the boundary and the building. Occasional pruning wounds due to crown lifting (occluding slowly). Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 290	Mature Sycamore *Acer pseudoplatanus*	18	3	75	9	Single stemmed and vertical with a balanced crown. The crown overhangs the boundary. Occasional pruning wounds due to crown lifting (generally occluding well).	GOOD	GOOD	20-40	HIGH	No action required.	N/A	A	2
T 291	Mature Sycamore *Acer pseudoplatanus*	21	5	89	12	Twin stemmed at 6m with vertical stems. The crown overhangs the boundary and building. Multiple pruning wounds due to crown lifting (occluding slowly). Cavities forming at old pruning wounds with decayed wood present.	FAIR	FAIR	20-40	HIGH	Monitor biennially.	LOW	B	2
T 292	Mature Common Lime *Tilia europaea*	21	3	75	8	Single stemmed and vertical with a balanced crown. The crown overhangs the footpath and the building. Occasional pruning wounds due to crown lifting, minor deadwood and epicormic growth at the base noted.	GOOD	GOOD	20-40	HIGH	No action required.	N/A	A	2
G 293	Semi-mature Common Holly *Ilex aquifolium*	8	1	12	3	Two trees of a reasonable form. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 294	Semi-mature Common Holly *Ilex aquifolium*	8	1	15	3	Single stemmed and vertical with a balanced crown. No major visible defects.	GOOD	GOOD	20-40	HIGH	No action required.	N/A	A	2
T 295	Semi-mature Common Holly *Ilex aquifolium*	8	1	15	3	Single stemmed and vertical with a balanced crown. No major visible defects.	GOOD	GOOD	20-40	HIGH	No action required.	N/A	A	2
T 296	This tree has now been removed.													
T 297	This tree has now been removed.													
T 298	Mature Common Lime *Tilia europaea*	22	6	71	11	Twin stemmed at 4m with a kinked lower stem. The crown overhangs the driveway and the footpath. Occasional pruning wounds due to crown lifting (generally occluding well). Crown die-back and moderate deadwood noted.	FAIR	FAIR	10-20	HIGH	Crown clean to remove the deadwood.	MOD	B	2
T 299	This tree has now been removed.													
T 300	Early-mature Common Holly *Ilex aquifolium*	11	1	27	5	Twin stemmed at ground level with a slight lean and a slightly unbalanced crown. The crown overhangs the road. Occasional pruning wounds due to crown lifting (generally occluding well). No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 301	Early-mature Common Holly *Ilex aquifolium*	12	1	26	5	Multiple stemmed at ground level with a slightly unbalanced crown. Occasional pruning wounds due to crown lifting (occluding slowly). No major visible defects.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 302	This tree has now been removed.													
T 303	This tree has now been removed.													

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 304	Early-mature Common Holly *Ilex aquifolium*	8	2	24	4	Twin stemmed at ground level with an unbalanced crown; a suppressed specimen. A stem wound noted.	FAIR	FAIR	20-40	HIGH	Monitor biennially.	LOW	B	2
T 305	Early-mature Sycamore *Acer pseudoplatanus*	16	3	27	8	Multiple stemmed at ground level with vertical stems. The crown overhangs the footpath and road. A stem wound noted.	GOOD	FAIR	20-40	HIGH	Monitor biennially.	LOW	B	2
T 306	Mature Common Holly *Ilex aquifolium*	15	4	36	8	Twin stemmed at ground level with vertical stems. The crown overhangs the road. Occasional pruning wounds due to crown lifting (generally occluding well). Appears to be in an acceptable condition at this time.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 307	Early-mature Common Holly *Ilex aquifolium*	11	3	26	5	Single stemmed with a slight lean and a balanced crown. The crown overhangs the footpath. Occasional pruning wounds due to crown lifting observed. Bark wounding with onset of decay from 2m to 3m.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 308	Early-mature Common Holly *Ilex aquifolium*	11	3	26	5	Twin stemmed at ground level with vertical stems. Multiple pruning wounds due to crown lifting (generally occluding well). Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 309	Early-mature Common Holly *Ilex aquifolium*	8	4	12	4	Multiple stemmed at ground level with a slight lean and a slightly unbalanced crown; a suppressed specimen. Occasional pruning wounds due to crown lifting (generally occluding well).	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 310	Mature Common Lime *Tilia europaea*	18	7	75	11	Single stemmed and vertical with a balanced crown. The crown overhangs the footpath. Occasional pruning wounds due to crown lifting (generally occluding well). Minor deadwood and epicormic growth in the crown noted. Appears to be in an acceptable condition at this time.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 311	Semi-mature Common Holly *Ilex aquifolium*	6	2	14	4	Multiple stemmed at ground level and vertical with a slightly unbalanced and very sparse crown. A suppressed specimen.	POOR	FAIR	<10	MOD	Remove.	MOD	R	N/A
T 312	Mature Common Lime *Tilia europaea*	21	8	73	10	Single stemmed and vertical with a balanced crown. The crown overhangs the road. Occasional pruning wounds due to crown lifting (generally occluding well). Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	Remove the larger deadwood from over the targets.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 313 A	This tree has now been removed.													
T 313 B	Early-mature Common Holly *Ilex aquifolium*	13	2	25	4	A dead tree.	DEAD	DEAD	<10	MOD	Remove.	MOD	R	N/A
T 313 C	Early-mature Common Holly *Ilex aquifolium*	11	2	30	3	Single-stemmed and slightly leaning. The crown is slightly unbalanced and has significant die-back.	POOR	FAIR	<10	MOD	Remove to ground level.	MOD	R	N/A
T 314	Mature Sycamore *Acer pseudoplatanus*	18	9	74	11	Single stemmed with a slight lean and a balanced crown. The crown overhangs the road. Multiple pruning wounds due to crown lifting (occluding slowly). Minor basal damage noted.	GOOD	FAIR	20-40	HIGH	Monitor annually.	MOD	B	1
T 315	This tree has now been removed.													
T 316	This tree has now been removed.													
T 317	This tree has now been removed.													
T 318	This tree has now been removed.													
T 319	Early-mature Common Holly *Ilex aquifolium*	12	0	19	4	Twin stemmed at 0.5m with a tight union. Appears to be in an acceptable condition at this time.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 320	Mature Common Holly *Ilex aquifolium*	13	0.5	27	6	Multiple stemmed at ground level with a slightly unbalanced crown. Multiple pruning wounds due to crown lifting (occluding slowly). Basal bark wounds and min deadwood noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 321	Mature Common Holly *Ilex aquifolium*	12	1	32	6	Multiple stemmed at ground level with a slightly unbalanced crown. The crown overhangs the road. Multiple pruning wounds due to crown lifting (generally occluding well). Basal bark wounds and minor deadwood noted.	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 322	Mature Weeping Ash *Fraxinus pendula*	16	3	78	11	Single stemmed and vertical with a balanced crown. The crown overhangs the sports field. Decay forming at a large, poorly executed pruning wound at 2.5m. Significant Ash Dieback throughout.	POOR	FAIR	<10	HIGH	Remove to ground level.	MOD	R	N/A
T 323	This tree has now been removed.													
T 324	Mature Silver Lime *Tilia tormentosa*	19	2	109	14	Single stemmed and vertical with a balanced crown. The crown overhangs the adjacent building and footpath. Multiple pruning wounds due to crown lifting (generally occluding well). Min deadwood and several over-extended branches noted. Appears to be in an acceptable condition at this time.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 325	Early-mature Common Holly *Ilex aquifolium*	12	1	31	5	Twin stemmed at ground level with an unbalanced crown; a suppressed specimen. The crown overhangs the sports field. a tight union with significant included bark at 2m. Occasional pruning wounds due to crown lifting (occluding slowly). Moderate deadwood noted.	FAIR	FAIR	10-20	HIGH	Crown clean to remove the deadwood. Monitor annually.	MOD	B	1
T 326	Early-mature Common Holly *Ilex aquifolium*	17	1	39	7	Single stemmed with a slight lean and a slightly unbalanced crown. A drawn up specimen. The crown overhangs the sports field. Multiple pruning wounds due to crown lifting (occluding slowly) and minor deadwood noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 327	Early-mature Common Holly *Ilex aquifolium*	17	1	38	7	Twin stemmed at ground level with a tight union with included bark and decay forming at 0.5m. Leaning slightly with a slightly unbalanced crown. The crown overhangs the footpath and sports field. Occasional pruning wounds due to crown lifting (occluding slowly).	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 328	Semi-mature Flowering Cherry *Prunus sp.*	8	2	25	4	Twin stemmed at 1.5m with a tight union. The crown overhangs the footpath. Occasional pruning wounds due to crown lifting (occluding slowly).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 329	Semi-mature Common Holly *Ilex aquifolium*	12	2	24	4	Single stemmed and vertical with a balanced crown. The crown overhangs the building and footpath. Occasional pruning wounds due to crown lifting (generally occluding well). Ivy on the stem.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 330	Early-mature Common Holly *Ilex aquifolium*	12	3	27	4	Single stemmed with a slight lean and a slightly unbalanced crown. The crown overhangs the footpath. Occasional pruning wounds due to crown lifting (generally occluding well).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 331	Semi-mature Common Holly *Ilex aquifolium*	9	1	10	3	Multiple stemmed at ground level with a slightly unbalanced crown. The crown overhangs the building. Occasional pruning wounds due to crown lifting, generally occluding well. Deadwood noted (minor).	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 332	Semi-mature Common Holly *Ilex aquifolium*	9	1	13	4	Multiple stemmed at ground level with vertical stems. Occasional pruning wounds due to crown lifting (generally occluding well).	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 333	Semi-mature Common Ash *Fraxinus excelsior*	16	4	31	6	Twin stemmed at 0.5m with vertical stems. The crown overhangs the building. Rubbing branches observed which are slowly causing wounds. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 334	Semi-mature Common Holly *Ilex aquifolium*	7	2	10	3	Twin stemmed at ground level with a slight lean with a slightly unbalanced crown; a suppressed specimen. The crown overhangs the building. Occasional pruning wounds due to crown lifting.	GOOD	GOOD	20-40	MOD	No action required.	N/A	A	2
T 335	Semi-mature Common Holly *Ilex aquifolium*	6	3	15	4	Single stemmed and vertical with a balanced crown. Occasional pruning wounds due to crown lifting. No major visible defects.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 336	Semi-mature Common Holly *Ilex aquifolium*	6	2	10	3	Single stemmed and vertical with a balanced crown. No major visible defects.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 337	Semi-mature Common Holly *Ilex aquifolium*	6	1	14	3	Single stemmed with a slight lean with a slightly unbalanced crown. No major visible defects.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 338	Mature Sycamore *Acer pseudoplatanus*	18	5	69	10	Single stemmed and vertical with a balanced crown. The crown overhangs the play area. Occasional pruning wounds due to crown lifting. Minor deadwood and tear wounds noted.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 339	Semi-mature Common Holly *Ilex aquifolium*	7	2.5	10	3	Single stemmed and vertical with a slightly unbalanced crown; a suppressed specimen. Occasional pruning wounds due to crown lifting (generally occluding well). No major visible defects.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 340	Early-mature Silver Birch *Betula pendula*	16	5	29	9	Twin stemmed at 2.5m with vertical stems. The crown overhangs the play area. Occasional pruning wounds due to crown lifting (occluding slowly). A cavity with the onset decay noted at 2m.	GOOD	FAIR	20-40	HIGH	Monitor the progress of the decay annually.	MOD	B	1
T 341	Semi-mature Common Holly *Ilex aquifolium*	9	2	17	4	Twin stemmed at ground level with a slight lean and an unbalanced crown; a suppressed specimen. The crown overhangs the play area. Occasional pruning wounds due to crown lifting (generally occluding well). Minor deadwood noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 342	Semi-mature Holly *Tilia europaea*	6	2	20	4	A dead tree.	DEAD	DEAD	<10	HIGH	Remove to ground level.	MOD	R	N/A
T 343	Semi-mature Common Holly *Ilex aquifolium*	6	2	12	3	Single stemmed and vertical with a slightly unbalanced crown; a suppressed specimen. The crown overhangs the play area. Occasional pruning wounds due to crown lifting (generally occluding well).	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 344	Semi-mature Common Holly *Ilex aquifolium*	9	2	27	5	Single stemmed and leaning with an unbalanced crown; a suppressed specimen. The crown overhangs the play area. Occasional pruning wounds due to crown lifting (generally occluding well).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 345	Semi-mature Common Holly *Ilex aquifolium*	9	2	26	4	Twin stemmed at 2.5m with vertical stems. The crown overhangs the play area. Occasional pruning wounds due to crown lifting (generally occluding well).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 346	Semi-mature Common Holly *Ilex aquifolium*	2	0	13	3	Single stemmed and vertical with a balanced crown. No major visible defects.	GOOD	GOOD	20-40	MOD	No action required.	N/A	A	2
T 347	Early-mature Sycamore *Acer pseudoplatanus*	15	2	18	7	Multiple stemmed at ground level with vertical stems. The crown overhangs the building and sports court.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 348	Early-mature Sycamore *Acer pseudoplatanus*	15	6	24	6	Multiple stemmed at ground level with vertical stems. The crown overhangs the building and sports court.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	1
T 349	Semi-mature Mountain Ash *Sorbus aucuparia*	11	7	15	4	Single stemmed and vertical with a balanced crown. A drawn up specimen. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 350	Semi-mature Common Ash *Fraxinus excelsior*	14	8	26	5	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the sports court. Occasional pruning wounds due to crown lifting. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 351	Early-mature Common Ash *Fraxinus excelsior*	16	5	36	9	Single stemmed and vertical with a balanced crown. The crown overhangs the sports court. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 352	Early-mature Sycamore *Acer pseudoplatanus*	13	7	33	6	Single stemmed with a slight lean and a balanced crown; a suppressed specimen. The crown, which is sparse, overhangs the sports court.	FAIR	FAIR	20-40	HIGH	Monitor the sparse crown annually.	MOD	B	1
T 353	Semi-mature Sycamore *Acer pseudoplatanus*	7	2	13	3	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the sports court.	FAIR	FAIR	20-40	MOD	No action required.	N/A	A	2
T 354	Early-mature Sycamore *Acer pseudoplatanus*	16	7	37	8	Single stemmed and vertical with an unbalanced crown. The crown overhangs the sports court.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 355	Early-mature Scots Pine *Pinus sylvestris*	16	5	27	3	Single stemmed and vertical with a balanced crown. The crown overhangs the play area. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 356	Early-mature Silver Birch *Betula pendula*	14	7	27	7	Single stemmed and leaning with an unbalanced crown; a suppressed specimen. The crown overhangs the sports court.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 357	Semi-mature Common Holly *Ilex aquifolium*	8	1	23	4	Single stemmed and vertical with a slightly unbalanced crown; a suppressed specimen. The crown overhangs the play area. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 358	Early-mature Corsican Pine *Pinus nigra var.maritima*	17	6	37	4	Single stemmed and vertical with a balanced crown. The crown overhangs the play area. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 359	Early-mature Common Holly *Ilex aquifolium*	9	2	23	3	Single stemmed with a slight lean and an unbalanced crown; a suppressed specimen. The crown overhangs the play area. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 360	Semi-mature Common Holly *Ilex aquifolium*	8	2	12	3	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the sports court.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 361	Early-mature Sycamore *Acer pseudoplatanus*	17	7	29	7	Single stemmed and vertical with a balanced crown. The crown overhangs the sports court. Basal bark wounding with the onset of decay noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 362	Semi-mature Common Holly *Ilex aquifolium*	9	2	12	4	Twin stemmed from ground level with vertical stems. The crown, which is slightly unbalanced, overhangs the play area.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 363	Early-mature Sycamore *Acer pseudoplatanus*	15	7	34	7	Single stemmed and vertical with an unbalanced crown. The crown overhangs the sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1
T 364	Semi-mature Sycamore *Acer pseudoplatanus*	8	2	13	3	Single stemmed and vertical with a balanced crown. The crown overhangs the sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the vegetation then re-inspect.	MOD	B	1
T 365	Semi-mature Common Holly *Ilex aquifolium*	8	1	14	3	Single stemmed and vertical with a balanced crown. No major visible defects.	GOOD	FAIR	20-40	MOD	No action required.	N/A	A	2
T 366	Semi-mature Sycamore *Acer pseudoplatanus*	9	3	23	4	Single stemmed with a slight lean and a slightly unbalanced crown. The crown overhangs the play area. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 367	Semi-mature Common Holly *Ilex aquifolium*	8	1	13	3	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the play area. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 368	Early-mature Flowering Cherry *Prunus sp.*	9	3	31	7	Single stemmed with a slight lean and a slightly unbalanced crown. The crown overhangs the sports court. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1
T 369	Semi-mature Sycamore *Acer pseudoplatanus*	7	2	13	3	Single stemmed and vertical with a balanced crown. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 370	Semi-mature Common Holly *Ilex aquifolium*	7	0	12	3	Multiple stemmed at ground level with vertical stems. The crown overhangs the footpath. Occasional pruning wounds due to crown lifting noted.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 371	Early-mature Common Hawthorn *Crataegus monogyna*	6	2	19	3	Twin stemmed at 0.75m with vertical stems. The crown overhangs the footpath. Dense Ivy prevented a detailed inspection.	FAIR	FAIR	20-40	HIGH	Remove the Ivy then re-inspect.	MOD	B	1
T 372	Semi-mature Common Holly *Ilex aquifolium*	7	0.5	13	3	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the footpath.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 373	Early-mature Goat Willow *Salix caprea*	14	2	21	7	Twin stemmed at ground level with vertical stems; the basal union is tight with included bark. The crown overhangs the sports field and the sports court. Occasional pruning wounds due to crown lifting noted.	FAIR	FAIR	10-20	HIGH	Monitor annually.	MOD	B	1
T 374	Mature Goat Willow *Salix caprea*	14	2	83	8	Multiple stemmed at 1m with vertical stems. The crown overhangs the footpath, the sports court and the sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 375	Semi-mature Common Ash *Fraxinus excelsior*	14	9	15	4	Twin stemmed at ground level with vertical stems. The crown overhangs the sports court. Occasional pruning wounds due to crown lifting. Minor Ash Dieback noted	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 376	Semi-mature Common Hawthorn *Crataegus monogyna*	6	3	15	4	Single stemmed and leaning with a unbalanced crown. Suppressed specimen. The crown overhangs the footpath. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 377	Early-mature Common Horse Chestnut *Aesculus hippocastanum*	15	4	32	9	Single stemmed and vertical with an unbalanced crown. The crown overhangs the footpath and the sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 378	Early-mature Common Lime *Tilia europaea*	18	4	51	11	Single stemmed and vertical with a balanced crown. The crown overhangs the sports field and the sports court. Occasional pruning wounds due to crown lifting (occluding slowly). Deadwood (minor) and bark wounds noted.	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 379	Early-mature Common Lime *Tilia europaea*	18	6	54	9	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the sports court and the sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 380	Early-mature Common Lime *Tilia europaea*	16	6	47	11	Single stemmed and vertical with an unbalanced crown; a suppressed specimen with unusual form. The crown overhangs the sports field. Occasional pruning wounds due to crown lifting. Deadwood noted (moderate).	FAIR	FAIR	20-40	HIGH	Crown clean to remove the deadwood.	LOW	B	2
T 381	Early-mature Common Ash *Fraxinus excelsior*	14	9	26	5	Single stemmed and vertical with a balanced crown. The crown overhangs the sports court. Occasional pruning wounds due to crown lifting (occluding slowly). Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 382	Semi-mature Common Ash *Fraxinus excelsior*	14	1	12	6	Multiple stemmed at ground level with vertical stems. The crown overhangs the sports court and the sports field. Dense Ivy prevented a detailed inspection. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Remove the Ivy then re-inspect. Monitor biennially.	MOD	B	2
T 383	Early-mature Sycamore *Acer pseudoplatanus*	14	2	27	5	Single stemmed and vertical with a balanced crown. The crown overhangs the sports court. Ivy on the stem.	GOOD	FAIR	20-40	HIGH	Remove the Ivy.	LOW	B	2
T 384	Early-mature Common Ash *Fraxinus excelsior*	13	9	15	4	Single stemmed and vertical with a balanced crown. The crown overhangs the sports court. Dense Ivy prevented a detailed inspection. Significant Ash Dieback noted	POOR	POOR	<10	HIGH	Remove to ground level.	MOD	R	N/A
T 385	Early-mature Common Ash *Fraxinus excelsior*	14	9	24	6	Twin stemmed at ground level with vertical stems. The crown overhangs the sports court. Multiple pruning wounds due to crown lifting (occluding slowly). Significant Ash Dieback noted.	POOR	POOR	<10	HIGH	Remove to ground level.	MOD	R	N/A
T 386	Semi-mature Sycamore *Acer pseudoplatanus*	9	2	13	4	Single stemmed and vertical with an unbalanced crown. The crown overhangs the sports court. Occasional pruning wounds due to crown lifting (occluding slowly).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 387	Semi-mature Sycamore *Acer pseudoplatanus*	8	2	13	4	Twin stemmed aground level, vertical with an unbalanced crown. The crown overhangs the sports field. Minor dieback observed. Appears to be in an acceptable condition at this time.	FAIR	FAIR	10-20	HIGH	No action required.	N/A	A	2
T 388	Early-mature Common Oak *Quercus robur*	16	2	45	8	Single stemmed and vertical with an unbalanced crown. The crown overhangs the sports field. Multiple pruning wounds due to crown lifting (occluding slowly).	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 389	Early-mature Leyland Cypress *X Cupressocyparis leylandii*	19	0	75	7	Twin stemmed at 2m with vertical stems. The crown overhangs the sports court and sports field. Occasional pruning wounds due to crown lifting (occluding slowly).	GOOD	FAIR	40+	HIGH	No action required.	N/A	A	2
T 390	Semi-mature Common Ash *Fraxinus excelsior*	9	2	12	4	Multiple stemmed at ground level with vertical stems and a slightly unbalanced crown; a suppressed specimen. The crown overhangs the sports field. Multiple pruning wounds due to crown lifting. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 391	Semi-mature Sycamore *Acer pseudoplatanus*	13	2	18 x 2	6	Twin-stemmed at ground level with a balanced crown. The crown overhangs the sports court and the sports field. Decay forming at base where other stems have been previously removed. Dieback throughout. Limited future.	FAIR	POOR	<10	HIGH	Remove.	MOD	R	n/a
T 392	Semi-mature Sycamore *Acer pseudoplatanus*	10	2	10	4	Multiple stemmed at ground level with vertical stems. The crown overhangs the sports field. Occasional pruning wounds due to crown lifting.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 393	Semi-mature Common Ash *Fraxinus excelsior*	12	2	12	4	Multiple stemmed at ground level with vertical stems. The crown overhangs the sports field. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 394	Semi-mature Sycamore *Acer pseudoplatanus*	6	2	11	3	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the sports court.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 395	Semi-mature Common Ash *Fraxinus excelsior*	12	3	14	4	Single stemmed and vertical with a balanced crown. The crown overhangs the sports court. Minor Ash Dieback noted.	GOOD	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 396	Semi-mature Sycamore *Acer pseudoplatanus*	9	1	21	5	Multiple stemmed at ground level with vertical stems. The crown overhangs the sports court and the sports field. Occasional pruning wounds due to crown lifting (occluding slowly). Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 397	Semi-mature Common Ash *Fraxinus excelsior*	9	1	12	4	Twin stemmed at ground level with vertical stems. The crown overhangs the sports field. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2
T 398	Semi-mature Common Ash *Fraxinus excelsior*	11	1	9	5	Multiple stemmed at ground level with vertical stems. The crown overhangs the sports field. Minor Ash Dieback noted.	FAIR	FAIR	10-20	HIGH	Monitor biennially.	LOW	B	2

Tree Ref.	Age Species *Latin Name*	Height (m)	Crown Height (m)	Diameter (cm)	Crown Spread (m)	Observations	Physiological Condition	Structural Condition	Life Expectancy (yrs)	Target Value	Recommendations	Priority	Safety Category	Re-Inspection Timing (yrs)
T 399	Semi-mature Sycamore *Acer pseudoplatanus*	8	3	23	4	Single stemmed and vertical with a balanced crown. The crown overhangs the sports court. Occasional pruning wounds due to crown lifting. No major visible defects.	GOOD	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 400	Semi-mature Common Ash *Fraxinus excelsior*	15	3	27	7	Twin stemmed at 0.3m with vertical stems. The crown overhangs the sports court and sports field. Multiple pruning wounds due to crown lifting (occluding slowly). Deadwood noted (minor). Significant Ash Dieback noted.	POOR	POOR	10-20	HIGH	Remove to ground level.	MOD	R	N/A
T 401	Semi-mature Common Oak *Quercus robur*	4	0.5	24	5	Single stemmed and vertical with an unbalanced crown. Previously topped. The crown overhangs the sports court. Deadwood noted (minor).	FAIR	FAIR	20-40	HIGH	No action required.	N/A	A	2
T 402	Semi-mature Common Oak *Quercus robur*	9	1	13	4	Single stemmed and vertical with a slightly unbalanced crown. The crown overhangs the sports field. No major visible defects.	GOOD	GOOD	40+	HIGH	No action required.	N/A	A	2

Appendix 2: Arboricultural Terms of Reference

A2.1 Measurements

HEIGHT of the tree is measured from the stem base to the top of the canopy.

CROWN HEIGHT is an indication of the height at which the main crown begins above ground level.

STEM DIAMETER is measured at 1.5 metres above (higher) ground level. Where the tree is multi-stemmed at this point; the diameter is measured close to ground level, just above the root buttress.

CROWN SPREAD is a measurement of the overall width of the crown, at its widest point.

A2.2 Evaluations

AGE CLASS of the tree is described as Young, Semi-Mature, Early-Mature, Mature, Over-Mature or Veteran.

PHYSIOLOGICAL CONDITION is classed as good, fair, poor, or dead. This is an indication of the health of the tree and takes into account vigour, presence of disease and dieback.

STRUCTURAL CONDITION is classed as good, fair or poor. This is an indication of the structural integrity of the tree and takes into account significant wounds, decay and quality of branch junctions.

LIFE EXPECTANCY is classed as; less than 10 years (<10), 10-20 years, 20-40 years, or more than 40 years (40+). This is an indication of the number of years before removal of the tree is likely to be required.

TARGET VALUE is classed as high, moderate or low. This is an indication of the likelihood of persons or objects, the latter having variable significance, being within falling distance of a tree or its branches.

PRIORITY. A priority rating is given concerning the time periods in which the recommended works should be undertaken. HIGH priority works should be completed as soon as practically possible (within 3 months or as otherwise specified), MOD (moderate) priority works should be undertaken within 6 months and LOW priority works should be undertaken within 12 months of the survey. If no works are recommended, N/A (not applicable) will be used.

RE-INSPECTION TIMING is classed as; 6 months (0.5), 1 year (1), 2 years (2), or within 5 years (5). This is an indication of the timescale in which a tree should be re-inspected; a specific time of year for the inspection may also be detailed in the recommendations.

© JCA Limited 2025

A2.3 Works Categories

WORK CATEGORIES for the trees are as follows:

A (marked in green on the plan) = posing no immediate risk: no action required at this time.

These trees are considered to be in an acceptable condition at present and require no action at this time. However, these trees may require future management.

B (marked in light blue on the plan) = posing a potential risk: action required.

These trees pose a potential risk and therefore require active management.

Such trees may also require a further, more detailed, investigation (such as a climbing inspection or a decay detection analysis) or may require future monitoring (re-surveying and re-assessing) at a timescale specified within this report.

R (marked in red on the plan) = trees to be removed.

These trees require removal usually because they are dead, dying or dangerous and are therefore potentially hazardous. Such trees shall usually require removal as a matter of high priority.

Trees may also require removal in order to prevent damage occurring to existing structures or buildings (where trees are growing within close proximity or are in actual contact) or in order to benefit adjacent trees (where trees are growing in direct competition, the poorer of the two trees may be removed). Such work is usually of a lower priority.

A2.4 Recommended Clearances from Tree Canopies

JCA recommend the following distances are maintained from tree canopies:

Height for pedestrian access:	No less than 2.5m
Height for vehicular access:	No less then 4m for a minor road
	No less than 6m for major roads (or where double-decker buses or HGV's will pass).
Distance from overhead cables:	No less than 2m
Distance from a building/structure:	No less than 2m
Distance from lamppost/sign:	Sufficient to not impede visibility for 2 years.

© JCA Limited 2025

Appendix 3: Author Qualifications

Principal Consultant and Managing Director

Jonathan Cocking *F.R.E.S., Tech. Cert. (Arbor.A), PDipArb (RFS) FArborA CBiol MSB. MICFor.* Jonathan is a Registered Consultant and Fellow of the Arboricultural Association and sits on its Professional Committee. He has 31 years' experience in the Arboricultural profession and served for eight years as Senior Arboriculturist with a large local authority before establishing JCA in 1997. Jonathan has since developed JCA's portfolio of services and its extensive client base. He is a Chartered Biologist, a Chartered Arboriculturalist and an Expert Witness with much experience of litigation work.

Technical Director

Toby Thwaites *BSc (Hons), HND (Arboriculture), LANTRA Accredited PTI, MArborA.* Toby joined JCA in 1998 after graduating in Ecology at the University of Huddersfield and has since graduated in Arboriculture at the University of Central Lancashire. A former JCA team leader and Consulting Arboriculturist, Toby is now Technical Director and oversees all office and on-site activities at JCA and is on hand to offer technical support and advice.

Operations Director

Charles Cocking *FdSc (Arboriculture), LANTRA Accredited PTI, MArborA.* Charles joined JCA in January 2014 having previously worked for the company on a part time basis during 2013. Charles obtained his Foundation Degree in Arboriculture at Askham Bryan College, York, and is a Professional Member of the Arboricultural Association. Charles now oversees all internal operations for the company.

Arboricultural Projects Director

Luke Wickham *FdSc (Arboriculture and Urban Forestry), LANTRA Accredited PTI, MArborA.* Luke joined JCA in 2021 after obtaining his Foundation Degree in Arboriculture and Urban Forestry at Askham Bryan College. Having previously worked within the industry for the past 4 years, running his own small business and sub-contracting for local firms, Luke brings a sound knowledge and understanding of the practical and academic sides of the industry.

Consulting Staff: Arboriculture

Andrew Bussey *LANTRA Accredited PTI, TechArborA.* Andrew started working in consultancy at JCA in 2006 having spent 12 years working as an arborist for various private companies before joining a Local Authority forestry team. He has various NPTC qualifications and is QTRA qualified.

Emily Wilde *FdSc (Arboriculture), LANTRA Accredited PTI, TechArborA.* Emily joined JCA having previously worked for various private tree surgery and consultancy companies over the past 8 years. She initially obtained a ND in Forestry & Arboriculture, followed by a FdSc in Arboriculture at Askham Bryan College, York. Emily has various NPTC certificates and is QTRA qualified.

Mick Eltringham *ND (Forestry), LANTRA Accredited PTI, TechArborA.* Mick joined JCA after spending 12 years working in the industry for various private companies in the north and south of England. He has also spent the last five years working as a consultant for two canopy research projects in the Amazon Rainforest, working with Oxford University and the University of Arizona. He has various NPTC Qualifications.

Dan Kemp *FdSc (Arboriculture), BTEC Dip (Arb), LANTRA Accredited PTI, MArborA.* Dan joined JCA in February 2019 with nearly 30 years' experience in arboriculture with extensive Botanical and Mycological expertise. He worked as a London Tree Officer for 12 years and in several arboricultural and horticultural management posts, specialising particularly in tree risk assessments and tree related subsidence.

David de Peña *BSc (Hons) Ecology and Conservation, TechArborA.* After earning his degree from Manchester Metropolitan University, David worked as an ecologist at various consultancies, contributing to a wide range of projects, including major infrastructure projects across the UK. More recently, David transitioned to arboriculture and served as a surveyor for Manchester City of Trees, where he participated in a project to quantify the value of Greater Manchester's woodlands and trees.

Administrative Staff

Catherine Cocking Accounts Manager.
Kelly Saunders Credit Control Manager.
Adie Gray I.T. Officer.
Lorraine Spink Administrative Assistant.
Alannah Chapman Administrative Assistant.

© JCA Limited 2025

Appendix 4: General Guidelines

A4.1 All tree work should be undertaken to BS 3998: 2010 'Recommendations for tree work' or other recognised industry practice.

A4.2 Staff carrying out the work must be qualified, experienced and ideally be Arboricultural Association approved contractors. They should be covered by adequate public liability insurance.

A4.3 This report is based upon a visual inspection. The consultant shall not be responsible for events which happen after this time due to factors which were not apparent at the time, and the acceptance of this report constitutes an agreement with the guidelines and the terms listed in this report.

A4.4 Any defects seen by a contractor or the employer that were not apparent to the consultant must be brought to the consultant's attention immediately.

A4.5 No liability can be accepted by JCA in respect of the trees unless the recommendations of this report are carried out under the supervision of JCA and within JCA's timescale.

A4.6 It is advisable to have trees inspected by an arboricultural consultant on a regular basis. In this instance it is recommended that these inspections are made as per the recommended re-inspection timings at **Appendix 1**.

© JCA Limited 2025



Appendix 5: Site Plan

ADDRESS: Huddersfield Grammar School, Luck Lane, Marsh, Huddersfield, HD1 4QX.
JCA REF: 23001/AJB

SCALE 1:500	PAPER SIZE A1

SURVEYED BY: AJB	DRAWN BY: AJB	APPROVED BY: TT

TREE WORKS CATEGORIES

Detailed definitions of the works categories can be found at Appendix 2 of the arboricultural report.

	WORKS CATEGORY A: NO WORKS REQUIRED
	WORKS CATEGORY B: WORKS OR MONITORING REQUIRED
	WORKS CATEGORY R: TREE TO BE REMOVED

PLEASE NOTE THAT THE FOLLWOING TREES HAVE BEEN REMOVED (AS PREVIOUSLY ADVISED) AND HAVE THEREFORE BEEN OMITTED FROM THIS PLAN:

T18, T20, T30, T43, T51, T52, T98, T142, T192, T193, T226, T233, T249, T254, T260, T284, T296, T297, T299, T302, T303, T313A, T315, T316, T317, T318 and T323.

JCA Limited

Arboricultural & Ecological Consultants

I hope that this report provides all the necessary information, but should any further advice be needed please do not hesitate to contact the author.

Signed

.....

Andrew Bussey *LANTRA Accredited PTI, TechArborA*.

22nd August 2025

For and on behalf of ***JCA Ltd***

Registered Office

Unit 80
Bowers Mill
Branch Road
Barkisland
Halifax
HX4 0AD

Tel: 01422 376335
Email: info@jcaac.com

www.jcaac.com

© JCA Limited 2025

JCA Ltd. Arboricultural and Ecological Consultants
Professional Tree and Ecology Advice nationwide

ARBORICULTURAL SERVICES

Guidance for Architects and Developers

- British Standard 5837 Tree Surveys
- Arboricultural Implication Assessments (AIA)
- Arboricultural Method Statements (AMS)

Advice for Engineers, Loss Adjusters and Insurers

- Tree Surveys for Subsidence
- Heave Assessment
- Tree Root Identification

Advice for Local Authorities and Social Housing

- Tree Condition Surveys
- Specialist Decay Detection
- Landscape and Orchard Design

Tree Advice for the Legal Profession

- Subsidence Litigation
- Personal Injury and Accident Investigation
- Expert Witness, Planning Inquiries and Appeals

Veteran Tree Management

- Ancient Woodland Management
- Veteran Tree Management

Tree Health and Pest and Disease Management

- Pest and Disease Surveys
- Tree Health Checks
- Disease Mitigation and Control

ECOLOGICAL SERVICES

Ecological Pre-Planning Services

- Phase 1 Habitat Surveys
- Great Crested Newt eDNA Sampling
- Protected Species: Bat, Wintering and Nesting Bird, Badger, Amphibian, Otter, Water Vole, White-Clawed Crayfish, Dormice and Reptile Surveys.
- Preparation for Environmental Impact Assessment (EIA)
- Invasive Species Surveys
- Code for Sustainable Homes

Ecological Post-Planning Services

- Biodiversity Enhancement Plans
- Protected Species Mitigation
- Ecological Management (Bat and Bird box installation and inspection)



HEAD QUARTERS:

Unit 80 Bowers Mill,
Branch Road,
Barkisland,
Halifax, HX4 0AD.

Tel: 01422 376335
Email: info@jcaac.com
Website: www.jcaac.com

Company Reg No. 05005041
VAT No. 686 4674 78