193 Bedroom

Heritage Significance	Low
Description of Significance	1851 Plans and 1930s indicate this formed a singular large bedroom. . Note whilst corner rolls on ceilings in place, historic water damage to the outer wall has revealed these to be fitted age in nature (some brown gypsum sections) and it should be noted that the ceilings total loss due to demonstrable evidence of debonding, historic water damage, lath rot and multiple instances of poor repair and gypsum plaster application. It is noted that a similar issue arises to internal walls in respect of general plaster condition (very poor). The significance of this space is largely derived from its largely 1930 plan form, the volume and mansard form to the outer wall. Some of the 1930s door architraves remain
Demolition	Strip out Floor: **No** | Strip out Ceiling: **Yes** | Strip out Wall: **No** | Strip out FF&E: **Yes** Refer to demolition plans for more information.
Works to Floor	Enhancement to existing floor structure to provide fire & acoustic compliance. Refer to Detail 2 on AHR drawing 20300
Works to Ceiling	N/A
Works to Walls	New Partition with Skirting: **Yes** | New Door opening in existing Wall: **No** All existing plaster to be removed and existing walls to be made good. Plasterboard on metal framing system fixed back to existing masonry walls (Internal). Wall lining system with air gap to be installed against existing mansard externally. Refer to AHR drawing 20301.
Works to Windows	Window panelling to reveals to be reinstated (Where required) & redecorated
Works to Doors (External)	N/A
Works to Doors (Internal)	Existing architrave and door lining to be carefully removed bedroom side to allow for new internal doorset to be installed within the existing structural opening. Existing architrave to be reinstated where possible, where existing can't be reinstated, new shall be installed with a profile & material to be agreed with the conservation officer. Where door sits within a wall receiving plasterboard on metal lining the existing door lining shall be extended to suit.
Miscellaneous	New FF&E throughout. Refer to interior design strategy for more information. Ceilings and mansard wall plaster to be removed (left retained in place where practicable). Netting and stand off insulated liner system to be applied. Door architraves to be retained where possible. Refer to AHR Drawing L054-AHR-40-BA-ZZ-D-A-40701 for approach to skirting reinstatement / replacement.
M&E Works	Ventilation strategy is via vents within the existing facade. Services to be concealed in proposed ceiling void. Refer to MEP drawings for further details.

194 En-Suite

Heritage Significance	Detrimental
Description of Significance	Under 1886 plans formerly part of the wardrogroom for bedroom 195 - considered total material loss due to extensive historical interior works.
Demolition	Strip out Floor: **No** | Strip out Ceiling: **Yes** | Strip out Wall: **Yes** | Strip out FF&E: **Yes** Refer to demolition plans for more information.
Works to Floor	Enhancement to existing floor structure to provide fire & acoustic compliance. Refer to Detail 7 on AHR drawing 20300
Works to Ceiling	N/A
Works to Walls	New Partition with Skirting: **No** | New Door opening in existing Wall: **Yes** Existing lime plaster to be retained where practically possible. Areas requiring repair are to be removed before recieving traditional lime plaster.
Works to Windows	N/A
Works to Doors (External)	N/A
Works to Doors (Internal)	Existing opening widened, new internal doorset installed within opening.
Miscellaneous	Refer to AHR Drawing L054-AHR-40-BA-ZZ-D-A-40701 for approach to skirting reinstatement / replacement.
M&E Works	Exposed services within corridor spaces concealed via expanded mesh ceiling raft with integral lighting. Refer to MEP drawings for more information.

196 En-Suite

Heritage Significance	Detrimental
Description of Significance	Under 1886 plans formerly part of the wardrogroom for bedroom 195 - considered total material loss due to extensive historical interior works.
Demolition	Strip out Floor: **No** | Strip out Ceiling: **Yes** | Strip out Wall: **Yes** | Strip out FF&E: **Yes** Refer to demolition plans for more information.
Works to Floor	Enhancement to existing floor structure to provide fire & acoustic compliance. Refer to Detail 7 on AHR drawing 20300
Works to Ceiling	N/A
Works to Walls	New Partition with Skirting: **No** | New Door opening in existing Wall: **No** Existing lime plaster to be retained where practically possible. Areas requiring repair are to be removed before recieving traditional lime plaster.
Works to Windows	Existing window to be removed and opening to be made good
Works to Doors (External)	N/A
Works to Doors (Internal)	Existing architrave and door lining to be carefully removed bedroom side to allow for new internal doorset to be installed within the existing structural opening. Existing architrave to be reinstated where possible, where existing can't be reinstated, new shall be installed with a profile & material to be agreed with the conservation officer. Where door sits within a wall receiving plasterboard on metal lining the existing door lining shall be extended to suit.
Miscellaneous	Refer to AHR Drawing L054-AHR-40-BA-ZZ-D-A-40701 for approach to skirting reinstatement / replacement.
M&E Works	Exposed services within corridor spaces concealed via expanded mesh ceiling raft with integral lighting. Refer to MEP drawings for more information.

195 Bedroom

Heritage Significance	Low
Description of Significance	Under 1886 plans this formed a singular bedroom with and has an original dedicated doorway into ensuite 196 (former small sitting room). 1930s plans included opening formed into former dedicated general WC 194 and new opening to ensuite 196 (former small sitting room). Note whilst corner rolls on ceilings in place, historic water damage to the outer wall has revealed these to be fitted age in nature (some brown gypsum sections) and it should be noted that the ceilings total loss due to demonstrable evidence of debonding, historic water damage, lath rot and multiple instances of poor repair and gypsum plaster application. It is noted that a similar issue arises to internal walls in respect of general plaster condition (very poor). Significance derives largely from largely unamended 1886 plan form and entrance WC door ways which retain their 1886 profiles architraves
Demolition	Strip out Floor: **No** | Strip out Ceiling: **Yes** | Strip out Wall: **No** | Strip out FF&E: **Yes** Refer to demolition plans for more information.
Works to Floor	Enhancement to existing floor structure to provide fire & acoustic compliance. Refer to Detail 2 on AHR drawing 20300
Works to Ceiling	N/A
Works to Walls	New Partition with Skirting: **Yes** | New Door opening in existing Wall: **No** All existing plaster to be removed and existing walls to be made good. Plasterboard on metal framing system fixed back to existing masonry walls (Internal). Wall lining system with air gap to be installed against existing mansard externally. Refer to AHR drawing 20301.
Works to Windows	Window panelling to reveals to be reinstated (Where required) & redecorated
Works to Doors (External)	N/A
Works to Doors (Internal)	Existing architrave and door lining to be carefully removed bedroom side to allow for new internal doorset to be installed within the existing structural opening. Existing architrave to be reinstated where possible, where existing can't be reinstated, new shall be installed with a profile & material to be agreed with the conservation officer. Where door sits within a wall receiving plasterboard on metal lining the existing door lining shall be extended to suit.
Miscellaneous	New FF&E throughout. Refer to interior design strategy for more information. Ceilings and mansard wall plaster to be removed (left retained in place where practicable). Netting and stand off insulated liner system to be applied. Door architraves to be retained where possible. Refer to AHR Drawing L054-AHR-40-BA-ZZ-D-A-40701 for approach to skirting reinstatement / replacement.
M&E Works	Ventilation strategy is via vents within the existing facade. Services to be concealed in proposed ceiling void. Refer to MEP drawings for further details.

(20) Heritage Scoping General Notes & Key

Heritage Significance Key

- Considerable
- High
- Moderate
- Low
- Neutral
- Detrimental

Drawings to be read in conjunction with the following drawing packages.

Demolition Plans

L054-AHR-20-ZZ-ZZ-D-A-20010 - Ground & Mezzanine Floor Demolition Plan
L054-AHR-20-01-ZZ-D-A-20012 - First Floor Demolition Plan
L054-AHR-20-ZZ-02-D-A-20013 - Second Floor Demolition Plan
L054-AHR-20-ZZ-03-D-A-20014 - Third Floor Demolition Plan
L054-AHR-20-ZZ-04-D-A-20015 - Fourth Floor Demolition Plan
L054-AHR-20-ZZ-B1-D-A-20016 - Basement Level Demolition Plan
L054-AHR-20-ZZ-RF-D-A-20017 - Roof Level Demolition Plan

Proposed Plans

L054-AHR-ZZ-ZZ-00-D-A-20700 - Proposed Ground Floor Plan (Planning)
L054-AHR-ZZ-ZZ-M-D-A-20701 - Proposed Mezzanine Floor Plan (Planning)
L054-AHR-ZZ-ZZ-01-D-A-20702 - Proposed First Floor Plan (Planning)
L054-AHR-ZZ-ZZ-02-D-A-20703 - Proposed Second Floor Plan (Planning)
L054-AHR-ZZ-ZZ-03-D-A-20704 - Proposed Third Floor Plan (Planning)
L054-AHR-ZZ-ZZ-04-D-A-20705 - Proposed Fourth Floor Plan (Planning)
L054-AHR-ZZ-ZZ-ZZ-D-A-20706 - Proposed Basement Floor Plan (Planning)
L054-AHR-ZZ-ZZ-ZZ-D-A-20707 - Proposed Roof Plan (Planning)

Refurbishment Strategy Drawings

L054-AHR-20-BA-00-D-A-20201 - Ground Floor Reception - Refurbishment Strategy
L054-AHR-20-BA-00-D-A-20202 - Ground Floor Reception Elevations - Refurbishment Strategy
L054-AHR-20-BA-00-D-A-20203 - Conference Room - Refurbishment Strategy
L054-AHR-20-BA-01-D-A-20204 - Former Dining Room - Refurbishment Strategy
L054-AHR-20-BA-00-D-A-20205 - Former Signing Room - Refurbishment Strategy

Interior Design Strategy

L054-AHR-ZZ-ZZ-ZZ-T-I-08901 - Interior Design Strategy

X77 Circ.

Heritage Significance	Low
Description of Significance	this space has remained largely unaltered from the 1886 form as transition lobby for Bed 175 & 177. Acting as an original corridor and "lobby" it is framed by the plaster archway adjoining X77. All brickwork to openings and skirtings appear to be 1930s in origin. Ceilings appear to be 1970s in origin.
Demolition	Strip out Floor: **No** | Strip out Ceiling: **Yes** | Strip out Wall: **No** | Strip out FF&E: **Yes** Refer to demolition plans for more information.
Works to Floor	Enhancement to existing floor structure to provide fire & acoustic compliance. Refer to Detail 7 on AHR drawing 20300
Works to Ceiling	N/A
Works to Walls	New Partition with Skirting: **No** | New Door opening in existing Wall: **No** Existing lime plaster to be retained where practically possible. Areas requiring repair are to be removed before recieving traditional lime plaster.
Works to Windows	N/A
Works to Doors (External)	N/A
Works to Doors (Internal)	N/A
Miscellaneous	As x71 - reinstatement of ceiling in coffer style, archway rolls and doorway 30s roll timber architraves to be retained where practicable. Refer to AHR Drawing L054-AHR-40-BA-ZZ-D-A-40701 for approach to skirting reinstatement / replacement.
M&E Works	Exposed services within corridor spaces concealed via expanded mesh ceiling raft with integral lighting. Refer to MEP drawings for more information.

197 Store

Heritage Significance	Detrimental
Description of Significance	under 1886 plans this formed a sole bathroom of the circulation X77 (general bathroom) Under 1930s plans this was converted into a general storeroom. Note whilst corner rolls on ceilings in place, historic water damage to the outer wall has revealed these to be fitted age in nature (some brown gypsum sections) and it should be noted that the ceilings total loss due to demonstrable evidence of debonding, historic water damage, lath rot and multiple instances of poor repair and gypsum plaster application. It is noted that a similar issue arises to internal walls in respect of general plaster condition (very poor). Significance derives largely from largely unamended 1886 plan form and entrance WC door way which retain their 1886 profiles architraves
Demolition	Strip out Floor: **No** | Strip out Ceiling: **Yes** | Strip out Wall: **Yes** | Strip out FF&E: **Yes** Refer to demolition plans for more information.
Works to Floor	Enhancement to existing floor structure to provide fire & acoustic compliance. Refer to Detail 2 on AHR drawing 20300
Works to Ceiling	N/A
Works to Walls	New Partition with Skirting: **No** | New Door opening in existing Wall: **No** All existing plaster to be removed and existing walls to be made good. Plasterboard on metal framing system fixed back to existing masonry walls (Internal). Wall lining system with air gap to be installed against existing mansard externally. Refer to AHR drawing 20301.
Works to Windows	N/A
Works to Doors (External)	N/A
Works to Doors (Internal)	Existing door opening to be infilled.
Miscellaneous	New FF&E throughout. Refer to interior design strategy for more information. Ceilings and mansard wall plaster to be removed (left retained in place where practicable). Netting and stand off insulated liner system to be applied. Door architraves to be retained where possible. Refer to AHR Drawing L054-AHR-40-BA-ZZ-D-A-40701 for approach to skirting reinstatement / replacement.
M&E Works	Ventilation strategy is via vents within the existing facade. Services to be concealed in proposed ceiling void. Refer to MEP drawings for further details.

199 En-Suite

Heritage Significance	Detrimental
Description of Significance	As 197 - finishes comprise total loss due to historic strip out works and water damage.
Demolition	Strip out Floor: **No** | Strip out Ceiling: **Yes** | Strip out Wall: **Yes** | Strip out FF&E: **Yes** Refer to demolition plans for more information.
Works to Floor	Enhancement to existing floor structure to provide fire & acoustic compliance. Refer to Detail 2 on AHR drawing 20300
Works to Ceiling	N/A
Works to Walls	New Partition with Skirting: **No** | New Door opening in existing Wall: **No** All existing plaster to be removed and existing walls to be made good. Plasterboard on metal framing system fixed back to existing masonry walls (Internal). Wall lining system with air gap to be installed against existing mansard externally. Refer to AHR drawing 20301.
Works to Windows	Window panelling to reveals to be reinstated (Where required) & redecorated
Works to Doors (External)	N/A
Works to Doors (Internal)	Existing architrave and door lining to be carefully removed bedroom side to allow for new internal doorset to be installed within the existing structural opening. Existing architrave to be reinstated where possible, where existing can't be reinstated, new shall be installed with a profile & material to be agreed with the conservation officer. Where door sits within a wall receiving plasterboard on metal lining the existing door lining shall be extended to suit.
Miscellaneous	New FF&E throughout. Refer to interior design strategy for more information. Ceilings and mansard wall plaster to be removed (left retained in place where practicable). Netting and stand off insulated liner system to be applied. Door architraves to be retained where possible. Refer to AHR Drawing L054-AHR-40-BA-ZZ-D-A-40701 for approach to skirting reinstatement / replacement.
M&E Works	Ventilation strategy is via vents within the existing facade. Services to be concealed in proposed ceiling void. Refer to MEP drawings for further details.

183 Bedroom

Heritage Significance	Low
Description of Significance	This formed a singular bedroom space under the 1886 plans which was amended in the 1930 plans to include the adjacent en suite 184 by the forming of a new opening through flanking wall. Timberwork associated with the 1930s door way into the adjacent bathroom is consistent with the 30s roll style architrave to the main entrance door and sole remaining skirting (poor condition) section to the outside wall. Note whilst corner rolls on ceilings in place, historic water damage to the outer wall has revealed these to be fitted age in nature (some brown gypsum sections) and it should be noted that the ceilings total loss due to demonstrable evidence of debonding, historic water damage, lath rot and multiple instances of poor repair and gypsum plaster application. It is noted that a similar issue arises to internal walls in respect of general plaster condition (very poor). The significance of this space is largely derived from its largely unaltered plan form, the volume and mansard form to the outer wall. The door reveals retain some of their 1930s architraves.
Demolition	Strip out Floor: **No** | Strip out Ceiling: **Yes** | Strip out Wall: **No** | Strip out FF&E: **Yes** Refer to demolition plans for more information.
Works to Floor	Enhancement to existing floor structure to provide fire & acoustic compliance. Refer to Detail 2 on AHR drawing 20300
Works to Ceiling	N/A
Works to Walls	New Partition with Skirting: **Yes** | New Door opening in existing Wall: **Yes** All existing plaster to be removed and existing walls to be made good. Plasterboard on metal framing system fixed back to existing masonry walls (Internal). Wall lining system with air gap to be installed against existing mansard externally. Refer to AHR drawing 20301.
Works to Windows	Window panelling to reveals to be reinstated (Where required) & redecorated
Works to Doors (External)	N/A
Works to Doors (Internal)	New internal doorset to be installed within new opening in existing wall. New frames & architraves to match existing.
Miscellaneous	New FF&E throughout. Refer to interior design strategy for more information. Ceilings and mansard wall plaster to be removed (left retained in place where practicable). Netting and stand off insulated liner system to be applied. Refer to AHR Drawing L054-AHR-40-BA-ZZ-D-A-40701 for approach to skirting reinstatement / replacement.
M&E Works	Ventilation strategy is via vents within the existing facade. Services to be concealed in proposed ceiling void. Refer to MEP drawings for further details.

184 En-Suite

Heritage Significance	Detrimental
Description of Significance	Nov 183 - detrimental as interruption to plan form of 1886 and 1930s and modernised extensively in 1970s/ 80s. Note, historic works represent a total loss of ceiling and mansard finishes due to water ingress and subsequent repair works.
Demolition	Strip out Floor: **No** | Strip out Ceiling: **Yes** | Strip out Wall: **Yes** | Strip out FF&E: **Yes** Refer to demolition plans for more information.
Works to Floor	Enhancement to existing floor structure to provide fire & acoustic compliance. Refer to Detail 2 on AHR drawing 20300
Works to Ceiling	N/A
Works to Walls	New Partition with Skirting: **Yes** | New Door opening in existing Wall: **Yes** All existing plaster to be removed and existing walls to be made good. Plasterboard on metal framing system fixed back to existing masonry walls (Internal). Wall lining system with air gap to be installed against existing mansard externally. Refer to AHR drawing 20301.
Works to Windows	Window panelling to reveals to be reinstated (Where required) & redecorated
Works to Doors (External)	N/A
Works to Doors (Internal)	Existing opening to be infilled.
Miscellaneous	New FF&E throughout. Refer to interior design strategy for more information. Note, historic works represent a total loss of ceiling and mansard finishes due to water ingress and subsequent repair works. Refer to AHR Drawing L054-AHR-40-BA-ZZ-D-A-40701 for approach to skirting reinstatement / replacement.
M&E Works	Ventilation strategy is via vents within the existing facade. Services to be concealed in proposed ceiling void. Refer to MEP drawings for further details.

201 En-Suite

Heritage Significance	Detrimental
Description of Significance	Nov 200 - formerly part of one bed in 1886 plans, separated into 2 beds in 1930s works and new entrance to corridor X71 formed; later works performed (1970s and beyond) to sub divide into en suite (along with 184) and a small WC (accessed via a new door opening formed in existing bedroom) - adjacent bedroom 200. Material condition fully stripped surfaces and little historic fabric remaining.
Demolition	Strip out Floor: **No** | Strip out Ceiling: **Yes** | Strip out Wall: **Yes** | Strip out FF&E: **Yes** Refer to demolition plans for more information.
Works to Floor	Enhancement to existing floor structure to provide fire & acoustic compliance. Refer to Detail 2 on AHR drawing 20300
Works to Ceiling	N/A
Works to Walls	New Partition with Skirting: **Yes** | New Door opening in existing Wall: **Yes** All existing plaster to be removed and existing walls to be made good. Plasterboard on metal framing system fixed back to existing masonry walls (Internal). Wall lining system with air gap to be installed against existing mansard externally. Refer to AHR drawing 20301.
Works to Windows	N/A
Works to Doors (External)	N/A
Works to Doors (Internal)	New internal door within new opening formed within the existing wall, new frames & architraves to match the existing
Miscellaneous	New FF&E throughout. Refer to interior design strategy for more information. Refer to AHR Drawing L054-AHR-40-BA-ZZ-D-A-40701 for approach to skirting reinstatement / replacement.
M&E Works	Ventilation strategy is via vents within the existing facade. Services to be concealed in proposed ceiling void. Refer to MEP drawings for further details.

200 Bedroom

Heritage Significance	Detrimental
Description of Significance	Under 1886 plans this formed a large singular bedroom with the adjacent (now WC spaces) 195 & 194. The room was separated during 1930s works into 2 equal sized bedrooms (the current plan form) with later works (1970s and beyond) to sub divide into en suite (along with 201) and adjacent areas, the ceiling and mansard plasterwork are deemed total loss due to historic works and damage.
Demolition	Strip out Floor: **No** | Strip out Ceiling: **Yes** | Strip out Wall: **Yes** | Strip out FF&E: **Yes** Refer to demolition plans for more information.
Works to Floor	Enhancement to existing floor structure to provide fire & acoustic compliance. Refer to Detail 2 on AHR drawing 20300
Works to Ceiling	N/A
Works to Walls	New Partition with Skirting: **No** | New Door opening in existing Wall: **No** All existing plaster to be removed and existing walls to be made good. Plasterboard on metal framing system fixed back to existing masonry walls (Internal). Wall lining system with air gap to be installed against existing mansard externally. Refer to AHR drawing 20301.
Works to Windows	Window panelling to reveals to be reinstated (Where required) & redecorated
Works to Doors (External)	N/A
Works to Doors (Internal)	Existing architrave and door lining to be carefully removed bedroom side to allow for new internal doorset to be installed within the existing structural opening. Existing architrave to be reinstated where possible, where existing can't be reinstated, new shall be installed with a profile & material to be agreed with the conservation officer. Where door sits within a wall receiving plasterboard on metal lining the existing door lining shall be extended to suit.
Miscellaneous	New FF&E throughout. Refer to interior design strategy for more information. ceilings and mansard wall plaster to be removed (left retained in place where practicable). Netting and stand off insulated liner system to be applied. Door architraves to be retained where possible. Refer to AHR Drawing L054-AHR-40-BA-ZZ-D-A-40701 for approach to skirting reinstatement / replacement.
M&E Works	Ventilation strategy is via vents within the existing facade. Services to be concealed in proposed ceiling void. Refer to MEP drawings for further details.

198 Bedroom

Heritage Significance	Low
Description of Significance	plan form largely unchanged as a bedroom under 1886 and 1930s plans. Fireplace loss and new opening to WC formed in 1930s works Note whilst corner rolls on ceilings in place, historic water damage to the outer wall has revealed these to be fitted age in nature (some brown gypsum sections) and it should be noted that the ceilings total loss due to demonstrable evidence of debonding, historic water damage, lath rot and multiple instances of poor repair and gypsum plaster application. It is noted that a similar issue arises to internal walls in respect of general plaster condition (very poor). Significance derives largely from largely unamended 1886 plan form and entrance WC door way which retain their 1886 profiles architraves
Demolition	Strip out Floor: **No** | Strip out Ceiling: **Yes** | Strip out Wall: **Yes** | Strip out FF&E: **Yes** Refer to demolition plans for more information.
Works to Floor	Enhancement to existing floor structure to provide fire & acoustic compliance. Refer to Detail 2 on AHR drawing 20300
Works to Ceiling	N/A
Works to Walls	New Partition with Skirting: **Yes** | New Door opening in existing Wall: **No** All existing plaster to be removed and existing walls to be made good. Plasterboard on metal framing system fixed back to existing masonry walls (Internal). Wall lining system with air gap to be installed against existing mansard externally. Refer to AHR drawing 20301.
Works to Windows	Window panelling to reveals to be reinstated (Where required) & redecorated
Works to Doors (External)	N/A
Works to Doors (Internal)	Existing architrave and door lining to be carefully removed bedroom side to allow for new internal doorset to be installed within the existing structural opening. Existing architrave to be reinstated where possible, where existing can't be reinstated, new shall be installed with a profile & material to be agreed with the conservation officer. Where door sits within a wall receiving plasterboard on metal lining the existing door lining shall be extended to suit.
Miscellaneous	New FF&E throughout. Refer to interior design strategy for more information. Ceilings and mansard wall plaster to be removed (left retained in place where practicable). Netting and stand off insulated liner system to be applied. Door architraves to be retained where possible. Refer to AHR Drawing L054-AHR-40-BA-ZZ-D-A-40701 for approach to skirting reinstatement / replacement.
M&E Works	Ventilation strategy is via vents within the existing facade. Services to be concealed in proposed ceiling void. Refer to MEP drawings for further details.

04 Level 04 - Fourth Floor Heritage Scoping Plan - Sheet 2

1 : 50

Rev	Description	Date	Dr by	App by
P3	Issued for Planning	15.05.2026	DR	MS
P2	Issued for Stage 3	16.05.2025	DR	MCS
P1	Issued for Planning	22.04.2025	DR	MCS

original by: DR | date created: 02/01/2025 | Approved by: MS

AHR Architects Ltd
No.1 Aire Street
Leeds
LS1 4PR
United Kingdom

T +44(0)113 3858787
E leeds@ahr.co.uk
www.ahr.co.uk

GMI

Kirklees COUNCIL

client name: GMI Construction Group

project: George Hotel Refurbishment

drawing: Fourth Floor Heritage Scoping Plan - Sheet 2

computer file: I:\0.22.11.CD\06_Profiles_Folder_selection\cursor-client\Documents\Revit Files\Local Files\Revit 2024\L054-AHR-ZZ-ZZ-M-A-08001_detail_Main.rvt

plot date:

project number: 2024.00373.000

scale: As indicated@A0

drawing number: L054-AHR-20-BA-04-D-A-20048

rev: P3

issue status: S2

This drawing is to be read in conjunction with all related drawings. All dimensions must be checked and verified on site before commencing any work or producing shop drawings. The originator should be notified immediately of any discrepancy.
This drawing is copyright and remains the property of AHR.

N

SCALE 1 : 50

0 1 2 3