

Riven Slabs



SCAN HERE

Rugged riven texture.

Riven Slabs are engineered with a natural, rugged feel, emulating natural stone. Riven Slabs are the ideal paving slabs for creating a rustic look.

- Superb hard-wearing riven surface
- Vibrant long-lasting colours
- Resembles the rugged appearance of natural stone

PrimeTop®

R


Riven

Finish




Pedestrian
Use


Refer to relevant guidance in BS 7533



600 x 600mm



450 x 450mm



400x400mm

Sizes



35mm
40mm

Depths

Riven Slabs



Specification



Product type	Concrete Paving Slab
Manufactured to	BS EN 1339:2003
Surface Layer	Hard-wearing surface layer with a minimum of 4mm and >390kg/m ³ cement
Chamfer	Chamfered
Efflorescence	Minimum 12 hour vapour curing to significantly reduce the possibility of efflorescence
Bending Strength	Characteristic tensile splitting strength not less than 3.6 MPa
Slip/Skid Resistance	Mean polished skid resistance value (PSRV) >45 Mean unpolished skid resistance value (USRV) >45
Installed to	BS 7533-102:2025
NS	Plus Q25 315 Create 45-20-64/395
Tolerances on Dimensions (mm)	Length ±2mm, width ±2mm, thickness ±3mm
Abrasion Resistance (mm)	≤ 23mm (Wide Wheel Abrasion Test) Class 3
Durability (Freeze-thaw)	≤ 1.0 kg/m ² as a mean with no individual value > 1.5 kg/m ² Class 3
External Fire Performance	Deemed to satisfy when used for roofing
Reaction to fire	Class A1
Applications	Refer to the relevant part of BS 7533 for the correct sub-base design and the most suitable product size for your application. Available from www.bsigroup.com
Energy used	100% renewable energy
Water used	100% from our rainwater harvesting system and groundwater bore hole
Recycled content	Not less than 5%
 Carbon Footprint	EPD Verified (2020) 400x400x40mm 9.06kgCo ₂ e/m ² 450x450x35mm 8.86kgCo ₂ e/m ² 600x600x40mm 9.80kgCo ₂ e/m ²
Recyclable	100% of this product can be recycled
Manufacturing & Delivery	From one location within the UK
 Breeam rating www.bre.co.uk	A , according to the Green Guide to Specification, 4 th Edition 2009. A+ , can be achieved by using a recycled sub-base.

Tobermore products are manufactured in accordance with an accredited ISO 9001:2015 Quality Management. Manufacturing facilities are accredited to ISO14001:2015 Environmental Management. The company publish environmental labels and declarations in accordance with BES 6001.

Contact Us

GB: 0844 800 5736
NI: 028 7964 2411
ROI: 048 7964 2411

Email

technical@tobermore.co.uk
sales@tobermore.co.uk

tobermore.co.uk

v1.4

Riven Slabs



Stock

product	size (mm)	edge	colours available	in stock	no. per m ²	no. per pack	no. per pallet	weight kg per pack GB	weight kg per pack NI/ROI
Riven Slabs	600 x 600 x 40	Chamfered	Buff, Charcoal, Natural	YES	2.78	24	24	850	840
	450 x 450 x 35	Chamfered	Buff, Charcoal, Natural	YES	4.94	30	60	538	528
	400 x 400 x 40	Chamfered	Charcoal, Natural	YES	6.25	25	100	410	400

Natural



Charcoal



Buff

