

EXTERIO

VISAGE LED 3

The Visage LED 3 is a modern street lighting luminaire made from die cast aluminium. The luminaire can be supplied in a range of outputs and optional extras. It is IP66 rated and is made with a die-case aluminium body.

FEATURES

- IP66 construction
- High intensity die-cast aluminium body
- Quick access for easy maintenance
- Available with NEMA photocell
- Grey Housing as Standard
- IK08 Rated
- Rear or Bottom Post Entry



LED

IP66

SON/MH
EQUIVALENT

5 YEAR
WARRANTY

TECHNICAL DETAILS

Part Number	Description	Replaces	Weight (kg)	No. Per 10A Breaker	Inrush Current (A)	Circuit Watts	Board Lumens	Luminaire Lumens	L/cw
V13S-14-4K	14W LED Street Light	42W PL	4.2	50	18A 120µs	14W	2090	1880	134.4
V13S-28-4K	28W LED Street Light	70W SON	4.2	50	22A 120µs	28W	4181	3763	134.4
V13S-40-4K	40W LED Street Light	80W MBF	4.2	20	30A 160µs	40W	5973	5375	134.4
V13S-56-4K	56W LED Street Light	100W MH	4.2	20	25A 260µs	56W	8362	7526	134.4

KEY FEATURES



OPTIONS AND ACCESSORIES

N	NEMA Photocell
BK	Black Housing
27K	2700K Colour Temperature
3K	3000K Colour Temperature
5K	5000K Colour Temperature

PHOTOMETRIC AND DIMENSION

