


PROPOSED NEW EXTENSION ROOF WITH ATTIC TRUSSES
SCALE 1:100




PROPOSED NEW ROOF WITH ATTIC TRUSSES TO EXISTING PROPERTY
SCALE 1:100




PROPOSED GROUND FLOOR PLAN
SCALE 1:100




PROPOSED FIRST FLOOR PLAN
SCALE 1:100




PROPOSED LOFT FLOOR PLAN
SCALE 1:100

NOTE:
EXTENSIONS/EXISTING PROPERTY
WALL CONSTRUCTION – TO BE BRICKWORK AND SAND/CEMENT RENDER EXTERNALLY TO MATCH EXISTING PROPERTY.

ROOF CONSTRUCTION – MARLEY AND PLAIN CONCRETE TILES TO SIDE EXTENSION/EXISTING PROPERTY WITH FORTICRETE CENTURION LOW–PITCHED ROOF TILES TO FRONT PORCH. ALLOW FOR GRP/FELT/EPDM ROOF COVERING TO REAR EXTENSION.

FLOOR CONSTRUCTION – INTERNAL FLOORS TO GROUND FLOOR TO BE OF SUSPENDED TIMBER FLOOR CONSTRUCTION OR CONCRETE GROUNDBEARING CONSTRUCTION WITH FIRST FLOOR OF SUSPENDED TIMBER CONSTRUCTION. ROOF TO SIDE EXTENSION AND EXISTING PROPERTY TO BE OF ATTIC TRUSSES.

NOTE:
UNDER THE PARTY WALL ACT 1996 – NOTICE MUST BE SERVED ON ADJOINING OWNERS BY THE PROPERTY OWNER PRIOR TO STARTING ANY WORK NEAR PROPERTY BOUNDARIES. THIS NOTICE MUST BE SERVED IN ACCORDANCE WITH THE ACT. MORE INFORMATION IS AVAILABLE ONLINE.

CONTRACTOR HAS FULL RESPONSIBILITY FOR TEMPORARY WORKS INCLUDING SCAFFOLDING STRENGTH OR DESIGN AND MAINTAINING STABILITY FOR DURATION OF WORKS.

LINTELS– ALL LINTELS TO ACHIEVE 150mm END BEARING. ALL LINTELS TO HAVE A HORIZONTAL DAMP PROOF COURSE.

FIRE STRATEGY FOR ALL FLOORS: ALLOW FOR SAFE FIRE ROUTE FROM ALL FLOORS TO FINAL EXIT INCLUDING MAINS WIRED AND INTERLINKED WITH BATTERY BACK–UP SMOKE/FIRE ALARMS ON ALL FLOORS AND HALF HOUR FIRE RATED INTERNAL DOORS ON ALL FLOORS.
ALLOW FOR HALF HOUR FIRE DOORS ON FIRST, GROUND AND LOFT FLOORS TO ALLOW FOR A PROTECTED FIRE ROUTE.




PROPOSED REAR ELEVATION
SCALE 1:100




PROPOSED SIDE ELEVATION
SCALE 1:100

PROPOSED FRONT ELEVATION
SCALE 1:100

- MAINS WIRED WITH BATTERY BACK–UP SMOKE/FIRE ALARMS TO BE INTRODUCED ON ALL FLOORS WITHIN HALLWAY AREAS
- STEEL BEAMS INTRODUCED TO PROVIDE SUPPORT TO FLOORS/WALLS/ROOFS ABOVE NEW OPENINGS. STEEL BEAM SUPPORTS WITH INDEPENDENT FOUNDATIONS MAY BE REQUIRED FOR MAJOR OPENINGS.
- INDICATES WALLS/CHIMNEYS/ ROOF STRUCTURE/OUTBUILDING TO BE REMOVED AND REMAINING AREA MADE GOOD
- BLOCK–OFF EXISTING DOOR/WINDOW OPENINGS
- MP2 ANCON WINDPOSTS POSITIONED WITHIN CAVITY FIXED TO FOUNDATIONS OF NEW EXTENSION ROOF – OBTAIN DESIGN FROM ANCON. ALLOW FOR MIN. 4–6 WEEKS LEAD TIME FOR DESIGN AND SUPPLY FROM ANCON
- ASSUMED JOIST SPAN TO GROUND AND FIRST FLOORS – CONTRACTOR TO CONFIRM THROUGH DISCUSSIONS WITH BUILDING CONTROL.




PROPOSED CROSS–SECTION THROUGH EXTENSION SIDE WALLS
SCALE 1:100




PROPOSED SITE PLAN
SCALE 1:100

NOTE – THIS DRAWING IS FOR PLANNING PURPOSES ONLY – FURTHER DETAILED DRAWINGS WILL BE REQUIRED AS PART OF A BUILDING REGULATIONS APPLICATION.

NOTE – DO NOT SCALE OFF DRAWING. DIMENSIONS TO BE CONFIRMED ON SITE

ALL DIMENSIONS IN MM

NOTE – THIS DRAWING IS TO BE READ IN CONJUNCTION WITH DRAWING NO. S03 – WORK SPECIFICATION

| Revisions | | |
|---|---|---|
| | Date | Sept 2026 |

Planning Application for:
34 Asquith Fields, Batley
Extensions, Front Porch and New Roof
Drawing Title:
Proposed Plans and Elevations
Drawing No: S02
Rev C
Scale: As shown
Paper Size: A0