

		BRIDGE & STRUCTURE EXAMINATION REPORT Highways England Bridge Visual Examination							
ELR: HMF		Contract Mileage: 005m 00.00chs				Struc. Ref: 3			
Exam ID:	3452	No of Spans:	01	No of Spans Examined:		Exam Date	09/03/2026		
NR Route:	HRE			GUID:	3452				
Structure Name:	New Mill Road			Type:	BU	OS Ref:	SE155102		
Line Name:	Holmfirth - Brockholes								
Section A: To Be Completed By The Examining Organisation									
PARTS NOT EXAMINED (EXCLUDING FOUNDATIONS)									
10% Viewed - West Parapet - Reason - Vegetation 0% Viewed - East Parapet - Reason - Vegetation									
Item	Description	Location	Est. Cost £k +/- 20%	Priority Within	Quantity	Severity	Probability	Risk Score	Works Category
1	Remove dilapidated fencing and install appropriate fencing at all four corners and provide handrail on top of parapets	At top approaches and parapets	12	1yr	60 m	5	1	E5	Fencing Repair/Renewal
2	Rake and separation fracture open 5-6mm and repoint.	SW face rings/spandrel	2	2yrs	6 m	3	2	M6	Masonry Repointing
3	Replace missing height warning signage and clean existing	West elevation	1	6mths	1 unit	5	1	M5	Bridge Strike Ancillaries
4	Rake out bed joint and repoint. Ensure any vegetation is removed.	SW and NE wingwall	1	2yrs	6 m	2	3	E6	Masonry Repointing
5	Recase displaced coping stone at the top of the wingwall (above footpath).	SE wingwall	2	1yr	6 m	5	1	E5	Masonry Repairs
6	Rake out and repoint open diagonal step fracture open upto 10mm running through pilaster. Apply date tab to monitor movement	NW pilaster	1	1yr	2 m	3	2	M6	Masonry Repointing
7	Remove large tree growing behind wingwall and ecoplug due to bulging to the wingwall in this area	SE wingwall 4m from newel	3	2yrs	1 unit	4	2	M8	Vegetation Removal
8	Remove vegetation from behind the parapets to allow access for examination	Internal parapets	1	1yr	50 m2	2	4	E8	Vegetation Removal