

NOTES

Plant Schedule

Trees						
Species	Height	Girth	Specification	Density	Number	
Acer campestre	350-425cm	12-14cm	Europe (UK native); 3 x tr, hessian and wire wrapped root ball	Counted	18 -	
Alnus glutinosa	400 - 450cm	14-16cm	3x ; RB ; Large Feathered ; 7 breaks	Counted	4 -	
Betula pendula	350 -425cm	12-14cm	Heavy Standard; clear stem 175-200cm; 5 breaks	Counted	11 -	
Quercus robur	400-450cm	16-18cm	3 x tr, hessian and wire wrapped root ball	Counted	4 -	
Tilia cordata	400-450cm	16-18cm	3 x tr, hessian and wire wrapped root ball	Counted	15 -	
Tilia platyphyllos	350-425cm	12-14cm	Europe (UK native); Strong, well grown, pot full bushy plants	Counted	4 -	Total :56 -

Shrubs						
Species	Height	Pot Size	Specification	Density	Number	
Bergenia cordifolia	40-60cm	3L	Strong, well grown bushy plants	7/m²	397 -	
Choisya ternata	30-40cm	3L	Strong, well grown, pot full bushy plants	3/m²	55 -	
Elaeagnus ebbingei	45-60cm	5L	Strong, well grown bushy plants	3/m²	327 -	
Hebe albicans	30-45cm	3L	Strong, well grown, pot full bushy plants	5/m²	441 -	
Lavandula angustifolia 'Hidcote'	20-30cm	3L	Strong, well grown, pot full bushy plants	3/m²	101 -	
Spiraea japonica 'Little Princess'	30-40cm	5L	Strong, well grown bushy plants 7 breaks	2/m²	23 -	Total :1344 -

Hedge						
Species	Height	Pot Size	Specification	Density	Number	
Carpinus betulus	40-60cm	3L	Strong, well grown bushy plants	0.3Ctr Double Staggered at 0.3m offset	761 -	
Carpinus betulus	150-175cm	70-90L	Instant Hedging - 1m Trough	1/m	62 -	Total :823 -

Herbaceous						
Species	Specification	Pot Size	Density	Number		
Tiarella cordifolia	Full Pot	2L	5/m²	555 -		Total :555 -

Grasses						
Species	Specification	Pot Size	Density	Number		
Molinia caerulea 'Moorhexe'	Strong, well grown bushy plants	10L	5/m²	120 -		Total :120 -

Grass Areas						
Description	Seed Mix Name	Seed Mix Supplier	Area			
Amenity Grass:	E2 - Tough Turf	Barenbrug	2698.6808m²			
Swales:	EM8F Wild Flowers for Wetlands	Emorsgate	53.7069m²			
Species Rich Grass:	General Purpose, Classic Hay Meadow	Barenbrug	259.3584m²			
			Total :3011.7461m²			

- Existing Trees & Vegetation Retained
- Relocated Existing Memorial Tree
- Proposed Tree Planting
- Native Hedge Planting
- Instant Hedge Screen
- Ornamental Planting
- Species Rich Grass
- Amenity Grass
- SuDs Seed Mix
- Existing Grass Retained
[Subject to condition/temporary works]

REVISION | P06 | DATE | 27.08.26 | BY | GS | CHECKED | KP

Planting species updated to remove potentially harmful and thorny species.

REVISION | P05 | DATE | 27.08.26 | BY | GS | CHECKED | KP

Updated to Site Plan

REVISION | P04 | DATE | 25.06.26 | BY | KP | CHECKED | AB
Tree specification updated to include clear stems. Proposed trees relocated to avoid existing underground services.

REVISION | P03 | DATE | 04.06.26 | BY | KP | CHECKED | AB

Eastern boundary hedge specification updated to Instant Hedging troughs.

REVISION | P02 | DATE | 28.05.26 | BY | GS | CHECKED | KP

Species updated.

REVISION | P01 | DATE | 08.05.26 | BY | GS | CHECKED | KP

First Issue

CLIENT | Bowmer + Kirkland

PROJECT | Gomersal St Mary's Primary School

TITLE | Detailed Planting Plan

DWG No. | SRP1134-ONE-ZZ-XX-D-L-0203 | REV | P06

STATUS | PRELIMINARY

SCALE | 1:200 | @ A1 | DATE | 08.05.26 | DRN BY | GS



0 2 4 8
metres 1:200

