Appendix B – Design Details

Erection of fixed timber framed Pergola (Canopy Shelter) within existing rear terrace area, including associated hard and soft landscaping works at:

The Elephant and Castle PH, Hollowgate, Holmfirth HD9 2DG

To be Read in Conjunction with ADP Drawing No's (1357-01 to 1357-05 incl).





CUPRONOL Ultimate Garden Preservative Wood Stain Finish to Proposed Treated Timber Fixed Frame Pergola and Timber Planters Ref: 'GOLDEN OAK'
NEW 1100mm High Mild Steel Balustrade/ Guarding to Part Terrace Area. 80x80mm SHS Posts, 40x8mm Flat Bar Intermediate Rails, 20mm Diameter Infill Bars No Gaps Greater than 99mm. Primed and Black Gloss Paint Finish Throughout





MARSHALLS Weathered Yorkstone PC Paving Flags to Terrace (Lower Section)
Raised Rustic Timber Planters 3no. 1800w x 400w x 900h and 1no. 2200w 400d x 900h Fully Lined/ Soft Landscaping Scheme to Terrace/ Outside Seating Area.







Supplementary External Furniture (Balmoral Teak Square Tables, Armchairs and Benches TBC)
GRIPSURE 'Classic' Commercial Grade Non-Slip Softwood Decking (28x145mm) Smooth Face with 3no. Gripsure Non-Slip Strips. Safe Overall Average PTV Rating 85. Pressure Treated Low Maintenance and Weathers to an Attractive 'Silvery Grey' Gripsure 15 Year Warranty to Cover Non-Slip Performanc.
NB: To Cover Upper Terrace Access Ramp, Stairs and Area Under Pergola